

SEEDING SCHEDULE

LOCATION STATION	SEEDING CLASS 2	NITROGEN	PHOSPHOROUS	POTASSIUM	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING
IL 146 (FAP 885)	ACRE	LBS	LBS	LBS	TON	ACRE	POUND
NW QUAD							
STA. 227+07.00 TO STA. 227+81.50	0.05	4.5	4.5	4.5	0.1	0.05	10
NE QUAD							
STA. 229+02.50 TO STA. 231+59.00	0.15	13.5	13.5	13.5	0.3	0.15	30
SW QUAD							
STA. 225+02.00 TO STA. 227+52.00	0.1	9	9	9	0.2	0.1	20
SE QUAD							
STA. 228+74.00 TO STA. 230+53.00	0.1	9	9	9	0.2	0.1	20
TOTALS	0.4	36	36	36	0.8	0.4	80

GUARDRAIL SCHEDULE

LOCATION STATION	TRAFFIC BARRIER TERMINAL				SPBGR TYPE A (6 FOOT POSTS)	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKER TYPE A	BARRIER WALL MARKER TYPE B
	TYPE 1 SPECIAL TANGENT	TYPE 1 SPECIAL FLARED	TYPE 6	TYPE 6 SPECIAL				
IL 146 (FAP 885)	EACH	EACH	EACH	EACH	FOOT	EACH	EACH	EACH
NW QUAD								
STA. 227+19.33 TO STA. 227+87.28		1		1		1		
NE QUAD								
STA. 228+89.07 TO STA. 231+33.01	1		1		150	1	2	
SW QUAD								
STA. 225+24.76 TO STA. 227+66.90	1		1		150	1	2	
SE QUAD								
STA. 228+68.69 TO STA. 229+99.34	1		1		37.5	1	1	
NORTH								
SOUTH								
TOTALS	3	1	3	1	337.5	4	5	4

FILE NAME = c:\pwworkspace\kell\proj\80242339\78152-aha-cvr-1.scd_index.dgn

USER NAME = *USER*	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -
PLOT DATE = 10/17/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	11B-1	HARDIN	50	11
CONTRACT NO. 78152				
ILLINOIS FED. AID PROJECT				