

PAVEMENT MARKING SCHEDULE

LOCATION STATION	TEMPORARY PAVEMENT MARKING LINE 4"	PAINT PAVEMENT MARKING LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL
IL 146 (FAP 885)	FOOT	FOOT	SQ FT	SQ FT
STA. 224+41.00 TO STA. 232+75.00				
WHITE (2 LINES)		1668		556
YELLOW SOLID		834		278
YELLOW SKIP		334		111
STAGE 1				
STA. 224+48.50 TO STA. 232+35.00	827		383	
STA. 226+43.00 TO STA. 227+75.00	134			
STA. 228+95.00 TO STA. 230+32.00	161			
STA. 230+20.00 TO STA. 230+48.00	28			
STAGE 2				
STA. 225+15.00 TO STA. 231+69.00	690		243	
STA. 226+53.00 TO STA. 226+90.00	37			
TOTAL	1877	2836	626	945

EROSION CONTROL SCHEDULE

LOCATION STATION	PERIMETER EROSION BARRIER	TEMPORARY EROSION CONTROL BLANKET
IL 146 (FAP 885)	FOOT	SQ YD
NW QUAD		
STA. 227+07.00 TO STA. 227+81.50	81	
STA. 227+50.00 TO STA. 227+81.00		58
NE QUAD		
STA. 229+02.50 TO STA. 231+59.00	266	
STA. 229+02.50 TO STA. 231+00.00		620
SW QUAD		
STA. 225+02.00 TO STA. 227+52.00	252	
SE QUAD		
STA. 228+74.00 TO STA. 230+53.00	170	
STA. 229+25.00 TO STA. 229+76.00		163
TOTALS	769	841

FILE NAME = c:\pwworkspace\kell\proj\80242339\78152-111a-cvr-1.scd_index.dgn

USER NAME = \$USER\$	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
PLOT DATE = 10/17/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	11B-1	HARDIN	50	12
CONTRACT NO. 78152				
ILLINOIS FED. AID PROJECT				