

SUMMARY OF QUANTITIES

CODE NO.	ITEM	URBAN		100% FEDERAL		
		CONSTRUCTION TYPE CODE		0021		
		UNIT	TOTAL QUANTITY	LOCATION 1 IL 13/OLD IL 13	LOCATION 2 IL 13/GRANGER ST	LOCATION 3 IL 13/E POPLAR ST
67100100	MOBILIZATION	L SUM	1	0.3	0.3	0.3
80400100	ELECTRIC SERVICE INSTALLATION	EACH	3	1	1	1
81028760	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	FOOT	453	252	142	59
81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	2003	852	416	735
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	10	4	4	2
82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	EACH	3	1	1	1
83062735	LIGHT POLE, WEATHERING STEEL, 45 FT. M. H., TENON MOUNT - TWIN	EACH	5	2	2	1
83600357	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	5	2	2	1
83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	20	8	8	4
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	1	1		