

**SUMMARY OF QUANTITIES**

ITEM NO.	SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
						ROADWAY 0004	STRUCTURE 0011
1		20100500	TREE REMOVAL, ACRES	ACRE	0.03	0.03	
2	SP	20200100	EARTH EXCAVATION	CU YD	103	103	
3		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	84		84
4		20700220	POROUS GRANULAR EMBANKMENT	CU YD	260		260
5		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	242	242	
6		25000210	SEEDING, CLASS 2A	ACRE	0.06	0.06	
7		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6	6	
8		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6	6	
9		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6	6	
10		25100115	MULCH, METHOD 2	ACRE	0.12	0.12	
11		25100630	EROSION CONTROL BLANKET	SQ YD	252	252	
12	BDE	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	24	24	
13		28000400	PERIMETER EROSION BARRIER	FOOT	177	177	
14		28100109	STONE RIPRAP, CLASS A5	SQ YD	349		349
15		28200200	FILTER FABRIC	SQ YD	349		349
16	SP	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	216	216	
17		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	95	95	
18	BDE	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	108	108	
19	BDE	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	23	23	
20		42001300	PROTECTIVE COAT	SQ YD	32	32	
21	BDE	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	694	694	
22		44000100	PAVEMENT REMOVAL	SQ YD	242	242	
23		44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	127	127	
24		44000300	CURB REMOVAL	FOOT	125	125	
25		44000600	SIDEWALK REMOVAL	SQ FT	605	605	
26	SP	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
27		50300300	PROTECTIVE COAT	SQ YD	275		275
28		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	51710		51710
29	SI	50900105	ALUMINUM RAILING, TYPE L	FOOT	98		98
30		51500100	NAME PLATES	EACH	1		1
31		54003000	CONCRETE BOX CULVERTS	CU YD	305.2		305.2
32		60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	140	140	
33	SZ	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
34	SZ	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
35		67100100	MOBILIZATION	L SUM	1	1	
36	SI	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	320	320	
37	RSP, SZ	78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
38	SI	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
39	SP	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
40	RSP	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	

SP=SPECIAL PROVISION      RSP=RECURRING SPECIAL PROVISIONS      SI=SPECIALTY ITEM      BDE=BUREAU OF DESIGN AND ENVIRONMENT

FILE NAME = Y:\3045\3045q001.dgn	USER NAME = bdecrone	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>F.A.U. 6143 (BAZORE ST.) SUMMARY OF QUANTITIES</b>	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 1/8" = 1' / 1"	CHECKED -	REVISED -	6143			11-00693-00-DR	LA SALLE	20	3	
PLOT DATE = 3/27/2012	DATE -	REVISED -	SCALE: N/A			SHEET NO. 1 OF 1 SHEETS	STA. N/A	TO STA. N/A	CONTRACT NO. 87522	
							FED. ROAD DIST. NO. 7 (ILLINOIS) FED. AID PROJECT BRN-506R(016)			