* SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0004 CONSTR. CODE WASHINGTON TOWNSHIP	ROADWAY 0004 CONSTR. CODE CITY OF EAST PEORIA
44000100	PAVEMENT REMOVAL	SQ YD	13618	8321	5297
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1111	950	161
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	121		121
44000600	SIDEWALK REMOVAL	SQ FT	127		127
44200108	PAVEMENT PATCHING TY II, 9 INCH	SQ YD	217	129	88
44200112	PAVEMENT PATCHING TY III, 9 INCH	SQ YD	167	106	61
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2	
50105220	PIPE CULVERT REMOVAL	FOOT	1115	897	218
50800105	REINFORCEMENT BARS	POUND	5210	5210	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	370	370	
50901760	PIPE HANDRAIL	FOOT	32	32	
54003000	CONCRETE BOX CULVERTS	CU YD	49.4	49.4	
542A0226	PIPE CULVERTS, CLASS A, TYPE 1 21"	FOOT	138	138	
542A0247	PIPE CULVERTS, CLASS A, TYPE 1 42"	FOOT	180	180	
542D5476	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 21"	FOOT	176	176	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2	
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	2	2	
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	759	597	162
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	192	192	0
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	439	439	0

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0004 CONSTR. CODE WASHINGTON TOWNSHIP	ROADWAY 0004 CONSTR. CODE CITY OF EAST PEORIA
	550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	290	0	290
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	84	0	84
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	414	359	55
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	331	277	54
	550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	1118	504	614
	550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	549	0	549
	550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	34	0	34
	550A4100	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	74	74	0
	60100905	PIPE DRAINS 4"	FOOT	207	0	207
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	
	60255500	MANHOLES TO BE ADJUSTED	EACH	2		2
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4		4
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	10602	6449	4153
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	163	163	
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
	66600105	FURNISHING AND ERECTING ROW MARKERS	EACH	7	7	
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	6	4
	67100100	MOBILIZATION	L SUM	1	0.6	0.4
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.6	0.4
	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	0.6	0.4
	70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	0.6	0.4