

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)	
LOCATION	UNIT
CITY OF EAST PEORIA	
STA. 3385+97.47, 28.36' LT	6
STA. 3386+63.86, 27.61' LT	6
STA. 3401+41.81, 30.87' LT	6
SUBTOTAL	18
WASHINGTON TOWNSHIP	
STA. 3404+45.52, 40.00' LT	6
STA. 3406+32.16, 27.66' LT	12
STA. 3408+30.90, 33.54' RT	6
STA. 3408+59.76, 36.67' RT	6
STA. 3410+97.80, 29.46' LT	12
STA. 3411+90.62, 34.65' LT	12
STA. 3412+59.81, 35.42' LT	12
STA. 3412+82.72, 35.58' LT	12
STA. 3413+02.55, 35.55' LT	12
STA. 3416+11.29, 31.41' LT	6
SUBTOTAL	96
TOTAL	114

25100900 TURF REINFORCEMENT MAT	
LOCATION	SQ YD
WASHINGTON TOWNSHIP	
STA. 3405+75.14, 119.4' RT	32
TOTAL	32

28100107 STONE RIPRAP, CLASS A4	
LOCATION	SQ YD
WASHINGTON TOWNSHIP	
STA. 3412+94.91, 44.02' RT	95.3
TOTAL	95.3

44000100 PAVEMENT REMOVAL	
LOCATION	SQ YD
CITY OF EAST PEORIA	
BEGIN TO STA. 3401+50.55	42004.86
STA. 3401+50.55 TO STA. 3402+14.45	544.14
CITY OF EAST PEORIA (SOUTH)	
SPRING HAVEN DR	1286.88
CLORIA ST	871.18
BARBARA PARKWAY	1816.10
THOMAS COURT	1147.47
SUB TOTAL	5296.74
WASHINGTON TOWNSHIP	
STA. 3401+50.55 TO STA. 3402+14.45	857.70
WASHINGTON TOWNSHIP (NORTH)	
STA. 3402+14.45 TO END	68331.39
SCHOOL ST	2893.78
TEEL LN	1246.35
SPRING CREEK RD.	1558.31
SUB TOTAL	8320.84
TOTAL	13617.6

28000500 INLET AND PIPE PROTECTION			
LOCATION	EACH	LOCATION	EACH
CITY OF EAST PEORIA		STA. 3405+65.38, 33.53' LT	1
STA. 3381+08.88, 28.98' LT	1	STA. 3406+75.02, 20.47' RT	1
STA. 3381+34.12, 15.63' LT	1	STA. 3406+98.96, 30.45' RT	1
STA. 3381+41.12, 15.63' LT	1	STA. 3407+52.59, 29.97' RT	1
STA. 3381+34.14, 15.62' RT	1	STA. 3407+52.18, 15.62' LT	1
STA. 3384+01.14, 15.63' LT	1	STA. 3407+59.17, 15.62' RT	1
STA. 3384+08.14, 15.63' LT	1	STA. 3407+52.26, 33.34' LT	1
STA. 3384+01.13, 15.62' RT	1	STA. 3412+00.02, 34.91' LT	1
STA. 3386+68.99, 15.62' LT	1	STA. 3412+85.00, 49.91' LT	1
STA. 3386+68.99, 15.62' RT	1	STA. 3412+91.16, 48.81' LT	1
STA. 3386+68.99, 15.62' LT	1	STA. 3413+30.00, 15.62' LT	1
STA. 3387+30.05, 15.62' LT	1	STA. 3413+29.98, 15.62' RT	1
STA. 3389+19.48, 15.63' LT	1	STA. 3415+93.00, 15.63' LT	1
STA. 3389+26.48, 15.63' LT	1	STA. 3416+00.00, 15.62' LT	1
STA. 3389+19.49, 15.62' RT	1	STA. 3415+92.85, 15.71' RT	1
STA. 3392+19.22, 15.62' LT	1	STA. 3415+99.84, 15.62' RT	1
STA. 3392+26.31, 15.63' LT	1	STA. 3418+00.04, 15.63' LT	1
STA. 3392+26.31, 15.62' RT	1	STA. 3418+07.04, 15.63' LT	1
STA. 3394+29.31, 15.63' LT	1	STA. 3418+07.06, 15.62' RT	1
STA. 3394+36.31, 15.63' LT	1	STA. 3419+83.43, 38.36' LT	1
STA. 3394+29.31, 15.62' RT	1	STA. 3420+30.82, 38.65' LT	1
STA. 3396+39.32, 15.62' LT	1	STA. 3421+61.31, 15.62' LT	1
STA. 3396+46.32, 15.62' LT	1	STA. 3422+73.00, 15.63' RT	1
STA. 3396+39.31, 15.62' RT	1	STA. 3422+72.99, 15.64' LT	1
STA. 3398+49.33, 15.61' LT	1	STA. 3422+79.99, 15.64' LT	1
STA. 3398+56.33, 15.61' LT	1	STA. 3423+82.90, 15.64' LT	1
STA. 3398+49.32, 15.63' RT	1	STA. 3423+89.90, 15.64' LT	1
STA. 3399+90.81, 15.63' LT	1	STA. 3423+89.90, 15.64' LT	1
STA. 3400+15.90, 15.62' RT	1	STA. 3424+98.08, 15.64' LT	1
STA. 3400+38.70, 39.49' LT	1	STA. 3424+98.08, 15.64' LT	1
STA. 3400+39.37, 32.52' LT	1	STA. 3424+98.08, 15.64' LT	1
STA. 3400+63.87, 15.63' LT	1	STA. 3427+55.78, 15.64' LT	1
STA. 3400+70.87, 15.63' LT	1	STA. 3427+48.79, 15.62' RT	1
SUBTOTAL	32	STA. 3427+55.79, 15.62' RT	1
		STA. 3428+32.17, 20.92' RT	1
WASHINGTON TOWNSHIP		STA. 3429+70.00, 15.53' RT	1
STA. 3404+54.03, 15.63' LT	1	STA. 3429+69.99, 15.64' LT	1
STA. 3404+61.03, 15.63' LT	1	STA. 3431+85.00, 15.62' RT	1
STA. 3404+61.04, 15.62' RT	1	STA. 3432+59.92, 17.34' LT	1
STA. 3405+63.38, 15.62' RT	1	STA. 3432+50.52, 16.15' RT	1
STA. 3405+70.38, 15.63' RT	1	STA. 3434+00.42, 26.10' LT	1
STA. 3405+63.38, 15.63' LT	1	SUBTOTAL	48
STA. 3405+70.38, 15.62' LT	1	TOTAL	80

28000250 TEMPORARY EROSION CONTROL SEEDING	
LOCATION	POUND
ENTIRE PROJECT (20 APPLICATIONS)	1815
TOTAL	1815

28200200 FILTER FABRIC	
LOCATION	SQ YD
WASHINGTON TOWNSHIP	
STA. 3412+94.91, 44.02' RT	95.3
TOTAL	95.3

28000305 TEMPORARY DITCH CHECKS	
LOCATION	FEET
WASHINGTON TOWNSHIP	
STA. 3427+25 TO STA. 3386+00, LT	48
STA. 3433+55.15 TO STA. 3434+37.35 R2, RT	36
TOTAL	84

42400800 DETECTABLE WARNINGS	
LOCATION	SQ FT
CITY OF EAST PEORIA	
STA. 3399+49.22, 29.27' RT	10
STA. 3399+87.42, 29.35' RT	10
WASHINGTON TOWNSHIP	
STA. 3406+81.68, 17.59' RT	10
STA. 3407+85.67, 17.59' RT	51
TOTAL	81.0

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)	
LOCATION	UNIT
WASHINGTON TOWNSHIP	
STA. 3406+23.25, 19.18' LT	24
STA. 3406+33.31, 22.57' LT	20
STA. 3414+78.65, 50.24' LT	24
STA. 3421+57.26, 33.20' LT	24
TOTAL	92

28000400 PERIMETER EROSION BARRIER	
LOCATION	FOOT
CITY OF EAST PEORIA	
STA. 3381+26.88, 17.43' RT TO STA. 3402+22.99, 42.66' RT	2142.5
STA. 3386+67.98, 41.49' LT TO STA. 3390+99.95, 40.96' LT	432.3
STA. 3392+22.30, 27.65' LT TO STA. 3393+50.00, 27.86' LT	127.7
SUBTOTAL	2702.5
WASHINGTON TOWNSHIP	
STA. 3402+46.99, 42.66' RT TO STA. 3434+37.35 R2, 17.34' RT	3835.1
STA. 3405+92.20, 30.09' LT TO STA. 3434+37.41 R2, 18.31' LT	3056.1
STA. 3426+45.76, 111.29' RT TO STA. 3427+92.94, 43.03' RT	174.2
STA. 3426+52.63, 116.72' RT TO STA. 3428+09.55, 45.54' RT	183.1
SUBTOTAL	7248.5
TOTAL	9951.0

42400100 PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	
LOCATION	SQ FT
CITY OF EAST PEORIA	
STA. 3399+45.22, 29.27' RT	88.0
THOMAS ST EAST	
STA. 3399+84.59, 29.35' RT	88.4
THOMAS ST WEST	
WASHINGTON TOWNSHIP	
STA. 3406+81.68, 17.59' RT	129.6
SCHOOL ST EAST	
STA. 3407+85.67, 17.59' RT	204.3
SCHOOL ST WEST	
TOTAL	510.2

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	
LOCATION	FOOT
CITY OF EAST PEORIA	
STA. 3381+27.62 TO STA. 3434+06.9	4088.66
STA. 3401+50.57 TO STA. 3402+14.45	63.88
SUBTOTAL	4152.54
WASHINGTON TOWNSHIP	
STA. 3401+50.57 TO STA. 3402+14.45	63.88
STA. 3402+14.45 TO STA. 3434+06.9	6384.90
SUBTOTAL	6448.78
TOTAL	10602.0

20100500 TREE REMOVAL (ACRES)	
LOCATION	ACRES
WASHINGTON TOWNSHIP	
STA. 3408+19.28 TO STA. 3410+01.11	0.04
STA. 3412+54.52 TO STA. 3413+50.11	0.06
STA. 3415+70.71 TO STA. 3416+71.21	0.08
STA. 3425+41.25 TO STA. 3428+72.55	0.33
TOTAL	0.51

44000600 SIDEWALK REMOVAL	
LOCATION	SQ FT
CITY OF EAST PEORIA	
STA. 3399+49.40, 31.59' RT	63.6
THOMAS ST EAST	
STA. 3399+89.01, 32.43' RT	63.36
THOMAS ST WEST	
TOTAL	127.0

21301052 EXPLORATION TRENCH 52" DEPTH	
LOCATION	FOOT
WASHINGTON TOWNSHIP	
STA. 3415+61.77, 50.94' TO STA. 3416+36.77, 50.94' LT	75
TOTAL	75

25000775 SELECTIVE MOWING STAKES	
LOCATION	EACH
WASHINGTON TOWNSHIP	
STA. 3427+11.45, 142.00' RT	1
STA. 3427+86.00, 129.71' RT	1
STA. 3428+66.55, 76.28' RT	1
TOTAL	3

44000500 COMBINATION CURB AND GUTTER REMOVAL	
LOCATION	FOOT
CITY OF EAST PEORIA	
STA. 3385+87, 38' TO STA. 3386+00, 13' LT	47.44
(AROUND RADIUS OF SPRING HAVEN, WEST)	
STA. 3386+68, 38' TO STA. 3386+64, 12.6' LT	43.35
(AROUND RADIUS OF SPRING HAVEN, EAST)	
STA. 3399+54.3, 34.5' TO STA. 3399+55, 50' R	15.50
STA. 3399+84, 35' TO STA. 3399+84, 50' RT	14.50
TOTAL	120.79

20054400 ROCK FILL	
LOCATION	CU YD
CITY OF EAST PEORIA	
WASHINGTON TOWNSHIP	
STA. 3414+50 TO 3415+50 (1.5' DEEP X 32' WIDE)	177.78
STA. 3431+50 TO 3433+40 (1.5' DEEP X 32' WIDE)	337.78
SUBTOTAL	515.56
TOTAL	515.56

25100630 EROSION CONTROL BLANKET	
LOCATION	SQ YD
WASHINGTON TOWNSHIP	
STA. 3426+38.66 TO STA. 3429+17.25, RT	155.78
STA. 3426+67.01 TO STA. 3429+12.27, RT	1375.34
TOTAL	1531.13

21001000 GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	
LOCATION	SQ YD
CITY OF EAST PEORIA	
WASHINGTON TOWNSHIP	
STA. 3414+50 TO 3415+50 (32' WIDE)	355.56
STA. 3431+50 TO 3433+40 (32' WIDE)	675.56
SUBTOTAL	1031.12
TOTAL	1031.12

20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	
LOCATION	CU YD
CITY OF EAST PEORIA	
WASHINGTON TOWNSHIP	
STA. 3414+50 TO 3415+50 (2' DEEP X 32' WIDE)	237.04
STA. 3421+15 TO 3423+15 (3' DEEP X 32' WIDE)	711.11
STA. 3431+50 TO 3433+40 (2' DEEP X 32' WIDE)	450.37
SUBTOTAL	1398.52
TOTAL	2109.63

25100635 HEAVY DUTY EROSION CONTROL BLANKET	
LOCATION	SQ YD
WASHINGTON TOWNSHIP	
STA. 3426+38.66 TO STA. 3429+12.27, RT	1331.13
TOTAL	1331.13

LOCATION	EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) CU YD	EMBANKMENT CU YD	EARTH WORK BALANCE WASTE (+) OR CU YD
CITY OF EAST PEORIA (STA. 3381+50.00 TO STA. 3401+50.00)				
CENTENNIAL DRIVE, STAGE 2	1220.78	915.58	359.00	556.58
TOPSOIL EXCAVATION, STAGE 2			435.48	-435.48
CITY OF EAST PEORIA TOTAL STAGE 2	1220.78		801.45	121.10
CENTENNIAL DRIVE, STAGE 3	1379.61	1034.71	801.45	233.26
TOPSOIL EXCAVATION, STAGE 3			695.99	-695.99
CITY OF EAST PEORIA TOTAL STAGE 3	1379.61			-462.73
WASHINGTON TOWNSHIP (STA. 3401+50.00 TO STA. 3434+50.00)				
CENTENNIAL DRIVE, STAGE 2	2169.75	1627.31	1901.92	-274.60
UNDERCUT, STAGE 2			355.56	-355.56
TOPSOIL EXCAVATION, STAGE 2			1095.53	-1095.53
WASHINGTON TOWNSHIP TOTAL STAGE 2	2169.75			-1725.69
CENTENNIAL DRIVE, STAGE 3	3890.87	2918.15	2047.46	870.69
UNDERCUT, STAGE 3			355.56	-355.56
TOPSOIL EXCAVATION, STAGE 3			1786.32	-1786.32
WASHINGTON TOWNSHIP TOTAL STAGE 3	3890.87			