

ROADWAY SCHEDULE								
LOCATION	AGGREGATE BASE COURSE, TYPE A, 12"	BITUMINOUS MATERIALS (PRIME COAT)	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMPS	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, NS0	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, NS0	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N 50
	35101100	40600200	40600215	40600982	40600990	40603080	40603230	40603535
	SO YD	TON	TON	SO YD	SO YD	TON	TON	TON
CITY OF EAST PEORIA								
STA. 3381+27.62 TO STA. 3401+50.55	7679.59	1.99	1.29			1881.72	736.32	654.51
STA. 3338+17.63 TO STA. 3338+27.63				29.59	17.30			3.31
STA. 3386+31.16, 13' LT TO STA. 3386+31.16, 49.74' LT				91.26	20.00			10.22
STA. 3391+86.41, 25.97' LT TO STA. 3391+86.41, 45.96' LT				96.80	20.00			10.84
STA. 3399+69.34, 39.93' RT TO STA. 3399+69.34, 49.93' RT				30.95	17.30			3.47
STA. 3399+97.32, 35.68' LT TO STA. 3399+87.32, 35.32' LT				20.13	15.00			2.25
STA. 3400+22.53, 35.68' LT TO STA. 3400+22.53, 35.68' LT				100.98	15.00			11.31
STA. 3401+50.55 TO STA. 3402+14.45, RT	103.58	0.04	0.02			35.42	13.86	12.32
HALF PAVEMENT WIDTH - JURISDICTION								
SPRING HAVEN DRIVE	147.44	0.05	0.03			43.60	17.06	15.17
GLORIA STREET	46.08	0.02	0.01			18.62	7.29	6.48
THOMAS COURT	112.04	0.04	0.02			36.35	14.22	12.64
BARBARA PARKWAY	172.84	0.05	0.03			50.26	19.67	17.48
		ON AGG	2.18	1.41				
		FOG COAT BTWN LIFTS	1.41	X2				
COEP SUBTOTAL	8261.57	3.59	2.82	369.70	104.60	2065.96	808.42	760.00
WASHINGTON TOWNSHIP								
STA. 3401+50.55 TO STA. 3402+14.45, LT	139.02	0.03	0.02			24.00	9.39	8.35
HALF PAVEMENT WIDTH - JURISDICTION								
STA. 3402+14.45 TO STA. 3434+25.09	12191.04	3.15	2.04			0.00	1168.95	1039.08
SCHOOL STREET	345.77	0.11	0.07			0.00	39.90	35.47
STA. 11+51.57 TO STA. 11+31.57 RT				64.11	17.30			7.18
TEEL LANE	126.00	0.04	0.03			38.97	15.25	13.56
STA. 3420+08.31, 45.49' LT TO STA. 3420+08.31, 55.48' LT				23.88	15.00			2.67
SPRING CREEK ROAD	120.22	0.04	0.03			36.77	14.39	12.79
STA. 3433+53.45, 45.90' LT TO STA. 3433+53.45, 55.88' LT				23.54	17.30			2.64
STA. 3434+25.31 TO STA. 3434+57 R 2		ON AGG	3.37	2.18	56.30	17.30		6.31
		FOG COAT BTWN LIFTS	2.18	X2				
WASH TOWN SUBTOTAL	12922.05	5.55	4.36	167.83	66.90	3189.06	1247.88	1128.03
TOTAL	21183.63	9.1	7.18	537.53	171.50	5255.02	2056.30	1888.04

50105220 PIPE CULVERT REMOVAL	
CITY OF EAST PEORIA	FOOT
STA. 3385+80.24, 24.27' LT TO STA. 3386+95.44, 23.63' LT	115.2
STA. 3391+33.60, 22.16' LT TO STA. 3392+10.84, 15.37' LT	77.55
STA. 3399+98.07, 18.32' LT TO STA. 3400+50.24, 17.55' LT	25.18
SUBTOTAL 217.94	
WASHINGTON TOWNSHIP	
STA. 3402+20.93, 21.72' LT TO STA. 3402+46.20, 21.22' LT	25.27
STA. 3403+66.36, 16.29' LT TO STA. 3403+90.18, 15.85' LT	23.83
STA. 3404+09.62, 16.07' LT TO STA. 3404+33.48, 16.39' LT	23.85
STA. 3405+66.52, 16.78' LT TO STA. 3405+96.87, 17.31' LT	30.38
STA. 3406+26.84, 15.57' LT TO STA. 3406+10.53, 17.38' RT	37.09
STA. 3405+82.12, 42.67' RT TO STA. 3406+10.53, 17.38' RT	38.11
STA. 3411+55.20, 19.75' RT TO STA. 3411+79.08, 21.09' RT	23.92
STA. 3412+03.26, 15.47' LT TO STA. 3412+23.29, 15.90' LT	20.04
STA. 3412+94.92, 16.31' LT TO STA. 3412+97.37, 44.33' RT	60.69
STA. 3413+63.45, 14.95' LT TO STA. 3414+11.48, 13.79' LT	48.04
STA. 3415+14.43, 17.72' RT TO STA. 3415+39.04, 17.85' RT	24.6
STA. 3416+09.34, 30.15' LT TO STA. 3416+25.68, 56.73' RT	88.77
STA. 3419+79.67, 17.15' RT TO STA. 3420+04.03, 17.04' RT	24.37
STA. 3420+46.52, 15.97' LT TO STA. 3420+70.86, 16.24' LT	24.34
STA. 3421+65.96, 14.97' LT TO STA. 3421+90.29, 14.56' LT	24.34
STA. 3423+17.41, 14.76' LT TO STA. 3423+76.75, 16.10' LT	59.36
STA. 3424+57.28, 20.20' RT TO STA. 3424+81.84, 19.78' RT	24.57
STA. 3426+43.26, 21.01' LT TO STA. 3426+67.35, 21.40' LT	24.12
STA. 3427+16.90, 20.59' LT TO STA. 3427+41.01, 21.75' LT	24.14
STA. 3432+60.42, 17.68' LT TO STA. 3434+03.13, 24.29' LT	142.87
STA. 3432+50.92, 15.80' RT TO STA. 3433+55.13, 20.39' RT	104.31
SUBTOTAL 897.03	
TOTAL 1114.97	

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"	
LOCATION	FOOT
EAST PEORIA	
STA. 3381+8.2 TO STA. 3401+82.39	4148.4
SUBTOTAL 4148.4	
WASHINGTON TOWNSHIP	
STA. 3401+82.39 TO STA. 3434+45.3	6525.8
11+31.6 TO STA. 12+03.5 (SCHOOL ST)	71.9
SUBTOTAL 6597.7	
TOTAL 10746.1	

70300250 TEMPORARY PAVEMENT MARKING - LINE 8"	
LOCATION	FOOT
WASHINGTON TOWNSHIP	
STA. 12+12.3 (SCHOOL STREET)	140.0
TOTAL 140.0	

70300250 TEMPORARY PAVEMENT MARKING - LINE 8"	
LOCATION	FOOT
WASHINGTON TOWNSHIP	
STA. 12+12.3 (SCHOOL STREET)	140.0
TOTAL 140.0	

78200410 GUARDRAIL MARKERS, TYPE A	
LOCATION	EACH
WASHINGTON TOWNSHIP	
STA. 3426+35 TO STA. 3424+47.50	3
TOTAL 3	

78300100 PAVEMENT MARKING REMOVAL	
LOCATION	SO FT
CITY OF EAST PEORIA	
STA. 3380+88.55, 25.72' LT TO STA. 3381+23.72, 11.24' LT	
8" WHITE	26.1
12" WHITE	5.4
STA. 3381+07.38, 20.31' RT TO STA. 3381+27.34, 10.16' RT	
8" WHITE	19.0
12" WHITE	6.0
TOTAL 56.6	

78201000 TERMINAL MARKER - DIRECT APPLIED	
LOCATION	EACH
WASHINGTON TOWNSHIP	
STA. 3425+85, RT	1
STA. 3424+37.5, RT	1
TOTAL 2	

50800105 REINFORCEMENT BARS	
LOCATION	POUND
WASHINGTON TOWNSHIP	
CULVERT EXTENSION	5210
TOTAL 5210	

63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	
LOCATION	FOOT
WASHINGTON TOWNSHIP	
STA. 3426+35 TO STA. 3424+47.50	162.5
TOTAL 162.5	

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	
LOCATION	EACH
WASHINGTON TOWNSHIP	
STA. 3425+85 TO STA. 3426+35, RT	1
STA. 3424+97.5 TO STA. 3424+37.5, R	1
TOTAL 2	

50800205 REINFORCEMENT BARS, EPOXY COATED	
LOCATION	POUND
WASHINGTON TOWNSHIP	
CULVERT EXTENSION	370
TOTAL 370	

67100100 MOBILIZATION	
LOCATION	L SUM
ENTIRE PROJECT	
	1
TOTAL 1	

54003000 CONCRETE BOX CULVERT	
LOCATION	CU YD
WASHINGTON TOWNSHIP	
CULVERT EXTENSION	49.4
TOTAL 49.4	

78001140 PAINT, PAVEMENT MARKING - LINE 8"	
LOCATION	FOOT
WASHINGTON TOWNSHIP	
STA. 12+12.3 (SCHOOL STREET)	140.0
TOTAL 140.0	

A2001228 TREE, ACER RUBRUM RED SUNSET (RED SUNSET RED MAPLE), 4" CALIPER, BALLED AND BURLAPPED	
LOCATION	EACH
WASHINGTON TOWNSHIP	
STA. 3427+19.80, 111.22' RT	1
STA. 3427+92.29, 101.79' RT	1
STA. 3428+60.57, 41.43' RT	1
TOTAL 3	

X2810210 STON RIPRAP, CLASS A5 (SPECIAL)	
LOCATION	TONS
WASHINGTON TOWNSHIP	
STA. 3426+49.07 TO STA. 3428+09.83	
RIFFLE #1	56.00
RIFFLE #2	75.00
RIFFLE #3	59.00
TOTAL 190.00	

50901760 PIPE HANDRAIL	
LOCATION	FOOT
WASHINGTON TOWNSHIP	
STA. 3416+01.87, 41.76' LT	32
DROP BOX	
TOTAL 32	

67000500 ENGINEERS FIELD OFFICE, TYPE B	
LOCATION	CAL MO
ENTIRE PROJECT	
	10
TOTAL 10	

78001110 PAINT, PAVEMENT MARKING - LINE 4"	
LOCATION	FOOT
EAST PEORIA	
STA. 3381+8.2 TO STA. 3401+82.39	4148.4
SUBTOTAL 4148.4	
WASHINGTON TOWNSHIP	
STA. 3401+82.39 TO STA. 3434+45.3	6525.8
11+31.6 TO STA. 12+03.5 (SCHOOL ST)	71.9
SUBTOTAL 6597.7	
TOTAL 10746.1	

78001180 PAINT, PAVEMENT MARKING - LINE 24"	
LOCATION	FOOT
WASHINGTON TOWNSHIP	
STA. 12+04.5 RT (SCHOOL STREET)	25.7
TOTAL 25.7	

D2C01736 EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 3' HEIGHT, CONTAINER	
LOCATION	EACH
WASHINGTON TOWNSHIP	
STA. 3426+51.56, 44.58' RT	1
STA. 3426+70.79, 31.95' RT	1
STA. 3426+97.70, 120.98' RT	1
STA. 3427+47.57, 104.26 RT	1
STA. 3427+65.13, 115.85' RT	1
STA. 3428+19.12, 93.74' RT	1
STA. 3428+36.73, 83.55' RT	1
STA. 3428+40.94, 58.63' RT	1
STA. 3428+87.35, 33.69' RT	1
TOTAL 9	

X6029000 JUNCTION BOX	
LOCATION	L SUM
WASHINGTON TOWNSHIP	
STA. 3405+88.61	1
TOTAL 1	

X0322869 REMOVE TIMBER RETAINING WALL	
LOCATION	L SUM
WASHINGTON TOWNSHIP	
STA. 3414+94.02, 18.40' LT	1

XX008748 COARSE AGGREGATE FILL	
LOCATION	TONS
CITY OF EAST PEORIA	
SUBTOTAL	
WASHINGTON TOWNSHIP	
STA. 3414+50 TO 3415+50 (0.5' DEEP X 32' WIDE)	118.52
STA. 3431+50 TO 3433+40 (0.5' DEEP X 32' WIDE)	225.18
SUBTOTAL 343.70	
TOTAL 343.70	