PIPE SCHEDULE

PIPE NO.	U/S STR-D/S STR	U/S INV.	D/D INV.	SLOPE (Percent)	TRENCH BACKFILL (CY) 20800150	PAVEMENT PATCHING TY II, 9IN 44200108	PAVEMENT PATCHING TY III, 9IN 44200112	REMARKS	STORM SEWER CLASS A, TYPE 1 12" 550A0050	15" 550A0070	24" 550A0120	36" 550A0160	24" ERS 550A4100	STORM SEWER CLASS A, TYPE 2 12" 550A0340	15" 550A0360	18" 550A0380	24" 550A0410	30" 550A0430	36" 550A0450	STORM SEWER TYPE 2, WATER MAIN QUALITY 12" Z0056668	18" Z0056670	30" Z0056675	PIPE DRAINS 4" 60100905	PIPE CULVERT CLASS A, TYPE 1 21" 542A0226	42" 542A0247	PIPE CULVERT CLASS D, TYPE 1 21" ERS 542D5476
CITY OF EAST PEORIA																										
A	2-1	711.5	711.3	1.4				REMOVE EXISTING 30" PIPE REPLACE WITH											10.5							
B	3-2	711.8	711.6	0.9															23.6							
C	4-3	712.1	711.9	0.6	7.1		19.3					27.6														
D	6-4	713.7	712.3	0.6	56.3	0.0						262.0														
E	5-6	716.1	715.8	1.1	1.8	12.5			28.0																	
F	7-6	717.5	714.3	1.2	82.5	0.0																263.9				
G	8-7	720.0	719.7	1.0	4.5	13.4									28.0											
H	9-8	721.2	720.4	1.4	7.8	0.0			58.1																	
I	EX-9	722.70	722.6		0.1	0.0			20.0																	
J	10-7	721.6	717.6	1.6	99.9	0.0												246.5								
K	11-10	724.1	723.2	3.2	4.1	12.5								28.0												
L	12-10	726.9	721.7	1.7	95.3	0.0												302.8								
M	13-12	728.9	728.5	1.4	3.4	12.5								28.0												
N	14-13	EX	730.4		1.1	0.0																	79.0			
O	15-12	730.9	727.5	1.7	51.5	0.0											199.5									
P	17-15	732.8	732.0	2.9	3.9	12.5			27.8																	
Q	16-17	EX	733.6		1.6	0.0																	28.0			
R	18-15	733.6	731.0	1.2	63.2	0.0											207.0									
S	19-18	735.7	734.8	3.4	4.0	12.5								27.8												
T	20-18	736.4	733.8	1.3	56.2	0.0											207.0									
U	21-20	737.9	737.5	1.2	3.5	12.5			27.6																	
V	22-20	740.4	737.0	2.0	32.8	0.0															162.6					
W	23-22	741.4	741.0	1.1	3.7		17.3													37.1						
X	25-22	741.3	740.5	1.6	12.8		24.6									53.5										
Y	24-25	742.0	741.8	0.7	0.0	0.0									27.4											
Z	26-25	EX	741.9		4.3	0.0																	100.1			
			SUBTOTAL		601.4	88.5	61.2		161.5	0.0	0.0	289.6	0.0	83.8	55.4	53.5	613.5	549.3	34.1	37.1	162.6	263.9	207.1	0.0	0.0	
WASHINGTON TOWNSHIP																										
AA	27-28	744.7	744.4	1.1	2.9	13.4				28.0																
AB	28-29	744.3	742.6	1.7	19.8	0.0									98.8											
AC	30-31	746.5	744.1	15.4	0.0	0.0				15.4																
AD	31-29	743.3	742.4	3.1	5.6		15.9										27.8									
AE	29-32	742.5	742.2	1.9	6.6	0.0											16.8									
AF	33-32	743.3	741.4	2.3	0.0	0.0											83.2									
AG	34-33	743.6	743.4	1.0	6.8	0.0											23.1									
AH	35-34	744.2	743.7	1.1	4.4	0.0					50.1															
AI	36-35	745.0	744.3	1.7	5.0		22.6				42.1															
AJ						0.0																				
AK	37-36	746.9	746.1	5.2	0.0	0.0				15.0																
AL	40-39	745.2	744.9	1.0	0.0	0.0			33.1																	
AM	41-40	749.0	748.7	1.1	2.2	12.5			27.8																	
AN	43-44	743.3	743.0	1.1	0.0	0.0											25.5									
AO	42-43	744.2	743.9	1.1	9.5	14.2										27.6										
AP	45-42	748.3	744.5	1.8	44.1	0.0									204.3											
AQ	46-45	748.9	748.4	2.0	2.5	13.4				28.0																
AR	47-46	752.8	749.4	1.9	6.0	0.0			175.9																	
AS	48-47	753.2	752.4	1.9	3.0	0.0			46.4																	
AT	49-50	752.1	750.3	1.6	2.5	0.0			108.7																	
AU	50-51	749.8	748.9	3.2	5.3	13.4									28.0											
AV	51-54	748.6	746.4	1.0	60.2	0.0										221.7										
AW	52-53	748.9	747.4	1.5	14.6	0.0				105.1																
AX	53-54	746.9	746.4	1.6	6.1	14.2										27.8										
AY	54-55	745.6	744.0	0.7	77.8	0.0											247.3									
AZ	56-55	745.9	744.7	4.2	4.3	13.4									27.8											
BA	55-57	743.3	742.4	1.1	34.4	0.0											80.5									
BB	58-57	749.2	745.5	2.7	3.1	0.0					135.0															
BC	59-58	749.8	749.5	1.1	1.9	12.5			27.8																	
BD	60-58	757.4	749.3	3.8	18.9	0.0					212.0															
BE	61-60	758.9	758.5	1.6	1.6	12.5			27.8																	
BF	62-61	762.1	759.0	4.2	1.1	0.0							74.0													
BG	63-60	763.0	758.4	7.2	1.1	0.0			64.5																	
BH																										
BI	65-32	744.0	741.4	3.8	17.6		23.1																	68.9		
BJ	66-32	744.0	741.4	3.8	17.6		23.1																	68.9		
BK	32-67	741.3	739.6	1.9	0.0	0.0																				88.1
BL	32-68	741.3	739.6	1.9	0.0	0.0																				88.1
BM	69-74	751.0	750.0	1.2	0.0	0.0			85.3																	
BN	70-72	747.3	744.9	3.0	38.5		20.9																		80.1	
						0.0																				
BP	44-EX	741.4	730.5	11.0	94.6	9.9																			99.4	
			SUBTOTAL		519.6	129.3	105.7		597.3	191.5	439.2	0.0	74.0	0.0	358.9	277.1	604.2	0.0	0.0	0.0	0.0	0.0	0.0	137.8	179.5	176.2
			TOTAL		1121.0	217	166.9		758.8	191.5	439.2	289.6	74.0	83.8	414.3	330.6	1117.7	549.3	34.1	37.1	162.6	263.9	207.1	137.8	179.5	176.2

FILE NAME = s:\237\2089\237289006\CentennialDrivePhaseVPh1\CADD\CADD Sheets\D489492-sht-drainage	USER NAME = wllewis	DESIGNED - RJA	REVISED -
MAURER-STUTZ ENGINEERS SURVEYORS	PLOT SCALE = 40.0000 ' / IN.	DRAWN - WLL	REVISED -
	PLOT DATE = 11/16/2012	CHECKED - RJA	REVISED -
		DATE -	REVISED -

CITY OF EAST PEORIA
WASHINGTON TOWNSHIP

CENTENNIAL DRIVE – PHASE V (GRANGE RD TO SPRING CREEK RD)
DRAINAGE SUMMARY

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6745	07-00069-00-WR	TAZEWELL	98	11

CONTRACT NO. 89492

ILLINOIS FED. AID PROJECT