



GENERAL NOTES:

1. Temporary Drainage - This work consists of furnishing and installing a 3 (75) PVC pipe in the proposed inlet to facilitate drainage off the pavement prior to the placement of bituminous surface course.
2. Adequate pavement drainage shall be maintained during all phases of construction.
3. The PVC pipe is to be filled with mortar prior to surface course placement.
4. This detail applies to all inlet types.

All dimensions are in inches (millimeters) unless otherwise noted.

01-01-97	RENUM. B-4.11, NEW REVISION BOX	T.P.				STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TEMPORARY INLET DRAINAGE TREATMENT	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
12-01-98	CORRECT GENERAL NOTE	J.A.							6745	07-00069-00-WR	TAZEWELL	98	66
10-16-06	REVISED TO 2007 SPEC.	M.A.											
							NOT TO SCALE	CADD STD. 602401-04		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			