

CODE NO.	20200100	20300100	20400800
	EARTH EXCAVATION	CHANNEL EXCAVATION	FURNISHED EXCAVATION
	CU YD	CU YD	CU YD
LOCATION			
STA. 119+00 TO 125+62	77	333	1205
TOTAL	77	333	1205

CODE NO.	63100045
	TRAFFIC BARRIER TERMINAL TYPE 2
	EACH
LOCATION	
LT. STA. 120+98.00 (DRIVEWAY)	1
TOTAL	1

CODE NO.	542A1909
	PIPE CULVERTS, CLASS A, TYPE 3 24"
	FOOT
LOCATION	
STA. 123+22.57, 45.0' RT. TO STA. 123+96.62, 56.9' RT.	75
TOTAL	75

CODE NO.	Z0001002
	GUARDRAIL AGGREGATE EROSION CONTROL
	TON
LOCATION	
RT. STA. 119+00 TO RT. STA. 121+51	41
RT. STA. 122+89 TO STA. 1+35.35 (SOB)	22
STA. 1+35.35 (SOB) TO RT. STA. 125+62	51
LT. STA. 119+00 TO LT. STA. 121+70	55
LT. STA. 123+09 TO LT. STA. 125+62	41
TOTAL	210

CODE NO.	X2501000	28000250	28000400
	SEEDING CLASS 2 (SPECIAL)	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER
	ACRE	POUND	FOOT
LOCATION			
RT. STA. 119+00 TO 121+51	0.2	20.0	285
LT. STA. 119+00 TO 120+89	0.1	10.0	192
LT. STA. 121+89 TO 121+72	0.1	10.0	112
RT. STA. 122+89 TO 1+35.35 (SOB)	0.1	10.0	150
STA. 1+35.35 (SOB) TO RT. 125+62	0.1	10.0	256
LT. STA. 122+09 TO 125+62	0.1	10.0	267
TOTAL	0.7	70.0	1262

CODE NO.	63200310
	GUARDRAIL REMOVAL
	FOOT
LOCATION	
LT. STA. 121+30.43 TO LT. STA. 121+71.43	41
LT. STA. 123+09.34 TO LT. STA. 123+50.34	41
RT. STA. 120+96.99 TO RT. STA. 121+50.99	54
RT. STA. 122+89.04 TO RT. STA. 123+15.91	27
TOTAL	163

CODE NO.	48203100
	HOT-MIX ASPHALT SHOULDERS, (6")
	TON
LOCATION	
RT. STA. 119+00 TO RT. STA. 121+51	52
RT. STA. 122+89 TO STA. 1+35.35 (SOB)	43
STA. 1+35.35 (SOB) TO RT. STA. 125+62	61
LT. STA. 119+00 TO LT. STA. 121+70	55
LT. STA. 123+09 TO LT. STA. 125+62	52
TOTAL	263

CODE NO.		35100100	40300100	40603310	40603080
	AREA	AGGREGATE BASE COURSE, TYPE A (8")	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 (1 1/2")	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N50 (8 1/2")
	SQ YD	TON	GALLON	TON	TON
LOCATION					
CH 40 / NEW CITY ROAD					
STA. 119+00 TO 121+60.27	636.20		319	54	303
STA. 122+99.73 TO STA. 125+62.28	641.80		321	54	306
TR SLABONEY RD					
STA. 0+11.14 TO STA. 1+35.35	258.80		130	22	124
DRIVEWAY					
STA. 121+98.00 LT.	63.70	87			
TOTAL		87	770	130	733

CODE NO.	63000001
	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6' POSTS
	FOOT
LOCATION	
LT. STA. 123+53.28 TO LT. STA. 124+78.28	125
RT. STA. 119+81.72 TO RT. STA. 121+06.72	125
RT. STA. 124+03.34 TO RT. STA. 124+53.34	50
TOTAL	300

CODE NO.	78200410
	GUARDRAIL MARKERS, TYPE A
	EACH
LOCATION	
LT. STA. 121+26.32 TO LT. STA. 124+78.28	6
RT. STA. 119+81.72 TO RT. STA. 124+53.34	6
LT. (SIDEROAD)	1
RT. (SIDEROAD)	1
TOTAL	14

CODE NO.	44000100
	PAVEMENT REMOVAL
	SQ YD
LOCATION	
STA. 119+00 TO 121+60.27	636.2
STA. 122+99.73 TO STA. 125+62.28	641.8
TOTAL	1278

CODE NO.	X6300130
	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)
	FOOT
LOCATION	
LT. STA. 120+98.00 (DRIVEWAY)	37.5
(SOBLOTNY ROAD) RT.	37.5
(SOBLOTNY ROAD) LT.	37.5
TOTAL	112.5

CODE NO.	X5420636
	PIPE CULVERT TO BE CLEANED 36"
	FOOT
LOCATION	
STA. 121+98 LT. (CH 40)	49
TOTAL	49

CODE NO.	78201000
	TERMINAL MARKER - DIRECT APPLIED
	EACH
LOCATION	
LT. STA. 119+80.43	1
LT. STA. 120+80.43	1
LT. STA. 125+28.28	1
RT. STA. 119+31.72	1
(SIDEROAD)	2
RT. STA. 125+03.34	1
TOTAL	7

CODE NO.	44000200
	DRIVEWAY PAVEMENT REMOVAL
	UNIT
LOCATION	SQ YD
ENTRANCES	
LT. STA. 124+78.28 TO LT. STA. 125+28.28	76.44
TOTAL	76

CODE NO.	X6310088
	TRAFFIC BARRIER TERMINAL, TYPE 6A (SPECIAL)
	EACH
LOCATION	
LT. STA. 121+26.32 TO LT. STA. 121+70.07	1
LT. STA. 123+09.53 TO LT. STA. 123+53.28	1
RT. STA. 121+06.72 TO RT. STA. 121+50.47	1
RT. STA. 122+89.93 TO RT. STA. 123+33.68	1
TOTAL	4

CODE NO.	63100167
	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT
	EACH
LOCATION	
LT. STA. 119+80.43 TO LT. STA. 120+80.43	2
LT. STA. 124+78.28 TO LT. STA. 125+28.28	1
RT. STA. 119+31.72 TO RT. STA. 119+81.72	1
(SOBLOTNY ROAD) RT.	1
(SOBLOTNY ROAD) LT.	1
RT. STA. 124+53.34 TO RT. STA. 125+03.34	1
TOTAL	7