

SUMMARY OF QUANTITIES					
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	50% FEDERAL 50% LOCAL	80% FEDERAL 20% LOCAL
20800150	TRENCH BACKFILL	CU YD	8		8
35101400	AGGREGATE BASE COURSE, TYPE B	TON	100		100
42001300	PROTECTIVE COAT	SQ YD	2,590		2,590
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	16		16
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	17,368		17,366
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	3,576		3,576
42400800	DETECTABLE WARNINGS	SQ FT	408		408
44000100	PAVEMENT REMOVAL	SQ YD	120		120
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	588		588
44000900	SIDEWALK REMOVAL	SQ FT	25,204		25,204
50901760	PIPE HANDRAIL	FOOT	70		70
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1		1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1		1
60255500	MANHOLES TO BE ADJUSTED	EACH	4		4
60260900	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	1		1
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	1		1
60286900	VALVE BOXES TO BE ADJUSTED	EACH	12		12
60603900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6 12	FOOT	496		496
66600200	NON-SPECIAL WASTE DISPOSAL	CU YD	62		62
68900460	SPECIAL WASTE PLANS AND REPORTS	L SUM	1		1
68900530	SOIL DISPOSAL ANALYSIS	EACH	5		5
67100100	MOBILIZATION	L SUM	1		1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1		1

SUMMARY OF QUANTITIES					
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	50% FEDERAL 50% LOCAL	80% FEDERAL 20% LOCAL
Δ 61028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	747	747	
Δ 61028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	127	127	
Δ 61400100	HANDHOLE	EACH	9	9	
Δ 61603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	3,816	3,816	
Δ 61702415	ELECTRIC CABLE IN CONDUIT, 900V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	635	635	
Δ 62500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	EACH	3	3	
Δ 63600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	160	160	
X0327018	DECORATIVE SIGN POST	EACH	17		17
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.1		0.1
X4240420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ FT	11,013		11,013
X4240440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	2,083		2,083
X6024502	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	1		1
X6026200	INLETS TO BE ADJUSTED (SPECIAL)	EACH	3		3
X7010215	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1
XX008716	RELOCATE GUTTER DRAIN	EACH	12		12
XX008716	WATER METER LIDS TO BE ADJUSTED	EACH	10		10
XX008717	LIGHT POLE, STREET & SIDEWALK, SPECIAL	EACH	31	31	
XX008718	LIGHT POLE, STREET, SPECIAL	EACH	7		7
XX008719	CLEAN AND SEAL EXISTING COLORED CONCRETE	SQ FT	7,834		7,834
XX008720	PORTLAND CEMENT CONCRETE SIDEWALK RAMP	EACH	1		1
XX008721	CONCRETE STEPS	EACH	3		3
XX008722	CONCRETE STEPS	SQ FT	2,437		2,437

SPECIAL PROVISION  
Δ SPECIALTY ITEMS

Revised V713