

ROUTE NO.	SECTION	CONTRACT	TOTAL SHEETS	SHEET NO.
11-0003-00-SW	MOULTRIE	44	14	
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJ. CT.	

CONTRACT #95696

RELOCATE GUTTER DRAIN	
LOCATION	EACH
Rt Sta. 11+32.0	1
Lt Sta. 21+44.8	1
Rt Sta. 23+32.4	1
Rt Sta. 23+49.6	1
Rt Sta. 23+70.7	1
Rt Sta. 23+91.7	1
Rt Sta. 24+12.8	1
Rt Sta. 24+33.8	1
Rt Sta. 24+54.9	1
Rt Sta. 24+75.0	1
Rt Sta. 24+92.3	1
Rt Sta. 25+05.7	1
Total	12

AGGREGATE BASE COURSE, TYPE B	
LOCATION	TON
Rt Sta. 23+21.9 to 25+05.2	100
Total	100

LOCATION	P.C.C. SIDEWALK, 4" SQ FT	P.C.C. SIDEWALK, 6" SQ FT	DETECTABLE WARNING SQ FT	P.C.C. SIDEWALK, 4" SPECIAL SQ FT	P.C.C. SIDEWALK, 6" SPECIAL SQ FT	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 FOOT
HARRISON STREET						
Lt 20+36.7 to 21+86.2	717					
Lt 20+36.8 to 22+01.5				645		
Lt 21+56.2 to 22+47.8		549				
Lt 21+99.8 to 22+26.9				102		
Lt 22+25.5 to 22+47.8				70		
Lt 22+47.8			12			
Rt 20+45.1 to 21+34.5	536					
Rt 20+34.4 to 20+85.4				232		
Rt 20+85.0 to 21+33.8				173		
Rt 21+34.5 to 21+57.9		140				
Rt 21+57.9 to 22+46.9	547					
Rt 21+57.9 to 22+43.2				418		
Rt 22+42.7 to 22+46.0					11	
Rt 22+43.6			12			
Lt 22+73.8 to 25+03.4	1492					
Lt 22+77.5 to 22+95.6				61		
Lt 22+77.4			12			
Lt 24+35.6 to 24+95.4				45		
Lt 24+95.6 to 25+01.7					29	
Lt 24+96.6			10			
Lt 24+96.0 to 25+01.2				39		
Rt 22+77.9 to 23+22.5	237					
Rt 22+99.5 to 22+99.5				50		
Rt 23+21.5 to 25+04.6	981					
Rt 22+92.8			10			
Rt 24+86.8 to 24+92.3				22		
Rt 24+91.8 to 25+05.2					23	
Rt 24+95.2			10			
Rt 24+96.3 to 25+03.9				14		
Rt 24+96.3 to 25+04.7				3E		
Rt 25+04.6			10			
Total	4510	689	76	1802	102	93

LOCATION	P.C.C. SIDEWALK, 4" SQ FT	P.C.C. SIDEWALK, 6" SQ FT	DETECTABLE WARNING SQ FT	P.C.C. SIDEWALK, 4" SPECIAL SQ FT	P.C.C. SIDEWALK, 6" SPECIAL SQ FT	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 FOOT
MAIN STREET						
Lt 30+47.1 to 31+32.4	512					
Lt 30+46.5 to 31+31.7				299		
Lt 31+32.4 to 31+48.0		93				
Lt 31+27.0 to 31+52.6					94	
Lt 31+48.0 to 32+58.8	774					
Lt 31+48.0 to 32+03.0				182		
Lt 32+43.5 to 32+57.8					34	
Lt 32+53.8			32			
Rt 30+26.4 to 31+32.3	722				42	
Rt 30+27.4 to 32+57.1						
Rt 30+27.4 to 30+33.8				48		
Rt 30+39.7 to 31+31.7				469		
Rt 31+32.3 to 31+62.7		183				
Rt 31+27.2 to 31+67.8					237	
Rt 31+62.7 to 32+58.1	606					
Rt 32+43.5 to 32+57.1					32	
Rt 32+52.8			32			
Lt 32+86.1 to 34+88.2	1123					
Lt 32+87.0 to 33+02.2					29	
Lt 32+93.0			25			
Lt 33+00.7 to 34+88.2				561		
Total	3737	276	90	1559	331	137

SIGN REPLACEMENT					
EXISTING LOCATION	DESCRIPTION	PROPOSED LOCATION DECORATIVE SIGN POST	PROPOSED LOCATION STREET LIGHT POLE	POLE #	MOUNTING HEIGHT
22.52/Lt 549+46.25	Library Direction 24"x24" **		23/Lt 548+40	5	7
25.20/Lt 549+00.99	Speed Limit 35 30"x36" **		23/Lt 549+49	7	8
22.73/Rt 549+47.79	Little Theatre on the Square 48"x18"		23/Rt 549+86	6	7
24.20/Rt 550+03.67	Washington Street Under Jackson Street Over	23/Rt 550+05.71			POST TOP
21.22/Rt 133+84.23	No Parking (anytime) R7-100-18		21/Rt 134+29	10	7
22.36/Lt 134+76.75	Speed Limit 30 30"x36" **		23/Lt 134+77	11	8
21.93/Lt 135+14.93	Police Station Sign	22/Lt 135+15			7
23.08/Lt 135+65.75	No Parking (anytime) R7-100-18		24/Lt 135+78	13	7
22.26/Rt 136+27.67	Hamilton Street Under Adams Street Over	22.26/Rt 136+27.67			POST TOP
20.77/Rt 137+14.1	Fire Station Warning 36"x36"		21/Rt 137+54	16	6
34.81/Rt 124+40.42	Jefferson Street Under Van Buren Over	34/Rt 124+40			POST TOP
43.01/Lt 124+44.16	Stop Sign R1-1-36" **	43/Lt 124+44			7
41.33/Rt 124+79.98	Stop Sign R1-1-36" **	47/Rt 124+75			7
29.15/Lt 14+43.88	Accessible Parking R7-8 and R7-101	29.15/Lt 14+43.88			4
28.50/Rt 14+81.34	Stop Sign R1-1-36" **	30/Rt 14+67			7
32.27/Lt 20+46.70	Stop Sign R1-1-36" **	32.29/Lt 20+39.88			7
30.65/Rt 20+74.16	Visitors Parking	30.65/Rt 20+74.16			5
30.52/Rt 21+09.50	Visitors Parking	30.52/Rt 21+09.50			5
30.84/Rt 21+21.70	Visitors Parking	30.84/Rt 21+21.70			5
32.09/Rt 23+42.79	Accessible Parking R7-8 and R7-101	32.09/Rt 23+42.79			4
33.09/Lt 24+64.98	Accessible Parking R7-8 and R7-101	33.09/Lt 24+64.98			4
30.22/Rt 24+91.94	Stop Sign R1-1-36" **	31/Rt 24+88			7
27.76/Lt 30+51.58	Stop Sign R1-1-36" **		29/Lt 30+62	42	7
26.84/Lt 30+64.10	30 Minute Parking	26.84/Lt 30+64.10			5
27.19/Lt 30+77.89	30 Minute Parking	27.19/Lt 30+77.89			5
Total (EACH)				17	

* The Contractor must measure all signs before ordering the sign brackets to coordinate the size.
 ** The Contractor shall coordinate these sign measurements with the Illinois Department of Transportation Traffic Department. IDOT is providing these signs.

DRAINAGE STRUCTURES												
No.	Location	Existing Type Grate or Lid	Existing Lid or F.L. Elevation	Proposed Lid or F.L. Elevation	Invert Incoming	Invert Outgoing	PAY ITEMS					
							Manhole to be Adjusted EACH	Inlet, Type A W/T-1F, OL EACH	Inlet, Type A W/T-8 Grate EACH	Inlet to be Adjusted W/T-3, F&G EACH	Inlet to be Adjusted (Special) EACH	Inlet to be Adjusted W/T-11, F&G EACH
1	OMITTED											
2	OMITTED											
3	25.0/Rt 549+94.6	1	658.77	658.55			1					
4	20.3/Rt 550+04.3		658.30	658.36					1			
5	24.8/Lt 133+90.9		671.45	671.83					1			
6	24.4/Lt 135+83.4		659.89	658.71					1			
7	23.3/Lt 136+24.8		658.38	659.39					1			
8	23.6/Lt 137+05.5	1	669.15	668.85					1			
9	28.3/Lt 12+86.2	15	669.85	669.85	668.25(SW)	667.50(S)			1			2
10	43.4/Rt 12+73.7	8	669.81	669.81					1			3
11	37.1/Lt 22+66.6	1	673.74	673.67					1			
12	31.8/Lt 22+83.5	15	674.22	673.40	672.27(N)	670.75(SW)					1	3
13	34.4/Lt 32+49.5	1	673.04	672.80					1			
15	30.0/Lt 11+27.9	3	667.97	667.97								
TOTAL									4	1	1	8

* Elevations shown are for estimating purposes only. Actual elevation to be determined in the field.

LOCATION	PROTECTIVE COAT SQ YD
JACKSON STREET	
Sidewalk	265
Curb and Gutter	11
HAMILTON STREET	
Sidewalk	519
Curb and Gutter	21
JEFFERSON STREET	
Sidewalk	802
Curb and Gutter	22
Pavement	16
HARRISON STREET	
Sidewalk	614
Curb and Gutter	12
MAIN STREET	
Sidewalk	483
Curb and Gutter	25
Total	2590

LOCATION	P.C.C. DRIVEWAY PAVEMENT, 6" SQ YD
JEFFERSON STREET	
Lt 11+81.0 to 12+11.9	16
Total	16

LOCATION	CONCRETE STEPS EACH	CONCRETE STEPS SQ FT	TRANSITION WALL EACH
JACKSON STREET			
Lt Sta. 14+33.6	1		
Lt Sta. 22+95.6 to 24+85.6		1098	
Lt Sta. 22+95.4			1
Lt Sta. 24+85.9			1
Rt Sta. 23+22.0 to 24+19.4		712	
Rt Sta. 23+21.7			1
Rt Sta. 24+19.6			1
Rt Sta. 24+19.9 to 24+86.7		434	
Rt Sta. 24+87.0			1
Lt Sta. 31+24.6	1		
Lt Sta. 32+03.2			1
Lt Sta. 32+03.5 to 32+44.0		193	
Lt Sta. 32+22.4	1		
Lt Sta. 32+44.3			1
Total	3	2437	7

LOCATION	P.C.C. SIDEWALK RAMP EACH	PIPE HANDRAIL FOOT
Rt Sta. 22+99.5 to 23+21.9	1	70
Total	1	70

	MILANO & GRUNLOH ENGINEERS, LLC	SCHEDULE OF QUANTITIES SIDEWALK ENHANCEMENT CITY OF SULLIVAN SECTION 11-00033-00-SW MOULTRIE COUNTY, ILLINOIS
	114 WEST WASHINGTON SULLIVAN, ILLINOIS 62451	
	PHONE: (217) 947-7282 FAX: (217) 947-7282	
	File name: S:\DWG\11002900\DWG\Quantities.dwg Plot date: 11/07/12 at 07:40	