



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 11, 2018

SUBJECT: Various Routes  
Project NHPP-R4FF(212)  
Section (84-4, 84-3, 84-9, 110)RS  
Sangamon County  
Contract No. 72J83  
Item No. 34, January 19, 2018 Letting  
Addendum C

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 12 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Priscilla Tobias, P.E.  
Director of Program Development  
Assistant Chief Engineer

A handwritten signature in black ink, appearing to read "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Jeffrey South, Region 4, District 6; D. Carl Puzey; Tim Kell; Estimates

CWR/ck

## **DELINEATOR SYSTEM**

This work consists of furnishing and installing a delineator system. The delineator system shall consist of two components; an anchor and the delineator post.

The anchor shall consist of Telescoping Steel Sign Support, Article 728 of the Standard Specifications, 2 inch. The anchor shall be ground mounted, and driven by hand or mechanical means to a minimum depth of 23 inches measured from the ground line. Anchors shall leave 1 inch exposed above the ground surface. The top of the anchor shall be protected by a suitable driving cap. Anchors shall consist of one continuous section of material.

The delineator post shall be 48 inch tall, terminating in a 3 inch by 12 inch flattened portion that accepts reflective sheeting. The reflective sheeting shall consist of a 3 inch by 9 inch reflector of the color of the pavement marking the delineator supplements. The delineator post shall attach to the anchor by pin connection. The anchor shall seat 1 inch into the delineator post. The delineator post shall be bright white finish with UV inhibiting finish, and sealed at the top.

The furnishing and installation of flexible delineator post system will be paid for at the contract unit price per each for DELINEATOR SYSTEM.

## **DELINEATOR REMOVAL**

This work consists of removing the existing delineator posts and reflectors as indicated on the plans or as directed by the Engineer. The delineator posts and reflectors shall be disposed according to Article 202.03 of the Standard Specifications.

This work will be measured and paid for at the contract unit price per each for DELINEATOR REMOVAL. No additional compensation will be allowed for two single reflectors placed on one post.