SEEDING SCHEDULE

LOCATION STATION TO STATION			LENGTH (INFORMATION ONLY)	SEEDING, CLASS 1B	SEEDING, CLASS 7	MULCH, METHOD 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	TEMPORARY EROSION CONTROL SEEDING	REMARKS
			FOOT	ACRE	ACRE	ACRE	POUND	POUND	POUND	TON	POUND	
IL 13 EASTBOUND												
168+30	TO	171+33	303	0.54	0.54	1.08	49	49	49	1.08	162	LEFT
IL 13 WESTBOUND												
160+82	TO	177+85	1703	0.85	0.85	1.70	77	77	77	1.70	255	MEDIAN
167+79	TO	170+75	296	0.56	0.56	1.12	51	51	51	1.12	168	RIGHT
BIKE PATH												
0+00	TO	5+25	525	0.14	0.14	0.28	13	13	13	0.28	42	
9+75	TO	27+55	1780	0.82	0.82	1.64	74	74	74	1.64	246	
TOTAL				2.91	2.91	5.82	264	264	264	5.82	873	

BARRIER SCHEDULE

LOCATION STATION TO STATION				LENGTH (INFORMATION ONLY)	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	CONCRETE BARRIER REMOVAL	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3	REMARKS
IL 13 EASTBOUND AND WESTBOUND				FOOT	FOOT	FOOT	FOOT	EACH	EACH	
STAGE III										
ECROSS RIGHT	12+45	TO	25+19	1300						INCLUDED IN STANDARD 701416
ECROSS LEFT	19+73	TO	23+60	400	400			1		NOT INCLUDED IN STANDARD 701416
STAGE III SUBTOTAL					400			1		
STAGE IV										
WCROSS LEFT	22+25	TO	34+04	1200		1200				RELOCATE FROM STAGE III, INCLUDED IN STANDARD 701416
WCROSS RIGHT	23+70	TO	31+45	800	300	500			1	NOT INCLUDED IN STANDARD 701416 - 500' RELOCATED FROM STAGE III, 300' NEW BARRIER
WCROSS RIGHT	23+70	TO	31+45	800			800			NOT INCLUDED IN STANDARD 701416
STAGE IV SUBTOTAL					300	1700	800			
TOTAL					700	1700	800	1	1	

⚠1 REVISED SHEET 1-4-2018

MODEL: Default
FILE NAME: pw:\\ILDOT-PW01.bentley.com:PWIDOT\Documents\IDOT Offices\District 8\Projects\78544\CAD\Data\CAD\sheets\78544 sht0-typ sch lts mesp\elements.dgn

USER NAME = russellcf	DESIGNED -	REVISED -	
	DRAWN -	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	
PLOT DATE = 1/3/2018	DATE -	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SEEDING SCHEDULE

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(12-1VBY,12-2VB)DM	JACKSON	111	19
		CONTRACT NO. 78544		
		ILLINOIS FED. AID PROJECT		