

RESURFACING
STU - 80% FEDERAL
0005

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	VILLAGE OF RINGWOOD	VILLAGE OF JOHNSBURG	MCHENRY TOWNSHIP ROAD DISTRICT	CITY OF MCHENRY
A1 20800150	TRENCH BACKFILL	CU YD	25		5	20	
28000510	INLET FILTERS	EACH	12	12			
* 40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	56,165	22,524	5,384	20,643	7,614
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	5	5	5	5
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4,020	1,675	485	1,860	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	557.0	251.0	37.0	131.0	138.0
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2,450	1,015			1,435
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8,990	3,740	840	3,220	1,190
* 40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	868	191	22	319	336
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1,900.0	1,071.0			829.0
* 42400800	DETECTABLE WARNINGS	SO FT	262.0	182.0			80.0
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SO YD	68,062.0	28,347.0	8,216.0	31,499.0	
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SO YD	19,841.0	8,224.0			11,617.0
44000600	SIDEWALK REMOVAL	SO FT	2,099.0	1,017.0			1,082.0
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SO YD	444.0	172.0	41.0	173.0	58.0
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SO YD	444.0	172.0	41.0	173.0	58.0
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SO YD	444.0	172.0	41.0	173.0	58.0
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SO YD	444.0	172.0	41.0	173.0	58.0
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	526	360			166
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,564	440	211	734	179
A1 50105220	PIPE CULVERT REMOVAL	FOOT	96		48	48	
54262715	METAL END SECTIONS 15"	EACH	2		2		
54262724	METAL END SECTIONS 24"	EACH	2			2	
542C1060	PIPE CULVERTS, CLASS C, TYPE 2 15"	FOOT	48		48		
542C1060	PIPE CULVERTS, CLASS C, TYPE 2 24"	FOOT	48			48	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2	2			
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	585.0	185.0		400.0	
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.25	0.25	0.25	0.25
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.25	0.25	0.25	0.25
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.25	0.25	0.25	0.25
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.25	0.25	0.25	0.25
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.25	0.25	0.25	0.25

* SPECIAL PROVISION
+ SPECIALTY ITEM

PLAN	DATE
BY	
REVISIONS	
NO.	
DATE	
BY	
REVISIONS	
NO.	
DATE	

PROFILE	DATE
BY	
REVISIONS	
NO.	
DATE	
BY	
REVISIONS	
NO.	
DATE	

HRG PROJECT NO.: 170709
 HRG PROJ. CONTACT: 170709-snt-sum.dicgn
 FILE NAME: L:\proj\170709\170709.dwg
 PLOT DRIVER: plot10tbl.tbl
 PEN TABLE:



HRGreen.com
 Illinois Professional Design Firm
 # 184-001322

USER NAME = dstencz	DESIGNED -	REVISED - Addendum 1-12/20/17
	DRAWN - DMS	REVISED -
PLOT SCALE = N.T.S.	CHECKED -	REVISED -
PLOT DATE = 12/15/2017	DATE = 12/15/17	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BARNARD MILL ROAD & RINGWOOD ROAD			
SUMMARY OF QUANTITIES			
SCALE: N.T.S.	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.

F.A.U. RTE. 0166/408	SECTION NO. 17-00005-00-RS	COUNTY MCHENRY	TOTAL SHEETS 29	SHEET NO. 4
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 61E36		

RESURFACING
STU - 80% FEDERAL
0005

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	VILLAGE OF RINGWOOD	VILLAGE OF JOHNSBURG	MCHENRY TOWNSHIP ROAD DISTRICT	CITY OF MCHENRY
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.5			0.5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	13,194.0	5,705.0	1,103.0	4,644.0	1,742.0
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	4,516.0	1,954.0	379.0	1,584.0	599.0
+ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	231.8	195.4			36.4
+ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	79,931.0	29,955.0	7,826.0	33,130.0	9,020.0
+ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,373.0	1,085.0			288.0
+ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	725.0	600.0			125.0
+ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	311.0	189.0	56.0		66.0
+ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	33				33
+ 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	32				32
+ * 88600600	DETECTOR LOOP REPLACEMENT	FOOT	200.0	200.0			
+ * X0326899	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	4	4			
* X0326806	WASHOUT BASIN	L SUM	1	0.5			0.5
* X0327584	GRADING AND SHAPING SHOULDERS, SPECIAL	FOOT	2,000.0	800.0	300.0	500.0	400.0
* X0964700	SHOULDERS, SPECIAL	SO YD	180.0	120.0			60.0
* X4400196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SO YD	543	151	62	251	79
* X4810200	AGGREGATE SHOULDER REMOVAL	CU YD	60	40			20
A1 + * X5012650	CONCRETE HEADWALL REMOVAL SPECIAL	EACH	1			1	
* X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	2		1	2
* X7240505	RELOCATE SIGN PANEL AND POST	EACH	3				3
* Z0004561	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	655.0	449.0			206.0
* Z0018300	DRAINAGE STRUCTURE REPAIR	EACH	13	13			
* Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	310.0	103.0	52.0	103.0	52.0

DATE	BY	REVISIONS	CHECKED
		PLANNED	ALIGNED
		NOTE BOOK	CADD FILE NAME
		NO.	

DATE	BY	REVISIONS	CHECKED
		GRADES	STRUCTURE
		NOTE BOOK	NOTATION SHEET
		NO.	

HRG PROJECT NO.: 170709
 HRG PROJ. CONTACT: 170709-spf-sum.dwg
 FILE NUMBER: 170709
 PEN TABLE: 170709.dwg



USER NAME = dstanec	DESIGNED -	REVISED Addendum 1-12/2017
	DRAWN - DMS	REVISED -
PLOT SCALE = N.T.S.	CHECKED -	REVISED -
PLOT DATE = 12/15/2017	DATE = 12/15/17	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

BARNARD MILL ROAD & RINGWOOD ROAD
 SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.U. RTE. 0166/408	SECTION NO. 17-00005-00-RS	COUNTY MCHENRY	TOTAL SHEETS 29	SHEET NO. 5
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 61E36		

* SPECIAL PROVISION
 + SPECIALTY ITEM