

MODEL: SOO SHEET 5 (Sheet)  
 FILE NAME: P:\work\p22\amby.com\PI\DOT\Documents\DOT Office\DH413\CRD Project\036667\CADD\InfoCAD\sheet\036667 SOO

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				90% FED 10% STATE	90% FED 10% STATE
				ROADWAY	BRIDGE
				0005	0047
				RURAL	S.N. 032-0078
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100701	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	EACH	1	1	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	△
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	28	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	11501	11501	
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	6709	6709	
70307130	TEMPORARY PAVEMENT MARKING - LINE 6" - TYPE IV TAPE	FOOT	5750	5750	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	800	800	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	787.5	787.5	
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	10	10	

\*= SPECIALTY ITEM

USER NAME = brandon.cofss	DESIGNED - ____	REVISED - ____
	DRAWN - ____	REVISED - ____
PLOT SCALE = 0.16666633' / In.	CHECKED - ____	REVISED - ____
PLOT DATE = 11/2/2023	DATE - ____	REVISED - ____

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET 5 OF 7 SHEETS STA. \_\_\_+\_\_\_ TO STA. \_\_\_+\_\_\_

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(32-2)RS,BRR	GRUNDY	39	7
CONTRACT NO. 66K67				
ILLINOIS FED. AID PROJECT				