F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	*	COOK	631	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* (2425 & 2626) R-2 CONTRACT NO. 62111

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY		I-80 **	RAILROAD, BURNHAM, 175TH ST., BERNICE **	BRIDGE ** 016-2791	BRIDGE ** 016-2792	RETAINING WALLS **	SURVEILLANCE **	LANSING ****	LANSING ****	SIGNING **	CULVERT		TRAFFIC SIGNALS ##	CHICAGO HEIGHTS *****
						J000-2A	I000-2A	X271-2A	X281-2A	Y007	Y032-1F	I000-2A	Y060	Y002-1C	Y007		Y031-1F	Y060
	M7240320	REMOVE SIGN PANEL - TYPE 2	SQ M	26.3										26.3				
	M7240330	REMOVE SIGN PANEL - TYPE 3	SQ M	57.9										57.9				
	M7240720	RELOCATE SIGN PANEL - TYPE 2	SQ M	1.1										1.1				
*	M7280100	TELESCOPING STEEL SIGN SUPPORT	METER	38										38				
*	M7330030	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (1.53M X 2.14M)	METER	34.2										34.2				
*	M7330235	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (0.90M X 1.68M)	METER	8.4										8.4				
*	M7330255	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (0.90M X 2.14M)	METER	9.2										9.2				
*	M7330500	OVERHEAD SIGN STRUCTURE WALKWAY	METER	39.6										39.6				
*	M7340200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU M	16.4										16.4				
*	M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100MM	METER	1513			1513											
*	M7800115	THERMOPLASTIC PAVEMENT MARKING - LINE 150MM	METER	99								99						
*	M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	METER	137			137											
*	M7800140	THERMOPLASTIC PAVEMENT MARKING - LINE 600MM	METER	63			63											
*	M7800605	EPOXY PAVEMENT MARKING - LINE 100MM	METER	2002		2002												
*	M7800610	EPOXY PAVEMENT MARKING - LINE 125MM	METER	917		917												
*	M7800615	EPOXY PAVEMENT MARKING - LINE 150MM	METER	752		752												
*	M7802010	POLYUREA PAVEMENT MARKING, TYPE I - LINE 100MM	METER	9801		9801												
*	M7802012	POLYUREA PAVEMENT MARKING, TYPE I - LINE 125MM	METER	4604		4604												
*	M7802020	POLYUREA PAVEMENT MARKING, TYPE I - LINE 200MM	METER	2916		2916												
*	M7802030	POLYUREA PAVEMENT MARKING, TYPE I - LINE 300MM	METER	1013		1013												
	M7830100	PAVEMENT MARKING REMOVAL	SQ M	2688		2688												
*	M8120130	CONDUIT EMBEDDED IN STRUCTURE, 65 MM DIA. GALVANIZED STEEL	METER	160							160							
*	M8120230	CONDUIT EMBEDDED IN STRUCTURE, 50 MM DIA. PVC	METER	305							305							
*	M8120270	CONDUIT EMBEDDED IN STRUCTURE, 100 MM DIA. PVC	METER	72							72							
*	M8131400	JUNCTION BOX, NON-METALLIC, EMBEDDED IN STRUCTURE, 525MM X 275MM X 200MM	EACH	2							2							
*	M8860100	DETECTOR LOOP, TYPE I	METER	71													71	
*	M8950235	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	METER	74													74	
*	MX030063	STORM SEWER (WATER MAIN REQUIREMENTS) 300MM	METER	210.5			193.1						17.1					0.3
*	MX030067	STORM SEWER (WATER MAIN REQUIREMENTS) 900MM	METER	95.5			49						37.4					9.1
	MX030144	CATCH BASINS, 1.2M BY 0.9M SPECIAL, TYPE 20 FRAME AND GRATE	EACH	10		10												
	MX030151	STORM SEWER, DUCTILE IRON PIPE, TYPE 1 200MM	METER	2								2						
	MX030170	CATCH BASINS, 1.2M BY 1.5M SPECIAL, TYPE 22 FRAME AND GRATE	EACH	1		1												
	MX030199	TEMPORARY PAVEMENT	SQ M	295		295												
	MX030504	TEMPORARY PAVEMENT (INTERSTATE)	SQ M	2813		2813												
	MX030508	REMOVAL OF TEMPORARY SOIL RETENTION SYSTEM	SQ M	403					345						58			
*	MX032160	CONDUIT ENCASED, REINFORCED CONCRETE, 100MM DIA. PVC, 2 WIDE X 1 HIGH	METER	300							300							
	MX033183	SOIL STABILIZERS	KG	68017		68017												
	MX033234	SLOTTED DRAIN REMOVAL	METER	623		623												

*SPECIALTY ITEMS

**90% FEDERAL
10% STATE

***50% STATE
50% VILLAGE OF LANSING

****100% VILLAGE OF LANSING

*****100% CITY OF CHICAGO HEIGHTS

##90% FEDERAL
5% STATE
5% VILLAGE OF LANSING

Rev. 1-6-06

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. ROUTE 80/94 (KINGERY EXPRESSWAY)
EB & WB INSIDE LANES (MAINLINE) CONSTRUCTION
COOK COUNTY

SUMMARY OF QUANTITIES
V

SCALE: NONE
DATE: 9/13/05
DRAWN BY: SNM
CHECKED BY: KC

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

..\S07TR02A.DGN, ..\S07TR02A.DGN, ..\A8P09002A.DGN
9/14/2005 3:24:41 PM F:\DOT\MUNTY\92975\DVL\DGN\S07TR05A.DGN
STANKRJ