

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94		COOK	631	10
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* (2425 & 2626) R-2			CONTRACT NO. 62111	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	I-80 **	RAILROAD, BURNHAM, 175TH ST., BERNICE **	BRIDGE ** 016-2791	BRIDGE ** 016-2792	RETAINING WALLS **	SURVEILLANCE **	LANSING *****	CULVERT 5ND16-2013	TRAFFIC SIGNALS **
				J000-2A	I000-2A	X271-2A	X281-2A 124	Y007	Y032-1F	I000-2A	Y007	Y031-1F
MX033276	TEMPORARY SOIL RETENTION SYSTEM	SQ M	761									
MX033290	SEDIMENT CONTROL, SILT FENCE	METER	612	265	347							
MX033291	SEDIMENT CONTROL, SILT FENCE, MAINTENANCE	METER	612	265	347							
MX033292	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ M	1622	811	811							
MX033303	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ M	406	203	203							
MX355150	BITUMINOUS BASE COURSE SUPERPAVE, 150MM	SQ M	143		143							
MX355200	BITUMINOUS BASE COURSE SUPERPAVE, 200MM	SQ M	76		76							
MX406012	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	M TON	1589.1	1253.3	26.1					309.7		
MX407380	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 230MM	SQ M	4242		2644					1598		
MX407450	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 300MM	SQ M	5665		5665							
MX482280	BITUMINOUS SHOULDERS SUPERPAVE 150MM	SQ M	250	250								
MX512015	TEMPORARY SHEET PILING REMOVAL	SQ M	3434	3274		160						
MX704200	REMOVE TEMPORARY CONCRETE BARRIER	METER	5339	5339								
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	10787		9061					1726		
MZ031106	TEMPORARY MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ M	510				510					
MZ047300	PROTECTIVE SHIELD	SQ M	1164			1164						
MZ065755	SLOTTED DRAIN 300MM WITH VARIABLE SLOT HEIGHT	METER	96.9	96.9								
X0322916	PROPOSED STORM SEWER CONNECTION TO EXISTING STORM SEWER	EACH	10		10							
X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	2	1	1							
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	146	99	47							
X0324044	EROSION CONTROL, TEMPORARY PIPE SLOPE DRAIN	EACH	12	11	1							
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	8	8								
X0324587	NOISE ABATEMENT WALL ANCHOR ROD ASSEMBLY	EACH	45		21			24				
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	489	489								
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	20		20							
X6020166	DRAINAGE STRUCTURES, TYPE 1 SPECIAL WITH TWO TYPE 20 FRAME AND GRATES	EACH	14	14								
X6020167	DRAINAGE STRUCTURES, TYPE 2 SPECIAL WITH TWO TYPE 22 FRAME AND GRATES	EACH	1	1								
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1								
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	240	240								
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	10	10								
X8800020	SIGNAL HEAD ,LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4									4
X8800037	SIGNAL HEAD ,LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2									2
X8800038	SIGNAL HEAD ,LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2									2
X8800040	SIGNAL HEAD ,LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2									2
X8800045	SIGNAL HEAD ,LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2									2
X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	8									8
XX001452	CONCRETE MASONRY BULKHEAD	EACH	11	5	6							
Z0002600	BAR SPLICERS	EACH	1506			1242	264					

*SPECIALTY ITEMS
 **90% FEDERAL
 10% STATE
 ***50% STATE
 50% VILLAGE OF LANSING
 ****100% VILLAGE OF LANSING
 *****100% CITY OF CHICAGO
 HEIGHTS
 **90% FEDERAL
 5% STATE
 5% VILLAGE OF LANSING

STANKRU
 545556575859 6061 62 63
 4041 4243 44 45 46 47 4849 5051 52 53 54 55 56 57 5859 6061 62 63
 9-16-2005, 15:08:43
 T:\DOCUMENT\8151750\CHIL.DGN\50170072ALDGN
 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. ROUTE 80/94 (KINGERY EXPRESSWAY)
 EB & WB INSIDE LANES (MAINLINE) CONSTRUCTION
 COOK COUNTY

SUMMARY OF QUANTITIES
 VI

SCALE: NONE
 DATE: 9/13/05

DRAWN BY: SNM
 CHECKED BY: KC

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 CHICAGO, ILLINOIS

Rev. 1-6-06

Rev.