

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	*	COOK	631	11
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* (2425 & 2626) R-2		CONTRACT NO. 62111		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	I-80 **	RAILROAD, BURNHAM, 175TH ST., BERNICE **	BRIDGE ** 016-2791	BRIDGE ** 016-2792	RETAINING WALLS **	SURVEILLANCE **	SIGNING **
				J000-2A	I000-2A	X271-2A	X281-2A	Y007-	Y032-JF	Y002-IC
MX033555	PAINT PAVEMENT MARKING - LINE 125MM (SPECIAL)	METER	61	61						
M434000	DETECTABLE WARNINGS	SQ M	18		18					
MX033461	WICK DRAINS	METER	25274	25274						
MX033560	CONCRETE BARRIER SINGLE FACE 815MM HEIGHT, REINFORCED	METER	475	475						
X0325130	TUBULAR TRAFFIC SIGN POST	EACH	11							11
X0325174	SIGN STRUCTURE ATTACHED TO PARAPET - ONE POST	EACH	3							3
X0325175	SIGN STRUCTURE ATTACHED TO PARAPET - TWO POSTS	EACH	1							1
MX033559	CONCRETE GLARE SCREEN, SPECIAL	METER	45.6	45.6						
MX033556	PORTLAND CEMENT CONCRETE PAVEMENT 250MM (JOINTED) (COLORED)	SQ M	751	751						
M7040210	RELOCATE TEMPORARY CONCRETE BARRIER (SPECIAL)	METER	3162	3162						
M4217150	LUG SYSTEM COMPLETE 15.0 METER	EACH	1	1						
X6040300	FRAMES AND GRATES, TYPE 20 (SPECIAL)	EACH	8	8						
X6040305	FRAMES AND GRATES, TYPE 22 (SPECIAL)	EACH	2	2						
MX033561	DUCTILE IRON PIPE, STORM SEWER, 150MM	METER	86.5	86.5						
MX033562	DUCTILE IRON PIPE, STORM SEWER, 200MM	METER	1.5		1.5					
MX033565	STORM SEWERS TO BE GROUTED	CU M	1488	1319	169					
MX033566	CULVERTS GROUTED	CU M	425	425						
MX033550	CONDUIT EMBEDDED IN STRUCTURE, 30 MM DIA. CNC, 4 WIDE X 2 HIGH	METER	2065					2065		
MX033557	CONDUIT IN TRENCH, 3-100MM DIA., RIGID GALV STEEL	METER	100					100		
MX033558	CONDUIT ATTACHED TO STRUCTURE, 3-100MM DIA., RIGID GALV STEEL, PVC COATED	METER	122					122		
MX033565	CONDUIT ENCASED, REINFORCED CONCRETE, 30 MM DIA. CNC, 4 WIDE X 2 HIGH	METER	96					96		
MX033563	COILABLE NONMETALLIC CONDUIT, 25MM DIA. (INNERDUCT)	METER	1098					1098		
Z0002605	BAR SPLICERS, SPECIAL	EACH	84	84						
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.9	0.1					
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	27	27						
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2							2
Z0018600	DRAINAGE STRUCTURE TO BE RECONSTRUCTED	EACH	2	2						
Z0030070	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2	2						
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	2						
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	7	7						
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	4	4						
Z0076600	TRAINEES	HOUR	500	500						
M5503090	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN AND SEWER PIPE, CLASS III, 600 MM	METER	147.4	147.4						
M5503111	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN AND SEWER PIPE, CLASS III, 750 MM	METER	221.1	221.1						
M5503130	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN AND SEWER PIPE, CLASS III, 900 MM	METER	41.0	41.0						
M5503150	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN AND SEWER PIPE, CLASS III, 1200 MM	METER	14.1	14.1						
M5503170	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN AND SEWER PIPE, CLASS II, 1500 MM	METER	64.6	64.6						
M5503180	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN AND SEWER PIPE, CLASS II, 1650 MM	METER	147.4	147.4						
M5503390	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN AND SEWER PIPE, CLASS III, 1650 MM	METER	389.5	389.5						

\*SPECIALTY ITEMS  
 \*\*90% FEDERAL  
 10% STATE  
 \*\*\*50% STATE  
 50% VILLAGE OF LANSING  
 \*\*\*\*100% VILLAGE OF LANSING  
 \*\*\*\*\*100% CITY OF CHICAGO  
 HEIGHTS  
 \*\*90% FEDERAL  
 5% STATE  
 5% VILLAGE OF LANSING

STAINKRUJ  
 9-14-2005, 13:48:46  
 T:\DOCUMENT\937501\CIVIL\DON\S070062A.DGN  
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

○○ SFY-2A 90% FED./10% STATE  
 □ NON-PARTICIPATING  
 ○ Y080  
 △ SFY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. ROUTE 80/94 (KINGERY EXPRESSWAY)  
 EB & WB INSIDE LANES (MAINLINE) CONSTRUCTION  
 COOK COUNTY

**SUMMARY OF QUANTITIES  
 VII**

SCALE: NONE  
 DATE: 9/13/05

DRAWN BY: SNM  
 CHECKED BY: KC

**TENG**  
 TENG & ASSOCIATES, INC.  
 ENGINEERS/ARCHITECTS/PLANNERS  
 CHICAGO, ILLINOIS

Rev. 1-6-06

Rev.