

SCHEDULE OF QUANTITIES

Table with columns: F.A.I. RTE., SECTION, COUNTY, TOTAL SHEETS, SHEET NO., STA., TO STA., FED. ROAD DIST. NO., ILLINOIS, FED. AID PROJECT, CONTRACT NO.

SIDEWALK REMOVAL TOTAL 757 SQ M

Table with columns: LOCATION, FROM STATION, TO STATION, OFFSET, AVG WIDTH, SQ M. Includes rows for 175TH ST and BURNHAM.

Table with columns: LOCATION, FROM STATION, TO STATION, OFFSET, AVG WIDTH, SQ M. Includes rows for BURNHAM.

CONCRETE BARRIER REMOVAL TOTAL 1877 METER

Table with columns: LOCATION, FROM STATION, TO STATION, OFFSET, METER. Includes rows for 180.

PAVED SHOULDER REMOVAL TOTAL 7306 SQ M

Table with columns: LOCATION, FROM STATION, TO STATION, OFFSET, AVG WIDTH, SQ M. Includes rows for 180.

PAVEMENT BREAKING TOTAL 24822 SQ M

Table with columns: LOCATION, FROM STATION, TO STATION, OFFSET, AVG WIDTH, SQ M. Includes rows for 180 and BURNHAM.

PORTLAND CEMENT CONCRETE SHOULDERS - 360MM TOTAL 23803 SQ M

Table with columns: LOCATION, FROM STATION, TO STATION, OFFSET, WIDTH 1(M), SQ M. Includes rows for 1-80/94 MED and 1-80/94 EB OUT.

STORM SEWER REMOVAL 300MM TOTAL 828 METER

Table with columns: LOCATION, STATION, OFFSET, STATION, OFFSET, METER. Includes rows for 1-80/94 WB and BURNHAM AVE.

1-80/94 EB TOTAL 34.2 METER

Table with columns: LOCATION, FROM STATION, TO STATION, OFFSET, METER. Includes rows for 1-80/94 EB.

STORM SEWER REMOVAL 375MM TOTAL 611 METER

Table with columns: LOCATION, STATION, OFFSET, STATION, OFFSET, METER. Includes rows for 1-80/94 WB.

STORM SEWER REMOVAL 450MM TOTAL 363 METER

Table with columns: LOCATION, STATION, OFFSET, STATION, OFFSET, METER. Includes rows for 1-80/94 WB.

STORM SEWER REMOVAL 600MM TOTAL 155 METER

Table with columns: LOCATION, STATION, OFFSET, STATION, OFFSET, METER. Includes rows for 1-80/94 WB and BURNHAM AVE.

STORM SEWER REMOVAL 1200MM TOTAL 266 METER

Table with columns: LOCATION, STATION, OFFSET, STATION, OFFSET, METER. Includes rows for 1-80/94 WB and BURNHAM AVE.

CULVERTS TO BE GROUTED TOTAL 425 CU M

Table with columns: LOCATION, FROM STA, OFFSET, TO STA, OFFSET, PIPE LENGTH, PIPE SIZE, CU M. Includes rows for 1-80 EB and BL RAMP U.

CONCRETE REMOVAL TOTAL 17 CU M

Table with columns: LOCATION, FROM STA, OFFSET, TO STA, OFFSET, PIPE LENGTH, PIPE SIZE, CU M. Includes row for 1-80 EB/WB.

Table with columns: REVISIONS, NAME, DATE. Includes entry for KV on 1/4/06.

ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. ROUTE 80/94 (KINGERY EXPRESSWAY) EB & WB INSIDE LANES (MAINLINE) CONSTRUCTION COOK COUNTY SCHEDULE OF QUANTITIES IV SCALE: NONE DATE: 1/4/06 DRAWN BY: RJS CHECKED BY: DDH TENG ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS

Vertical text on the left edge of the page containing project and drawing information.