

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	LIGHTING-	SURVEIL-	SIGNING	ROADWAY	LIGHTING	SURVEIL-	SIGNING	VILLAGE			
				ILLINOIS	ILLINOIS	LANCE ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS
				CONSTRUCTION TYPE CODE											
				J000-2A	Y030-1E	Y032-1F	Y002-1C	J000-2A	Y030-1E	Y032-1F	Y002-1C	Y000			
* M7030560	PAVEMENT MARKING TAPE, TYPE III 300MM	METER	49	0	0	0	0	49	0	0	0	0			
* M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	2210	708	0	0	0	1502	0	0	0	0			
M7040100	TEMPORARY CONCRETE BARRIER	METER	2264	1385	0	0	0	879	0	0	0	0			
M7040210	RELOCATE TEMPORARY CONCRETE BARRIER (SPECIAL)	METER	8617.4	3561.6	0	0	0	5055.8	0	0	0	0			
* M7200100	SIGN PANEL - TYPE 1	SQ M	23	0	0	0	23	0	0	0	0	0			
* M7200200	SIGN PANEL - TYPE 2	SQ M	4	0	0	0	4	0	0	0	0	0			
* M7200300	SIGN PANEL - TYPE 3	SQ M	154	0	0	0	154	0	0	0	0	0			
* M7230100	INSTALL EXISTING SIGN PANEL	SQ M	9	0	0	0	9	0	0	0	0	0			
* M7240330	REMOVE SIGN PANEL - TYPE 3	SQ M	3	0	0	0	3	0	0	0	0	0			
* M7270100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	KG	540	0	0	0	540	0	0	0	0	0			
* M7330020	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (1.37M X 1.60M)	METER	90.7	0	0	0	90.7	0	0	0	0	0			
* M7330030	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (1.53M X 2.14M)	METER	27	0	0	0	27	0	0	0	0	0			
* M7330500	OVERHEAD SIGN STRUCTURE WALKWAY	METER	66.6	0	0	0	66.6	0	0	0	0	0			
* M7340100	CONCRETE FOUNDATIONS	CU M	2.9	0	0	0	2.9	0	0	0	0	0			
* M7340200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU M	56.4	0	0	0	56.4	0	0	0	0	0			
* M7800605	EPOXY PAVEMENT MARKING - LINE 100MM	METER	8795.1	2707.1	0	0	0	6088	0	0	0	0			
* M7800610	EPOXY PAVEMENT MARKING - LINE 125MM	METER	2099.4	812.6	0	0	0	1286.8	0	0	0	0			
* M7800620	EPOXY PAVEMENT MARKING - LINE 200MM	METER	1245	0	0	0	0	1245	0	0	0	0			
* M7800625	EPOXY PAVEMENT MARKING - LINE 300MM	METER	272	0	0	0	0	272	0	0	0	0			
* M7802010	POLYUREA PAVEMENT MARKING TYPE I - LINE 100MM	METER	4552.4	4552.4	0	0	0	0	0	0	0	0			
* M7802030	POLYUREA PAVEMENT MARKING TYPE I - LINE 300MM	METER	173.4	173.4	0	0	0	0	0	0	0	0			
M7830100	PAVEMENT MARKING REMOVAL	SQ M	911	169	0	0	0	742	0	0	0	0			
* M8100260	CONDUIT IN TRENCH, 50MM DIA., PVC	METER	1029	0	0	0	0	0	1029	0	0	0			
* M8100300	CONDUIT IN TRENCH, 100MM DIA., PVC	METER	2974	0	0	126	0	0	104	2744	0	0			
* M8120120	CONDUIT EMBEDDED IN STRUCTURE, 50 MM DIA. GALVANIZED STEEL	METER	58	0	0	8	0	0	50	0	0	0			
* M8120130	CONDUIT EMBEDDED IN STRUCTURE, 65 MM DIA. GALVANIZED STEEL	METER	96	0	0	96	0	0	0	0	0	0			
* M8120230	CONDUIT EMBEDDED IN STRUCTURE, 50 MM DIA. PVC	METER	492	0	0	0	0	0	492	0	0	0			
* M8120270	CONDUIT EMBEDDED IN STRUCTURE, 100 MM DIA. PVC	METER	50	0	0	42	0	0	0	8	0	0			
* M8130203	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 300MM X 610MM X 200MM	EACH	4	0	0	0	0	0	0	4	0	0			
* M8131400	JUNCTION BOX, NON-METALLIC, EMBEDDED IN STRUCTURE, 525MM X 275MM X 200MM	EACH	19	0	0	0	0	0	19	0	0	0			
* M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	2673	0	0	582	0	0	719	1372	0	0			
* MX030063	STORM SEWER (WATER MAIN REQUIREMENTS) 300MM	METER	27	0	0	0	0	0	0	0	0	27			
* MX030110	REMOVE AND PLUG ABANDONED WATER MAIN	METER	235.2	0	0	0	0	0	0	0	0	235.2			

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA
- • • • 100% VILLAGE OF LANSING

©© 3F1Y-3C

Rev. 12-5-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
SUMMARY OF QUANTITIES

SCALE: _____ DRAWN BY: ACE/CAD
DATE: 07/05 CHECKED BY: TAE

AMERICAN
CONSULTING ENGINEERS

I:\Projects\800113.rdb 09/19/2006 01:22:57 PM