

# SUMMARY OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	LIGHTING-	SURVEIL-	SIGNING	ROADWAY	LIGHTING	SURVEIL-	SIGNING	VILLAGE			
				ILLINOIS	ILLINOIS	LANCE ILLINOIS	ILLINOIS	INDIANA	INDIANA	LANCE INDIANA	INDIANA	OF LANSING			
				CONSTRUCTION TYPE CODE											
				J000-2A	Y030-1E	Y032-1F	Y002-1C	J000-2A	Y030-1E	Y032-1F	Y002-1C	Y060			
X0324698	APPLY DUST SUPPRESSION AGENTS	UNIT	2885	1393	0	0	0	1492	0	0	0	0			
* X0520100	JUNCTION BOX, TYPE J	EACH	1	0	0	1	0	0	0	0	0	0			
X6020166	DRAINAGE STRUCTURES, TYPE 1 SPECIAL WITH TWO TYPE 20 FRAME AND GRATES	EACH	10	10	0	0	0	0	0	0	0	0			
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	.33	0	0	0	.67	0	0	0	0			
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	240	80	0	0	0	160	0	0	0	0			
X7015000	CHANGEABLE MESSAGE SIGN	CAL MD	16	8	0	0	0	8	0	0	0	0			
XX001443	STEEL PLATES TO BE INSTALLED ON DRAINAGE STRUCTURE	EACH	12	8	0	0	0	4	0	0	0	0			
* XX004760	FIRE HYDRANT WITH AUXILIARY VALVE, VALVE BOX AND TEE	EACH	1	0	0	0	0	0	0	0	0	1			
XX005949	DRAINAGE STRUCTURES TO BE CLEANED	EACH	25	0	0	0	0	25	0	0	0	0			
Z0002600	BAR SPLICERS	EACH	36	36	0	0	0	0	0	0	0	0			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	.33	0	0	0	.67	0	0	0	0			
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	24	24	0	0	0	0	0	0	0	0			
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	6	2	0	0	0	4	0	0	0	0			
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	8	0	0	0	0	8	0	0	0	0			
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	7	3	0	0	0	4	0	0	0	0			
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2	0	0	0	2	0	0	0	0			
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	0	0	0	0	1	0	0	0	0			
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	8	5	0	0	0	3	0	0	0	0			
<del>Z0076600</del>	<del>TRAINEEES</del>	<del>—HOUR—</del>	<del>0</del>	<del>0</del>	<del>0</del>	<del>0</del>	<del>0</del>	<del>0</del>	<del>0</del>	<del>0</del>	<del>0</del>	<del>0</del>			
* MX033637	BLIND FLANGE CAP, 600MM DIA	EACH	5	0	0	0	0	0	0	0	0	5			
* MX033668	DUCTILE IRON WATER MAIN RESTRAINED JOINT TYPE, 600MM	METER	35	0	0	0	0	0	0	0	0	35			
* MX033669	DUCTILE IRON WATER MAIN RESTRAINED JOINT TYPE, 150MM	METER	8	0	0	0	0	0	0	0	0	8			
* MX033670	DUCTILE IRON WATER MAIN RESTRAINED JOINT TYPE, 600MM IN STEEL CASING PIPE, 1050MM AUGURED	METER	93	0	0	0	0	0	0	0	0	93			
* M6111740	TAPPING VALVES AND SLEEVES, 600MM	EACH	2	0	0	0	0	0	0	0	0	2			
* MX033672	VALVE VAULTS, TYPE A, 2.1M DIA., TYPE 1 FRAME, CLOSED LID	EACH	2	0	0	0	0	0	0	0	0	2			
* MX033673	ABANDON WATER MAIN IN PLACE, 600MM	L SUM	1	0	0	0	0	0	0	0	0	1			
MX033582	LUG SYSTEM COMPLETE (SPECIAL) 14.4 METER	EACH	1	1	0	0	0	0	0	0	0	0			
MX033583	REINFORCED CONCRETE PIPE TEE, 1950MM PIPE WITH 300MM RISER	EACH	3	3	0	0	0	0	0	0	0	0			
MX033584	REINFORCED CONCRETE PIPE TEE, 1950MM PIPE WITH 450MM RISER	EACH	1	1	0	0	0	0	0	0	0	0			
MX033585	STORM SEWER REMOVAL, 1200MM X 600MM ELLIPTICAL	METER	62	0	0	0	0	0	0	0	0	62			
MX033581	BARRIER SUPPORT STRUCTURE FOR NOISE ABATEMENT WALL	METER	279.6	279.6	0	0	0	0	0	0	0	0			
M6380205	CONCRETE GLARE SCREEN, SPECIAL	METER	22.8	22.8	0	0	0	0	0	0	0	0			

△  
△  
△  
△  
△  
△

- SPECIALTY ITEMS
- 100% STATE
- 100% INDIANA
- 100% VILLAGE OF LANSING
- △ SFTY-3N

△ Rev. 12-5-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
I-80/94/US 6  
KINGERY-BORMAN EXPRESSWAY  
BURNHAM ROAD TO US 41  
**SUMMARY OF QUANTITIES**

SCALE \_\_\_\_\_ DATE 07/05

DRAWN BY ACE/CAD  
CHECKED BY TAE

**AMERICAN**  
CONSULTING ENGINEERS