

SUMMARY OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE. 80/94	SECTION 2626.2-R-2	COUNTY COOK/LAKE	TOTAL SHEETS 1207	SHEET NO. 11
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT _____		
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	LIGHTING-	SURVEIL-	SIGNING	ROADWAY	LIGHTING	SURVEIL-	SIGNING	VILLAGE		
				ILLINOIS	ILLINOIS	LANCE ILLINOIS	ILLINOIS	INDIANA	INDIANA	LANCE INDIANA	INDIANA	OF LANSING		
				CONSTRUCTION TYPE CODE										
				J000-2A	Y030-1E	Y032-1F	Y002-1C	J000-2A	Y030-1E	Y032-1F	Y002-1C	Y000		
* M7802012	POLYUREA PAVEMENT MARKING, TYPE 1 - LINE 125MM	METER	2415	2415	0	0	0	0	0	0	0	0		
* MX030510	CONDUIT ATTACHED TO STRUCTURE, 100MM DIA., PVC, SCHEDULE 80	METER	160	0	0	0	0	0	0	160	0	0		
* MX033638	CONDUIT, ENCASED, REINFORCED CONCRETE, 100MM DIA., PVC, 6 WIDE X 2 HIGH	METER	22	0	0	22	0	0	0	0	0	0		
* MX033545	CONDUIT EMBEDDED IN STRUCTURE, 30MM DIA., CNC, 4 WIDE BY 2 HIGH	METER	904	0	0	904	0	0	0	0	0	0		
* MX0310115	CONDUIT ENCASED, REINFORCED CONCRETE, 30MM DIA., CNC, 4 WIDE BY 2 HIGH	METER	200	0	0	200	0	0	0	0	0	0		
* MX033674	CONDUIT ENCASED, REINFORCED CONCRETE, 100MM DIA., PVC, 3 WIDE BY 1 HIGH	METER	29	0	0	29	0	0	0	0	0	0		
* MX033675	CONDUIT EMBEDDED IN STRUCTURE, 75MM DIA., GALVANIZED STEEL	METER	5	0	0	5	0	0	0	0	0	0		
* MX033582	SEWER OUTFALL SEPARATOR SYSTEM	L SUM	1	1	0	0	0	0	0	0	0	0		
MX033639	SLIP-ON FLAT BOTTOM CHECK VALVE 1950MM	EACH	1	1	0	0	0	0	0	0	0	0		
MX033640	SLIP-ON FLAT BOTTOM CHECK VALVE 600 MM	EACH	1	0	0	0	0	1	0	0	0	0		
* MX033691	PLANTING MIX FURNISH AND PLACE 900 MM	SQ M	159	159	0	0	0	0	0	0	0	0		
* MX033691	PAINT PAVEMENT MARKING - LINE 125 MM (SPECIAL)	METER	114.3	114.3	0	0	0	0	0	0	0	0		
MX033590	BORROW (INDIANA)	CU M	30895.6	0	0	0	0	30895.6	0	0	0	0		
MX033591	EXCAVATION COMMON (INDIANA)	CU M	7518.7	0	0	0	0	7518.7	0	0	0	0		
MX033686	EXCAVATION, UNCLASSIFIED (INDIANA)	CU M	3810.3	0	0	0	0	3810.3	0	0	0	0		
MX033642	SUBGRADE TREATMENT, TYPE 1A (INDIANA)	SQ M	62501	0	0	0	0	62501	0	0	0	0		
MX033592	SUBBASE FOR PCCP, (225) (INDIANA)	CU M	14062.7	0	0	0	0	14062.7	0	0	0	0		
MX033593	DENSE GRADED SUBBASE (INDIANA)	CU M	515.4	0	0	0	0	515.4	0	0	0	0		
MX033643	COMPACTED AGGREGATE, NO. 73 (INDIANA)	SQ M	1030	0	0	0	0	1030	0	0	0	0		
MX033644	QC/OA - PCCP, 400 MM (INDIANA)	SQ M	57226	0	0	0	0	57226	0	0	0	0		
MX033645	QC/OA - PCCP, 330 MM (INDIANA)	SQ M	3867	0	0	0	0	3867	0	0	0	0		
MX033647	PROFILOGRAPH, PCCP (INDIANA)	L SUM	1	0	0	0	0	1	0	0	0	0		
MX033594	D-1 CONTRACTION JOINT (INDIANA)	METER	11334	0	0	0	0	11334	0	0	0	0		
MX033595	TERMINAL JOINT (INDIANA)	METER	308	0	0	0	0	308	0	0	0	0		
MX033646	RETROFITTED TIE BARS (INDIANA)	EACH	370	0	0	0	0	370	0	0	0	0		
MX033620	IMPACT ATTENUATOR CR, W2, TL-3 (INDIANA)	EACH	4	0	0	0	0	4	0	0	0	0		
MX033596	BARRIER, CONCRETE, 1145 MM (INDIANA)	METER	263.8	0	0	0	0	263.8	0	0	0	0		
MX033597	BARRIER, CONCRETE, 1145 MM, MODIFIED (INDIANA)	METER	1033	0	0	0	0	1033	0	0	0	0		
MX033598	CONCRETE BARRIER, TRANSITION (INDIANA)	EACH	14	0	0	0	0	14	0	0	0	0		
MX033599	BARRIER DELINEATOR (INDIANA)	EACH	519	0	0	0	0	519	0	0	0	0		
MX033648	BARRIER, CONCRETE, 840 MM, MODIFIED (INDIANA)	METER	547	0	0	0	0	547	0	0	0	0		
MX033676	FENCE, CHAIN LINK, 1220 MM (INDIANA)	METER	2049	0	0	0	0	2049	0	0	0	0		

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA
- • • • 100% VILLAGE OF LANSING
- Δ SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41

SUMMARY OF QUANTITIES

SCALE _____ DATE 07/05

DRAWN BY ACE/CAD
CHECKED BY TAE

AMERICAN
CONSULTING ENGINEERS