

SCHEDULE OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY
ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE. 80/94	SECTION 2626.2-R-2	COUNTY COOK/LAKE	TOTAL SHEETS 1207	SHEET NO. 28
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS		FED. AID PROJECT
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

PAVEMENT REINFORCEMENT 360MM

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
SEE M4210360 CON REINF PCC PVT 360					41,475.0
TOTAL =					41,475

BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
7+328.070	3.300	-	7+475.000	3.300	484.9
TOTAL =					485

PAVEMENT REMOVAL

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
WESTBOUND					
6+814.721	3.300	-	7+090.000	3.300	908.4
7+090.000	14.100	-	7+125.000	14.100	493.5
7+125.000	26.900	-	7+228.678	26.800	2,783.8
7+228.678	26.800	-	7+300.652	28.700	1,997.3
7+300.652	28.700	-	7+330.701	31.000	897.0
7+330.701	31.000	-	7+379.000	30.400	1,482.8
7+379.000	26.200	-	7+598.844	23.400	5,452.1
7+598.844	24.900	-	7+750.000	22.900	3,612.6
7+750.000	22.900	-	7+950.000	19.600	4,250.0
EASTBOUND					
7+125.000	11.100	-	7+600.000	11.200	5,296.2
7+600.000	14.200	-	7+750.000	15.400	2,220.0
7+750.000	15.400	-	7+950.000	15.100	3,050.0
CONTRACT 62350 ACCIDENT INVESTIGATION SITE					
7+386.255	4.000	-	7+443.189	4.000	227.7
7+443.189	5.750	-	7+550.000	5.750	614.2
EXISTING PUMP STATION					
RIVER DRIVE (50% OF QTY)					
7+967.028	7.750	-	7+971.887	7.750	18.9
SEE MX030505 TEMP PAVT INTERSTATE					3,203.6
TOTAL =					36,900

PAVEMENT REMOVAL

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
INDIANA					
WESTBOUND					
7+950.000	19.600	-	7+990.100	19.600	786.0
7+990.100	14.900	-	8+190.770	14.900	2,990.0
8+255.980	15.000	-	8+405.200	16.800	2,372.6
8+595.030	23.100	-	8+726.650	24.000	3,099.7
8+777.730	21.400	-	8+888.820	23.100	2,471.8
8+888.820	15.000	-	9+250.000	15.000	5,417.7
9+250.000	11.000	-	9+395.341	11.000	1,598.8
RAMP A					
20+658.870	7.200	-	20+448.400	11.000	1,915.3
CD NORTH					
0+016.120	6.000	-	0+019.800	4.800	19.9
0+019.800	4.800	-	0+065.000	4.900	219.2
0+065.000	4.900	-	0+193.470	4.900	629.5
EASTBOUND					
7+950.000	15.100	-	8+197.410	15.000	3,723.5
8+262.520	15.000	-	8+419.680	18.500	2,632.4
8+603.000	12.500	-	8+617.932	12.500	186.7
8+617.932	18.700	-	8+732.270	18.700	2,138.1
8+781.900	21.000	-	8+936.700	23.400	3,436.6
8+936.700	15.000	-	9+250.000	15.000	4,699.5
9+250.000	11.000	-	9+375.000	11.000	1,375.0
9+382.167	0.900	-	9+650.000	0.900	241.0

RAMP I

29+985.750	7.500	-	30+210.900	10.300	2,003.8
30+210.900	4.900	-	30+329.240	4.900	579.9
CD SOUTH					
30+210.900	4.900	-	30+255.000	4.900	216.1
0+000.000	4.900	-	0+138.163	4.900	677.0
RIVER DRIVE (50% OF QTY)					
7+967.028	7.750	-	7+971.887	7.750	18.9
SEE MX030504 TEMP PAVT INTERSTATE					3,059.5
TOTAL =					46,508

DRIVEWAY PAVEMENT REMOVAL

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
PUMP STATION					
					36.7
TOTAL =					37

COMBINATION CURB AND GUTTER REMOVAL

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
7+589.300	25.43 LT	-	7+598.844	25.46 LT	9.50
TOTAL =					9.5

COMBINATION CURB AND GUTTER REMOVAL

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
INDIANA					
I-80/94/US 6					
8+042.920	18.00 LT	-	8+193.710	18.00 LT	150.80
8+246.160	18.00 LT	-	8+407.900	20.50 LT	161.80
8+585.580	22.00 LT	-	8+725.340	24.00 LT	139.80
8+769.240	24.70 LT	-	8+927.060	28.00 LT	157.90
8+781.900	23.50 RT	-	8+863.260	26.15 RT	81.40
HOHMAN ST					
79+982.631	6.30 LT	-	80+031.094	5.87 LT	48.50
79+967.354	6.27 RT	-	80+034.596	5.88 RT	67.20
HARRISON ST					
89+977.092	3.06 LT	-	90+050.000	3.28 LT	72.90
89+951.689	4.35 RT	-	90+038.566	4.18 RT	86.90
TOTAL =					967.2

SIDEWALK REMOVAL

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
PUMP STATION REMOVAL					
					18.3
TOTAL =					18

SIDEWALK REMOVAL

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
INDIANA					
HOHMAN AVE					
79+953.640	2.000	-	79+964.700	1.800	21.0
79+955.400	1.500	-	79+962.500	1.500	10.7
79+971.800	1.550	-	80+031.150	1.550	92.0
79+957.190	1.520	-	80+029.500	1.520	109.9
TOTAL =					234

APPROACH SLAB REMOVAL

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
INDIANA					
HOHMAN AVE BRIDGE					
8+190.767	17.700	-	8+197.406	17.700	117.5
8+197.406	36.200	-	8+210.100	0.000	229.8
8+243.141	0.000	-	8+256.000	36.200	232.7
8+256.000	17.700	-	8+262.516	17.700	115.3
LITTLE CALUMET RIVER BRIDGE					
8+405.197	20.500	-	8+411.450	20.800	129.1
8+411.450	20.800	-	8+425.972	0.000	151.0
8+419.683	12.500	-	8+425.972	12.500	78.6
8+425.972	12.500	-	8+434.381	0.000	52.6
8+580.636	0.000	-	8+593.246	34.700	218.8
8+593.246	34.700	-	8+595.030	34.700	61.9
8+595.030	12.100	-	8+603.028	12.100	96.8
HARRISON AVE BRIDGE					
8+726.645	23.300	-	8+731.235	23.300	106.9
8+732.059	46.600	-	8+738.331	21.800	214.5
8+738.331	21.800	-	8+744.537	0.000	67.6
8+764.168	0.000	-	8+777.350	48.300	318.3
8+777.350	25.400	-	8+782.445	25.400	129.4
TOTAL =					2,321

CONCRETE BARRIER REMOVAL

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
6+814.721	0.00 RT	-	7+547.500	0.00 RT	732.8
TOTAL =					733

CONCRETE BARRIER REMOVAL

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
INDIANA					
9+250.000	0.00 RT	-	9+356.500	0.00 RT	106.5
9+382.167	0.00 RT	-	9+650.000	0.00 RT	267.8
9+105.100	22.20 LT	-	9+394.500	22.20 LT	289.4
9+192.859	21.20 RT	-	9+200.800	21.20 RT	7.9
TOTAL =					672

PAVED SHOULDER REMOVAL

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
INSIDE SHOULDER					
WESTBOUND					
6+814.721	2.200	-	7+125.000	2.200	682.6
7+125.000	2.200	-	7+400.000	2.300	618.8
7+400.000	2.300	-	7+600.000	2.300	460.0
EASTBOUND					
6+814.721	2.200	-	7+125.000	2.200	682.6
7+125.000	2.200	-	7+400.000	2.200	605.0
7+400.000	2.200	-	7+600.000	2.200	440.0
OUTSIDE SHOULDER					
EASTBOUND					
7+125.000	3.500	-	7+400.000	3.500	962.5
7+400.000	3.500	-	7+750.000	3.700	1,260.0
7+750.000	3.600	-	7+950.000	3.400	700.0
TOTAL =					6,412

PAVED SHOULDER REMOVAL

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
INDIANA					
INSIDE SHOULDER					
9+250.000	3.600	-	9+395.341	3.600	523.2
9+250.000	3.600	-	9+375.000	3.600	450.0
OUTSIDE SHOULDER					
WESTBOUND					
7+990.100	4.500	-	8+042.920	4.700	243.0
8+042.920	2.800	-	8+190.770	3.100	436.2
8+255.980	3.100	-	8+405.200	3.400	485.0
8+777.730	3.900	-	8+927.060	3.900	582.4
9+105.114	6.800	-	9+395.341	6.700	1,959.0
CD NORTH					
0+019.600	1.250	-	0+044.230	5.400	81.9
0+044.230	3.000	-	0+193.470	3.500	485.0
9+105.114					