ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	362A
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 62114 INDOT DES. NO. 0100987

SIGNING SCHEDULE - GROUND MOUNTED SIGNS

								ILLINOIS SIGN PANELS		STEEL SIGN SUPPORT			WOOD SIGN SUPPORT				INDIANA SIGN PANELS			INDIANA STEEL SIGN SUPPORT						
SIGN NO.	STATION	LT/RT	"AA" (M)	"BB" (M)	WIDTH (M)	DEPTH (M)	EXIST TO REMAIN (Y)	M7200100 INSTALL TYPE 1 (SQ. M)	M7200200 INSTALL TYPE 2 (SQ. M)	P1 (M)	M7280100 PAY LENGTH (M)	TUBULAR TF SIN POST (EACH)	P1 (M)	M7300100 PAY LENGTH (M)	73700100 REM CONC FDN-GR MT SUPPORT (M)	73700200 REM CONC FDN-GR MT (M)	S EN LEN LEG 203 (IN) (SQ M)	S EN LEN LEG 254 (IN) (SQ M)	S EN LEN LEG 318 (IN) (SQ M)	P1 (M)	SIGN POST WOOD (IN) (M.)	SIGN POST SQ T1 REINF AN BASE (M.)	SIGN POST SQ T2 REINF AN BASE (M.)	SIGN POST SQ T1 UNREINF AN BASE (M.)	SIGN POST SQ T2 UNREINF AN BASE (M.)	NOTES
IL80-53NW	6+949	RT			1.05	0.45		0.47																		MOUNTED TO NOISE WALL
IL80-53ANW					1.05	0.45		0.47																		MOUNTED TO BACK OF NOISE WALL
IL80-54NW					1.20	0.30		0.36																		MOUNTED TO NOISE WALL DOOR
IL80-54ANW					1.20	0.30		0.36																		MOUNTED TO NOISE WALL DOOR
IL80-55NW	6+973	LT			1.05	0.45		0.47																		MOUNTED TO NOISE WALL
IL80-55ANW					1.05	0.45		0.47																		MOUNTED TO BACK OF NOISE WALL
IL80-56NW					0.45	0.30		0.14																		MOUNTED TO NOISE WALL DOOR
IL80-56ANW					0.45	0.30		0.14																		MOUNTED TO NOISE WALL DOOR
IL80-57NW	7+074	RT			1.05	0.45		0.47																		MOUNTED TO NOISE WALL
IL80-57ANW					1.05	0.45		0.47																		MOUNTED TO BACK OF NOISE WALL
IL80-58NW					1.20	0.30		0.36																		MOUNTED TO NOISE WALL DOOR
IL80-58ANW					1.20	0.30		0.36																		MOUNTED TO NOISE WALL DOOR
IL80-59NW	7+926	LT			1.05	0.45		0.47																		MOUNTED TO NOISE WALL
IL80-59ANW					1.05	0.45		0.47																		MOUNTED TO BACK OF NOISE WALL
IL80-60NW					0.45	0.30		0.14																		MOUNTED TO NOISE WALL DOOR
IL80-60ANW					0.45	0.30		0.14																		MOUNTED TO NOISE WALL DOOR
TOTALS								22.21	4.32			4.00	0.00	0.00	0.00	0.00	0.00		0.00			0.00	0.00	0.00	0.00	

NOTE:
"AA" = DISTANCE FROM EDGE OF TRAVELED WAY
"BB" = DISTANCE FROM BOTTOM OF SIGN TO PAVEMENT

SIGN LOCATION SUBJECT TO MINOR RELOCATION IN FIELD AT TIME OF CONSTRUCTION AS DIRECTED BY THE ENGINEER

REVISIONS	
NAME	DATE
NEW SHEET - JBS	11-14-05

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41

SIGNING SCHEDULE

SCALE DRAWN BY ACE/CAD
DATE 07/05 CHECKED BY TAE

AMERICAN CONSULTING ENGINEERS