ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	365
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 62114 INDOT DES. NO. 0100987

SIGNING SCHEDULE - BREAKAWAY & OVERHEAD MOUNTED

			SIGN PANELS								INDIANA			BREAKAWAY STRUCTURAL STEEL SUPPORT					ILLINOIS OVERHEAD SIGN SUPPORT						INDIANA OVERHEAD SIGN SUPPORT					
SIGN NO.	STATION	LT/RT	"AA" (M.)	"BB" (M.)	WIDTH (M)	DEPTH (M)	EXIST TO REMAIN (Y)	M7200300 INSTALL TYPE 3 (SQ. M)	M7230100 INSTALL EX SIGN PANEL (SQ. M)	M7240330 REMOVE TYPE 3 (SQ. M)	SIGN PAN LEGEND (IN) (SQ. M.)	73600100 REMOVE SPAN (EACH)	73700300 REM CONC FND-OVHD (EACH)	POST SIZE	P1 (M.)	P2 (M.)	M7270100 STR STL SIN SUP BA (KG)	FDN DIA. (M.)	M7330010 TYPE I-A 1.22Mx1.37M (M)	M7330020 TYPE II-A 1.22Mx1.60M (M)	M7330030 TYPE III-A 1.53Mx2.14M (M)	M7330500 WALKWAY (M)	M7340100 CONC FND (CU M)	M7340200 DRILLED SHAFT CONC FND (CU M)	SP OVHD S STR B T (IN) (M.)	SP O S STR BT SP (IN) (M.)	WLKWY HDRL LT A (IN) (M.)	CONC SIN FDN (IN) TYPE	CONC SIN FDN (IN) (CU. M.)	RE STL SIGN FDN (IN) (KG.)
IL80-090H	6+952	LT			4.50	3.76		16.92												30.4		14.1		14.6						
IL80-100H					7.20	3.76		27.07																						
IL80-250H	7+240	RT			4.50	4.66		20.97												26.8		15.5		12.4						
IL80-260H					6.60	4.36		28.78																						
IL80-310H	7+313	LT			8.00	3.00		24.00												33.4		19.8		12.9						
IL80-320H					7.20	3.76		27.07																						
IL80-41BS	7+591	LT	4.62	8.2	4.27	2.10			8.97					W150X22	3.7	3.6	224.0	0.6					1.8							
IL80-48DMS	7+946	LT																			26.8	17.2		16.5						
I80-53BS	10+295	LT	4.8	7.0	3.50	2.70		9.45						W200X27	4.5	4.3	316.0	0.6					1.1							
IGI0-1	7+969	CL			7.80	4.88					38.06															27.885		LT FDN	16.4	2300
																												RT FDN	8.7	1880
IGD0-01A	8+265	CL			6.60	3.97					26.17														26.83			LT FDN	16.8	2240
					2.10	0.61					1.28																			
IGD0-01B					5.10	3.97					20.22																			
					1.80	0.61					1.10																			
IGD0-02A	8+375	CL			4.50	3.05					13.73														26.83			LT FDN	16.6	2200
					3.00	0.61					1.83																			
IGD0-02B					8.10	3.05					24.71																			
					2.70	0.61					1.65																			
IGD0-03A	8+933	CL			6.60	3.97					26.17														26.83			LT FDN	17	2360
					2.10	0.61					1.28																			
IGD0-03B					5.10	3.97					20.22																			
					1.80	0.61					1.10																			
IGD0-04A	9+202	CL			4.50	3.66					16.47														20			LT FDN	16.3	2290
IGD0-04B					4.50	3.66					16.47																	RT FDN	10.7	1860
IGDE-01	9+063	RT			1.20	2.40	N			2.88																				
IGD0E-01A	9+202	RT			4.50	3.00	N					1.0	2.0																	
IGD0E-01B					4.50	3.00	N																							
IGD0E-02A	9+398	LT											1																	
TOTALS								154.26	8.97	2.88	210.46	1	3				540		0.0	90.7	26.8	66.6	2.9	56.4	100.5	27.9	0.0		102.5	15130.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41

OVERHEAD SIGNING SCHEDULE

SCALE DRAWN BY ACE/CAD
DATE 07/05 CHECKED BY TAE

AMERICAN CONSULTING ENGINEERS