

62912

|                       |             |            |             |                 |           |
|-----------------------|-------------|------------|-------------|-----------------|-----------|
| F.A.P. RTE.           | F.A.U. RTE. | SECTION    | COUNTY      | TOTAL SHEETS    | SHEET NO. |
| 343                   | 1453        | 2005-005BR | COOK/DUPAGE | 14              | 3         |
| FED. ROAD DIST. NO. 1 |             | ILLINOIS   |             | HIGHWAY PROJECT |           |

| SUMMARY OF QUANTITIES |   |        | URBAN<br>X080-2A |                            | CONSTRUCTION TYPE CODE SFTY-2A |  |  |  |
|-----------------------|---|--------|------------------|----------------------------|--------------------------------|--|--|--|
| CODE NO               | ITEM  | UNIT   | TOTAL QUANTITIES | LOC. 1<br>COOK<br>016-0525 | LOC. 2<br>DUPAGE<br>022-0084   |  |  |  |
| 44001000              | BITUMINOUS CONCRETE SURFACE REMOVAL                         | SQ YD  | 110.6            | 10.6                       | 100                            |  |  |  |
| 50102400              | CONCRETE REMOVAL  | CU YD  | 22.7             | 5.9                        | 16.8                           |  |  |  |
| 50300255              | CONCRETE SUPERSTRUCTURE                                     | CU YD  | 32.2             | 13.5                       | 18.7                           |  |  |  |
| 50300300              | PROTECTIVE COAT   | SQ YD  | 117.3            | 44.7                       | 72.6                           |  |  |  |
| 50400405              | PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)         | SQ FT  | 569              | 569                        |                                |  |  |  |
| 50400505              | PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)         | SQ FT  | 2169             |                            | 2169                           |  |  |  |
| 50500405              | FURNISHING AND ERECTING STRUCTURAL STEEL                    | POUND  | 1260             |                            | 1260                           |  |  |  |
| 50800205              | REINFORCEMENT BARS, EPOXY COATED                            | POUND  | 3560             | 1410                       | 2150                           |  |  |  |
| 50900905              | REMOVING AND RE-ERECTING EXISTING RAILING                   | FOOT   | 78               | 78                         |                                |  |  |  |
| 58100200              | WATERPROOFING MEMBRANE SYSTEM                               | SQ YD  | 358.8            | 51.8                       | 305                            |  |  |  |
| 58300100              | PORTLAND CEMENT MORTAR FAIRING COURSE                       | FOOT   | 1487             | 268                        | 1219                           |  |  |  |
| 67000400              | ENGINEER'S FIELD OFFICE, TYPE A                             | CAL MD | 1                | 0.5                        | 0.5                            |  |  |  |
| 67100100              | MOBILIZATION  | L SUM  | 1                | 0.5                        | 0.5                            |  |  |  |
| 70102630              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601             | L SUM  | 1                |                            | 1                              |  |  |  |
| 70102632              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701602             | L SUM  | 1                | 1                          |                                |  |  |  |
| 70102640              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601             | L SUM  | 1                | 0.5                        | 0.5                            |  |  |  |
| 70300520              | PAVEMENT MARKING TAPE, TYPE III 4"                          | FOOT   | 80               |                            | 80                             |  |  |  |
| 70400100              | TEMPORARY CONCRETE BARRIER                                  | FOOT   | 760              | 120                        | 640                            |  |  |  |
| 70400200              | RELOCATE TEMPORARY CONCRETE BARRIER                         | FOOT   | 760              | 120                        | 640                            |  |  |  |
| * 78000100            | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS        | SQ FT  | 100              | 100                        |                                |  |  |  |
| * 78000200            | THERMOPLASTIC PAVEMENT MARKING - LINE 4"                    | FOOT   | 1640             | 200                        | 1440                           |  |  |  |
| X0320047              | REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS | SQ FT  | 2796             | 575                        | 2221                           |  |  |  |
| X0322467              | TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE              | SQ FT  | 96               | 48                         | 48                             |  |  |  |
| X4066424              | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50 | TON    | 41.8             | 7.5                        | 34.3                           |  |  |  |
| Z0001900              | ASBESTOS BEARING PAD REMOVAL                                | EACH   | 30               | 2                          | 28                             |  |  |  |

| SUMMARY OF QUANTITIES |   |      | URBAN<br>X080-2A |                            | CONSTRUCTION TYPE CODE SFTY-2A |  |  |  |
|-----------------------|---|------|------------------|----------------------------|--------------------------------|--|--|--|
| CODE NO               | ITEM  | UNIT | TOTAL QUANTITIES | LOC. 1<br>COOK<br>016-0525 | LOC. 2<br>DUPAGE<br>022-0084   |  |  |  |
| Δ Z0030240            | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2 | EACH | 4                | 2                          | 2                              |  |  |  |
| Δ Z0030340            | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2  | EACH | 2                | 1                          | 1                              |  |  |  |

Δ SFTY-3N  
\* SPECIALTY ITEMS

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

4/15/2005 11:08:38 AM