

ROUTE NO. SECTION SHEET NO. 4 TOTAL SMEETS Cook 14 10 ILLINOIS FED. AID PROJECT

4 SHEETS

Contract Number: 62912

Notes:

All Posts shall be normal to parapet.

All joints in rail shall be spliced per detail.

Provide 1-1/8" and 2-1/6" Aluminum Shims for 25% of the Posts. Rail elements shall be parallel to Grade-high spots will be ground and low spots shimmed.

This work shall be paid for at the contract unit price per foot for Removing and Re-erecting Existing Railing.

Horizontal rail element & rail posts shown are for information only.

ALUMINUM RAILING DETAIL

F.A.P. RT. 343 COOK COUNTY SN 016-0525