

<b>ROUTE</b>	<b>SECTION</b>	<b>COUNTY</b>	<b>TOTAL SHEETS</b>	<b>SHEET NUMBER</b>
FAP 342	530CRC-PP	COOK	16	6

CONTRACT 62962

**NORTHBOUND IL RTE. 53 EXTENSION**

PATCH LOCATION NUMBER	STATION	LANE	Northbound			TYPE
			SIZE (L X W)	AREA (SQ. YD.)		
1	445+17	3	265 x 12	353.3	IV	
2	444+50	1	100 x 12	133.3	IV	
3	444+50	2	100 x 12	133.3	IV	
4			x			
5	447+67	1	50 x 6	33.3	IV	
6	448+50	1	40 x 12	53.3	IV	
7			x			
8	453+40	2	40 x 12	53.3	IV	
9	453+40	3	40 x 12	53.3	IV	
10	454+40	3	30 x 12	40.0	IV	
11	458+23	3	15 x 12	20.0	III	
12	462+79	2	8 x 12	10.7	II	
12A	462+79	3	8 x 12	10.7	II	
13	463+50	2	20 x 12	26.7	IV	
14	466+61	1	12 x 12	16.0	III	
15	466+67	2	42 x 12	56.0	IV	
16	469+95	1	20 x 12	26.7	IV	
17	469+95	2	20 x 12	26.7	IV	
18	471+55	2	20 x 12	26.7	IV	
19	471+53	1	6 x 12	8.0	II	
20	471+78	1	6 x 12	8.0	II	
21	474+77	2	15 x 12	20.0	III	
22	475+54	1	8 x 12	10.7	II	
23	475+96	2	12 x 12	16.0	III	
24	476+47	2	25 x 12	33.3	IV	
25	477+17	2	15 x 6	10.0	II	

PATCH LOCATION NUMBER	STATION	LANE	Northbound			TYPE
			SIZE (L X W)	AREA (SQ. YD.)		
26	478+00	2	30 x 12	40.0	IV	
27	479+25	2	40 x 6	26.7	IV	
28	479+37	1	15 x 12	20.0	III	
29	479+79	2	8 x 12	10.7	II	
30	480+97	1	6 x 12	8.0	II	
31	481+52	2	15 x 12	20.0	III	
32	482+02	1	8 x 12	10.7	II	
33	482+62	1	35 x 12	46.7	IV	
34	482+62	2	35 x 12	46.7	IV	
35	483+74	1	8 x 12	10.7	II	
36	486+13	3/Ramp*	12 x 12	16	III	
37	486+09	2	8 x 12	10.7	II	
38	486+58	1	20 x 12	26.7	IV	
39	486+58	2	20 x 12	26.7	IV	
40	486+85	1	10 x 12	13.3	II	
41	487+60	1	30 x 12	40.0	IV	
42	489+45	1	10 x 12	13.3	II	
43	489+45	2	10 x 12	13.3	II	
44	489+76	1	12 x 12	16.0	III	
45	489+76	2	12 x 12	16.0	III	
46	491+59	1/Ramp*	12 x 12	16.0	II	
47	491+60	2/Ramp*	12 x 12	16.0	II	

\* SEE JOINT DETAILS (SHEET #11). THE COST OF PAVEMENT RELIEF JOINT SHALL BE INCIDENTAL TO CLASS A PATCHING.

- CENTER LINE OF IL RTE. 68 (DUNDEE) : STA. 435+44
- ALL STATIONINGS ARE CENTER OF EACH PATCHING LOCATIONS.

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**IL ROUTE 53 EXTENSION  
PAVEMENT PATCHING SCHEDULE  
1 OF 2**