# SCHEDULE OF QUANTITIES

## 70400100 TEMPORARY CONCRETE BARRIER

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | FOOT |
|---|---|---|---|---|---|
| US ROUTE 20 (HDR SECTION) | | | | | |
| EASTBOUND US ROUTE 20 - STAGE II | | | | | |
| 1704+50.0 | | | 1710+00.0 | | 550.0 |
| 1853+58.0 | | | 1866+70.5 | | 1312.5 |
| | | | SUB-TOTAL = | | 1862.5 |
| US ROUTE 20 (V3 SECTION) | | | | | |
| STD. 701402 | | | | | 1500 |
| WORKZONE | | | | | 490 |
| | | | SUB-TOTAL = | | 1990.0 |
| | | | TOTAL = | | 3852.5 |

## 70400200 RELOCATE TEMPORARY CONCRETE BARRIER

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | FOOT |
|---|---|---|---|---|---|
| US ROUTE 20 (HDR SECTION) | | | | | |
| EASTBOUND US ROUTE 20 - STAGE III | | | | | |
| 1846+23.0 | | | 1856+48.0 | | 1025.0 |
| EASTBOUND US ROUTE 20 - STAGE IV | | | | | |
| 1846+20.0 | | | 1866+70.0 | | 2050.0 |
| | | | TOTAL = | | 3075.0 |

## 72000200 SIGN PANEL - TYPE 2

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | SQ FT |
|---|---|---|---|---|---|
| US ROUTE 20 (HDR SECTION) | | | | | |
| EASTBOUND | | | | | |
| EB1 | | | | | 15.1 |
| EB2 | | | | | 15.1 |
| EB3 | | | | | 15.1 |
| WESTBOUND | | | | | |
| WB1 | | | | | 15.1 |
| WB2 | | | | | 15.1 |
| WB3 | | | | | 15.1 |
| | | | TOTAL = | | 91.0 |

## 72000300 SIGN PANEL - TYPE 3

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | SQ FT |
|---|---|---|---|---|---|
| US ROUTE 20 (HDR SECTION) | | | | | |
| EASTBOUND | | | | | |
| EB1 | | | | | 145.7 |
| EB2 | | | | | 143.8 |
| EB3 | | | | | 156.9 |
| EB4 | | | | | 26.2 |
| EB5 | | | | | 62.3 |
| WESTBOUND | | | | | |
| WB1 | | | | | 146.7 |
| WB2 | | | | | 143.8 |
| WB3 | | | | | 155.9 |
| WB4 | | | | | 26.2 |
| WB5 | | | | | 62.3 |
| IL ROUTE 75 | | | | | |
| 75N1 | | | | | 274.9 |
| 75N2 | | | | | 138.2 |
| 75S1 | | | | | 265.2 |
| 75S2 | | | | | 160.5 |
| | | | TOTAL = | | 1909.0 |

## 72400100 REMOVE SIGN PANEL ASSEMBLY - TYPE A

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | EACH |
|---|---|---|---|---|---|
| IL ROUTE 75 (HDR SECTION) | | | | | |
| STA. 32+68 NB | | | | | 1 |
| STA. 39+49 SB | | | | | 1 |
| | | | SUB-TOTAL = | | 2 |
| US ROUTE 20 (V3 SECTION) | | | | | |
| STA. 1969+25.45 WB | | | | | 1 |
| STA. 1970+75.96 WB | | | | | 1 |
| STA. 1972+24.87 WB | | | | | 1 |
| STA. 1973+74.83 WB | | | | | 1 |
| STA. 1975+24.85 WB | | | | | 1 |
| | | | SUB-TOTAL = | | 5 |
| | | | TOTAL = | | 7 |

## 72400200 REMOVE SIGN PANEL ASSEMBLY - TYPE B

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | EACH |
|---|---|---|---|---|---|
| US ROUTE 20 (HDR SECTION) | | | | | |
| STA. 1824+91 EB | | | | | 1 |
| STA. 1850+91 EB | | | | | 1 |
| STA. 1853+89 WB | | | | | 1 |
| STA. 1887+77 WB | | | | | 1 |
| | | | SUB-TOTAL = | | 4 |
| | | | TOTAL = | | 4 |

## 72700100 STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | POUNDS |
|---|---|---|---|---|---|
| US ROUTE 20 (HDR SECTION) | | | | | |
| EAST BOUND | | | | | |
| 1772+42 RT | 2 | W10X22 | SIGN PANEL EB1 | | 1188 |
| 1798+82 RT | 2 | W10X26 | SIGN PANEL EB2 | | 1508 |
| 1825+22 RT | 2 | W10X26 | SIGN PANEL EB3 | | 1404 |
| WEST BOUND | | | | | |
| 1914+64 LT | 2 | W10X26 | WB1 | | 1612 |
| 1888+24 LT | 2 | W10X26 | WB2 | | 1508 |
| 1861+84 LT | 2 | W10X26 | WB3 | | 1404 |
| IL ROUTE 75 | | | | | |
| 31+00 RT | 3 | W14X30 | 75N1 | | 2790 |
| 43+50 RT | 2 | W10X26 | 75N2 | | 1404 |
| 50+00 LT | 3 | W10X26 | 75S1 | | 2262 |
| 36+50 LT | 2 | W10X26 | 75S2 | | 1380 |
| RAMP BC | | | | | |
| 117+50 RT | 2 | W6X15 | SIGN PANEL WB5 | | 615 |
| RAMP AD | | | | | |
| 317+50 RT | 2 | W6X15 | SIGN PANEL EB5 | | 735 |
| | | | | TOTAL = | 17810 |

## 73000100 WOOD SIGN SUPPORT

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | FOOT |
|---|---|---|---|---|---|
| US ROUTE 20 (HDR SECTION) | | | | | |
| EASTBOUND | | | | | |
| 1832+00 RT | | | | | 34 |
| WESTBOUND | | | | | |
| 1855+00 LT | | | | | 36 |
| | | | TOTAL = | | 70 |

## 73200100 CONCRETE FOUNDATIONS FOR WOOD SIGN SUPPORT

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | EACH |
|---|---|---|---|---|---|
| US ROUTE 20 (HDR SECTION) | | | | | |
| EASTBOUND | | | | | |
| 1832+00 RT | | | SIGN PANEL EB4 | | 2 |
| WESTBOUND | | | | | |
| 1855+00 LT | | | SIGN PANEL WB4 | | 2 |
| | | | TOTAL = | | 4 |

## 73400200 DRILLED SHAFT CONCRETE FOUNDATIONS

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | CU YD |
|---|---|---|---|---|---|
| US ROUTE 20 (HDR SECTION) | | | | | |
| EAST BOUND | | | | NO. OF POSTS | |
| 1772+42 RT | W10X22 | | SIGN PANEL EB1 | 2 | 2.4 |
| 1798+82 RT | W10X26 | | SIGN PANEL EB2 | 2 | 2.4 |
| 1825+22 RT | W10X26 | | SIGN PANEL EB3 | 2 | 2.4 |
| WEST BOUND | | | | | |
| 1914+64 LT | W10X26 | | WB1 | 2 | 2.4 |
| 1888+24 LT | W10X26 | | WB2 | 2 | 2.4 |
| 1861+84 LT | W10X26 | | WB3 | 2 | 2.4 |
| IL ROUTE 75 | | | | | |
| 31+00 RT | W14X30 | | 75N1 | 3 | 4.2 |
| 43+50 RT | W10X26 | | 75N2 | 2 | 2.4 |
| 50+00 LT | W10X26 | | 75S1 | 3 | 3.6 |
| 36+50 LT | W10X22 | | 75S2 | 2 | 2.4 |
| RAMP BC | | | | | |
| 117+50 RT | W6X15 | | SIGN PANEL WB5 | 2 | 1.4 |
| RAMP AD | | | | | |
| 317+50 RT | W6X15 | | SIGN PANEL EB5 | 2 | 1.4 |
| | | | | TOTAL | 29.8 |

## 78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | FOOT |
|---|---|---|---|---|---|
| US ROUTE 20 (HDR SECTION) | | | | | |
| STA. 1827+06.49 TO STA. 1829+14.51 | | | | 51' LT TO 55' LT | 53 |
| STA. 1855+33.81 TO STA. 1858+89.34 | | | | 51 'LT | 356 |
| TOTAL US ROUTE 20 - W.B. | | | | | 409 |
| US ROUTE 20 - E.B. | | | | | |
| STA. 1828+17.27 TO STA. 1831+71.01 | | | | 51' RT | 354 |
| STA. 1858+53.81 TO STA. 1859+92.62 | | | | 55' RT TO 51' RT | 35 |
| TOTAL US ROUTE 20 - E.B. | | | | | 389 |
| RAMP BC | | | | | |
| STA. 103+00 TO STA. 106+63 | | | | 16' LT | 363 |
| TOTAL RAMP BC | | | | | 363 |
| RAMP DB | | | | | |
| STA. 213+02 TO STA. 216+43 | | | | 16' LT | 341 |
| TOTAL RAMP DB | | | | | 341 |
| RAMP AD | | | | | |
| STA. 303+00 TO STA. 306+64 | | | | 16' LT | 364 |
| TOTAL RAMP AD | | | | | 364 |
| RAMP CA | | | | | |
| STA. 411+86 TO STA. 414+95 | | | | 16' LT | 309 |
| TOTAL RAMP CA | | | | | 309 |
| | | | | TOTAL = | 1786 |

## 78003130 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"

| STATION | WIDTH(FT) | - | STATION | WIDTH(FT) | FOOT |
|---|---|---|---|---|---|
| U.S. 20 - W.B. (HDR SECTION) | | | | | |
| STA. 1697+00 TO STA. 1842+10 | | | | 39' LT | 3627 |
| STA. 1844+49 TO STA. 1904+40 | | | | 39' LT | 1498 |
| | | | | TOTAL U.S. 20 - W.B. | 5125 |
| U.S. 20 - E.B. | | | | | |
| STA. 1702+00 TO STA. 1710+00 | | | | 39' RT | 200 |
| | | | | TOTAL U.S. 20 - E.B. | 200 |
| | | | | SUB-TOTAL | 5325 |
| US ROUTE 20 (V3 SECTION) | | | | | |
| SKIP-DASH, 2' PAINT = 6' SPACE | | | | | |
| STA. 1914+41 TO 1998+81 WB LT | | | | | 2,110 |
| | | | | TOTAL = | 7435 |

## 78008200 POLYUREA PAVEMENT MARKING, TYPE I - LETTERS AND SYMBOLS

| STATION | WIDTH(FT) | - | STATION | OFFSET | SQ FT |
|---|---|---|---|---|---|
| IL ROUTE 75 (HDR SECTION) | | | | | |
| STA. 35+75 | | | | LT | 36.4 |
| STA. 38+25 | | | | LT | 36.4 |
| STA. 41+40 | | | | RT | 36.4 |
| STA. 43+90 | | | | RT | 36.4 |
| TOTAL RAMP IL ROUTE 75 | | | | | 146 |
| | | | | TOTAL = | 146 |

| REVISIONS | |
|---|---|
| NAME | DATE |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

US ROUTE 20

SCALE: VERT. HORIZ.

DATE 10/28/05

DRAWN BY DTE

CHECKED BY JAM