

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	*	STEPHENSON	290	37
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* 177-3,4,4-1-1				

V3 SCHEDULE

Station	Earth Excavation Cu Yd	Earth Exc Adjusted for Shrinkage Cu	Embankment Cu Yd	Earthwork Balance Waste (+) or Shortage (-)
1915+00.00	66	49	18	32
1916+00.00	66	49	18	32
1917+00.00	66	49	18	32
1918+00.00	66	49	18	32
1919+00.00	66	49	18	32
1920+00.00	66	49	18	32
1921+00.00	66	49	18	32
1922+00.00	66	49	18	32
1923+00.00	66	49	18	32
1924+00.00	66	49	18	32
1925+00.00	66	50	18	32
1926+00.00	66	50	18	32
1927+00.00	67	50	18	32
1928+00.00	66	50	18	32
1929+00.00	68	51	23	28
1930+00.00	67	50	18	33
1931+00.00	67	50	18	32
1932+00.00	67	50	19	31
1933+00.00	67	50	19	31
1934+00.00	67	50	19	31
1935+00.00	67	50	18	32
1936+00.00	67	50	19	31
1937+00.00	67	50	19	31
1938+00.00	67	50	18	32
1939+00.00	66	50	18	32
1940+00.00	68	51	24	27
1941+00.00	67	50	18	33
1942+00.00	66	50	18	32
1943+00.00	68	51	22	30
1944+00.00	70	53	23	29
1945+00.00	72	54	24	30
1946+00.00	72	54	24	30
1947+00.00	72	54	23	31
1948+00.00	94	71	21	50
1949+00.00	72	54	23	31
1950+00.00	72	54	24	30
1951+00.00	72	54	25	29
1952+00.00	73	54	27	28
1953+00.00	73	54	27	27
1954+00.00	73	54	26	28
1955+00.00	72	54	26	29
1956+00.00	73	54	27	28
1957+00.00	73	54	24	30
1958+00.00	73	54	27	28
1959+00.00	73	54	25	29
1960+00.00	73	54	25	30
1961+00.00	72	54	25	29
1962+00.00	72	54	26	29
1963+00.00	72	54	24	30
1964+00.00	73	54	25	29
1965+00.00	72	54	109	-55
1966+00.00	158	118	37	82
1967+00.00	124	93	78	15
1968+00.00	229	172	25	146
1969+00.00	239	179	24	156
1970+00.00	210	158	25	133
1971+00.00	219	164	15	149
1972+00.00	275	206	9	197
1973+00.00	476	357	9	348

Station	Earth Excavation Cu Yd	Earth Exc Adjusted for Shrinkage Cu	Embankment Cu Yd	Earthwork Balance Waste (+) or Shortage (-)
1974+00.00	401	301	9	292
1975+00.00	445	334	0	334
1976+00.00	375	282	0	282
1977+00.00	345	259	0	259
1978+00.00	244	183	330	-147
1979+00.00	231	173	0	173
1980+00.00	261	196	3	192
1981+00.00	231	173	66	107
1982+00.00	260	195	79	116
1983+00.00	117	88	46	42
1984+00.00	120	90	108	-18
1985+00.00	85	64	32	32
1986+00.00	76	57	8	49
1987+00.00	94	70	19	51
SMOKEY HOLLOW	510	383		383
Total	9265	6949	2084	4865

Earth Excavation: 9265 CU YD V3 SUB-TOTAL
 *TOPSOIL FURNISH AND PLACE, 6" 21780 SQ YD V3 SUB-TOTAL
 *SEE SEEDING CLASS 6 (MODIFIED) FOR AREA

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 EARTHWORK SCHEDULE
 US ROUTE 20

SCALE: VERT. N/A
 HORIZ. N/A
 DATE 10/28/05
 DRAWN BY DTE
 CHECKED BY JAM