

BITUMINOUS PAVEMENT PATCHING

STATION	LANE WIDTH	LENGTH OF PATCH		44200120		44200124		44200126		44000116		40601000	
		LT LANE (feet)	RT LANE (feet)	TYPE 2		TYPE 3		TYPE 4		Bit Rem over Patches 4"		Bit Repl over Patches	
				(Sq Yd)	(Sq Yd)	(Sq Yd)	(Sq Yd)	(Sq Yd)	(Sq Yd)	(Sq Yd)	(Sq Yd)	TON	TON
1723 + 18	12		10		13.3						14.6		3.3
1724 + 37	12	20						26.7		28.0		6.3	
1727 + 62	12		10		13.3						14.6		3.3
1731 + 15	12		6		8.0						9.3		2.1
1732 + 57	12		6		8.0						9.3		2.1
1734 + 16	12	10	10	13.3	13.3					14.6	14.6	3.3	3.3
1737 + 16	12		6		8.0						9.3		2.1
1737 + 54	12		15				20.0				21.3		4.8
1739 + 2	12		8		10.7						12.0		2.7
1740 + 3	12		6		8.0						9.3		2.1
1743 + 64	12		6		8.0						9.3		2.1
1744 + 76	12		8		10.7						12.0		2.7
1746 + 29	12		8		10.7						12.0		2.7
1746 + 30	12		6		8.0						9.3		2.1
1746 + 85	12		10		13.3						14.6		3.3
1748 + 35	12		6		8.0						9.3		2.1
1750 + 74	12		6		8.0						9.3		2.1
1751 + 70	12	6		8.0						9.3		2.1	
1753 + 5	12		6		8.0					9.3		2.1	
1754 + 81	12		10		13.3						14.6		3.3
1756 + 50	12		20					26.7		28.0		6.3	
1757 + 36	12		6		8.0						9.3		2.1
1760 + 89	12		8		10.7						12.0		2.7
1764 + 4	12		8		10.7						12.0		2.7
1764 + 95	12		8		10.7						12.0		2.7
1767 + 1	12		8		10.7						12.0		2.7
1769 + 17	12	6		8.0						9.3		2.1	
1769 + 18	12		6		8.0						9.3		2.1
1770 + 00	12		6		8.0						9.3		2.1
1770 + 27	12		6		8.0						9.3		2.1
1787 + 96	12		6		8.0						9.3		2.1
1790 + 49	12		6		8.0						9.3		2.1
1809 + 61	12	10		13.3						14.6		3.3	
1811 + 3	12		6		8.0						9.3		2.1
1811 + 73	12		8		10.7						12.0		2.7
1812 + 8	12	30						40.0		41.3		9.3	
1815 + 00	12		6		8.0						9.3		2.1
1817 + 24	12		8		10.7						12.0		2.7
1819 + 12	12		6		8.0						9.3		2.1
1819 + 33	12		6		8.0						9.3		2.1
1820 + 8	12		6		8.0						9.3		2.1
1824 + 16	12		6		8.0						9.3		2.1
1830 + 00	12		8		10.7						12.0		2.7
1835 + 00	12		10		13.3						14.6		3.3
1837 + 95	12		10		13.3						14.6		3.3
1838 + 77	12		10		13.3						14.6		3.3
1839 + 74	12		6		8.0						9.3		2.1
1840 + 19	12	15				20.0				21.3		4.8	
				42.7	389.3	20.0	20.0	66.7	26.7	147.7	481.4	33.1	107.8
FULL DEPTH PATCHES (50%)				216.0		20.0		47.0		629.1		140.9	

CLASS B PAVEMENT PATCHING

CONTRACT NO. 64577				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	*	STEPHENSON	290	42
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS FED. AID PROJECT		
• 177-(3, 4, 4-1)-1				

STATION	LANE WIDTH (feet)	LENGTH OF PATCH		AREA OF PATCHES								SAWING (3W+?L) (FT)	DOWEL BARS (EACH)	TIE BARS (EACH)	PAVEMENT FABRIC (SY)	
		LT LANE (FEET)	RT LANE (FEET)	TYPE 1		TYPE 2		TYPE 3		TYPE 4						
				(SY)	(SY)	(SY)	(SY)	(SY)	(SY)	(SY)	(SY)					
1853 + 60	12		6				8.0					42	20			
1864 + 28	12	6				8.0						42	20			
1866 + 62	12		6			8.0						42	20			
1867 + 11	12		6			8.0						42	20			
1873 + 60	12		6			8.0						42	20			
1874 + 67	12		6			8.0						42	20			
1875 + 43	12	6				8.0						42	20			
1875 + 94	12		6			8.0						42	20			
1880 + 9	12		6			8.0						42	20			
1880 + 24	12	6				8.0						42	20			
1884 + 93	12		6			8.0						42	20			
1885 + 00	12		6			8.0						42	20			
1885 + 31	12		6			8.0						42	20			
1886 + 7	12		6			8.0						42	20			
1886 + 78	12		6			8.0						42	20			
1887 + 74	12		6			8.0						42	20			
1888 + 33	12		6			8.0						42	20			
1889 + 7	12		6			8.0						42	20			
1891 + 48	12		6			8.0						42	20			
1893 + 91	12		6			8.0						42	20			
1894 + 58	12		6			8.0						42	20			
1941 + 20	12		6			8.0						42	20			
1940 + 25	12		6			8.0						42	20			
1940 + 31	12		8			10.7						44	20			
1942 + 64	12		6			8.0						42	20			
1942 + 83	12		6			8.0						42	20			
1951 + 65	12	6				8.0						42	20			
1953 + 79	12		6			8.0						42	20			
1956 + 44	12		6			8.0						42	20			
1957 + 9	12	6				8.0						42	20			
1957 + 50	12		6			8.0						42	20			
1958 + 14	12	8				10.7						44	20			
1960 + 26	12		6			8.0						42	20			
1960 + 28	12	6				8.0						42	20			
1960 + 75	12	6				8.0						42	20			
1963 + 12	12		6			8.0						42	20			
1970 + 45	24	12										84	44	32.0		
1970 + 83	24		12									84	44	32.0		
1974 + 28	24	12										84	44	32.0		
1975 + 00	24		6									78	44	16.0		
1978 + 73	24		12									84	44	32.0		
TOTALS				66.7		226.7		16.0		64.0		64.0		1930	940	144.0

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	PATCHING SCHEDULE	
PRE-FINAL	05/24/05	US ROUTE 20	
		SCALE: VERT. N/A	
		HORIZ. N/A	
		DATE 10/28/05	
		DRAWN BY TVN	
		CHECKED BY JAM	