

F.A. R. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	6M & TS	HENRY	257	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SUMMARY OF QUANTITIES URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE J000-2A	100% CITY Y060	80% FED 15% STATE 5% CITY Y031-1F	80% FED 20% STATE Y079	50% STATE 50% CITY SFTY-IB
*78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	820	820				
*78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	1251	1251				
*78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	146	146				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	126	126				
*80501000	SERVICE INSTALLATION (SPECIAL)	EACH	1			1		
81400400	CONCRETE HANDHOLE	EACH	4			4		
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1			1		
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 10	FOOT	975			975		
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL, 250 WATT	EACH	4			4		
82500605	LIGHTING CONTROLLER PHOTOCCELL RELAY	EACH	1			1		
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1		
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	1065			1065		
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	1093			1093		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	1819			1819		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	628			628		
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3C	FOOT	16			16		
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT	EACH	1			1		
87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT	EACH	1			1		
87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT	EACH	1			1		
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT	EACH	1			1		
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT	EACH	1			1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3			3		
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3			3		
87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	27			27		
*87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	26			26		
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	10			10		
*A2001714	TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5	5				
*A2007814	TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	4	4				
*B2002716	TREE, MALUS ADIRONDACK (ADIRONDACK CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6	6				
*X0300020	WATER SERVICE CONNECTION	EACH	35	23	12			
*X0301834	STORM SEWER TO BE FILLED	FOOT	212	212				
*X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	1			1		
*X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	213	213				
*X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	148	148				
*X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	266	266				
*X0322102	TEMPORARY SIDEWALK RAMP	EACH	4	4				
*X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	440	440				
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, No. 6 1C (GREEN)	FOOT	442			442		

\*SPECIALTY ITEM

PLOT DATE = Thu, Oct 27 11:48:04 2005  
 FILE NAME = c:\p\projects\p2165803\p165803.dgn  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = megillj