

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	GM & TS	HENRY	257	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

44000600	SIDEWALK REMOVAL	SQ. FT
	LOCATION	
	IL 81	
1345+ 50	to 1346+ 46 RT	287
1346+ 54	to 1346+ 87 RT	113
1347+ 5	to 1347+ 57 RT	174
1347+ 62	to 1347+ 73 RT	40
99+ 76	to 99+ 12 LT LEXINGTON SOUTH	404
98+ 77	to 98+ 35 LT LEXINGTON SOUTH	186
96+ 28	to 96+ 51 RT LEXINGTON SOUTH	117
886+ 85	to 887+ 14 LT 5TH ST WEST	147
98+ 35	to 98+ 49 RT LEXINGTON SOUTH	72
98+ 58	to 99+ 41 RT LEXINGTON SOUTH	367
99+ 73	to 99+ 84 RT LEXINGTON SOUTH	53
1348+ 7	to 1348+ 38 RT	153
1348+ 94	to 1349+ 10 RT	70
1349+ 18	to 1349+ 32 RT	63
1349+ 32	to 1349+ 52 RT	100
1349+ 85	to 1349+ 95 RT	50
1350+ 16	to 1350+ 26 RT	49
1350+ 26	to 1350+ 77 RT	255
1350+ 77	to 1350+ 87.5RT	45
1351+ 11	to 1351+ 52 RT	196
1351+ 64	to 1352+ 46 RT	403
1352+ 95	to 1353+ 23 RT	138
1353+ 47	to 1353+ 88 RT	204
1354+ 0	to 1354+ 69.5RT	334
599+ 73	to 599+ 85 LT CHESTNUT SOUTH	58
599+ 58	to 599+ 85 RT CHESTNUT SOUTH	153
1355+ 2	to 1355+ 13 RT	50
1355+ 18	to 1356+ 89 RT	778
699+ 56	to 699+ 81 RT TREMONT SOUTH	121
698+ 93	to 699+ 36 RT TREMONT SOUTH	215
698+ 67	to 699+ 36 LT TREMONT SOUTH	345
1357+ 24	to 1358+ 40 RT	585
1358+ 51	to 1358+ 97 RT	227
1359+ 30	to 1359+ 80 RT	243
1360+ 77	to 1360+ 89 RT	125
100+ 43	to 100+ 64 LT LEXINGTON NORTH	98
100+ 50	to 101+ 13 RT LEXINGTON NORTH	315
100+ 50	to 100+ 32 RT LEXINGTON NORTH	86
100+ 27	to 100+ 14 RT LEXINGTON NORTH	64
1348+ 8	to 1348+ 50 LT	213
1348+ 50	to 1350+ 86 LT	1138
1350+ 86	to 1351+ 11 LT	134
200+ 17	to 200+ 28 LT MADISON NORTH	57
200+ 33	to 200+ 43 LT MADISON NORTH	45
200+ 78	to 200+ 98 RT MADISON NORTH	100
200+ 43	to 200+ 33 RT MADISON NORTH	48
200+ 28	to 200+ 17 RT MADISON NORTH	65
1351+ 37	to 1351+ 53 LT	50
1351+ 77	to 1352+ 23 LT	527
1352+ 61	to 1353+ 62 LT	536
1353+ 94	to 1354+ 53 LT	520
300+ 39	to 300+ 44 LT CHESTNUT NORTH	21
1354+ 81	to 1355+ 45 LT	319
1355+ 53	to 1356+ 89 LT	692
700+ 21	to 700+ 34 LT TREMONT NORTH	61
700+ 34	to 700+ 93 LT TREMONT NORTH	295
700+ 66	to 700+ 93 RT TREMONT NORTH	135
700+ 67	to 700+ 51 RT TREMONT NORTH	68
700+ 30	to 700+ 20 RT TREMONT NORTH	46
1357+ 29	to 1357+ 62 LT	207
1357+ 87	to 1358+ 87 LT	474
1359+ 32	to 1360+ 94 LT	785

44000600	SIDEWALK REMOVAL	SQ. FT
	LOCATION	
	IL 78	
367+ 41	to 368+ 16 RT	375
368+ 58	to 369+ 14.5 RT	278
369+ 59	to 369+ 90 RT	156
371+ 26	to 371+ 41 RT	160
12+ 17	to 13+ 87 RT 6TH ST EAST	693
14+ 40	to 16+ 2 RT 6TH ST EAST	795
13+ 74	to 12+ 7 LT 6TH ST EAST	783
11+ 32	to 11+ 11 LT 6TH ST EAST	115
10+ 38	to 10+ 31 LT	40
371+ 62	to 372+ 4 RT	203
372+ 24	to 373+ 24 RT	498
373+ 34	to 373+ 53 RT	94
373+ 62	to 374+ 16 RT	277
374+ 50	to 375+ 60 RT	552
375+ 94	to 376+ 33 RT	92
376+ 94	to 377+ 19 RT	187
377+ 43	to 377+ 51 RT	28
377+ 55	to 377+ 76 RT	100
377+ 76	to 377+ 80 RT	20
20+ 20	to 20+ 27 LT 7TH ST EAST	34
20+ 32	to 20+ 65.5LT 7TH ST EAST	166
365+ 46	to 368+ 58 RT	794
367+ 0	to 367+ 44 LT	241
367+ 86.5	to 368+ 0 LT	66
368+ 5	to 368+ 15 LT	50
899+ 4	to 899+ 19 LT 5TH ST WEST	77
899+ 12	to 899+ 16 LT 5TH ST WEST	47
899+ 54	to 899+ 64 LT 5TH ST WEST	43
899+ 68	to 899+ 80 LT 5TH ST WEST	51
368+ 50	to 369+ 20 LT	352
370+ 93	to 371+ 15 LT	108
372+ 0	to 372+ 39 LT	192
372+ 69	to 373+ 39 LT	354
372+ 91	to 373+ 16 LT	750
373+ 69	to 373+ 96 LT	135
374+ 9	to 374+ 35 LT	133
374+ 49	to 374+ 61 LT	62
374+ 70	to 375+ 16 LT	231
375+ 34	to 376+ 21 LT	420
376+ 33	to 376+ 80 LT	237
376+ 92	to 377+ 27 LT	175
377+ 42	to 377+ 75 LT	183
377+ 75	to 377+ 93.0LT	87
	TOTAL	24453

48200410	BITUMINOUS SHOULDERS 6 1/2"	SQ. YD
	LOCATION	
	IL 81 Sta. 1345+10 to 1345+50	28
	TOTAL	28

50800105	REINFORCEMENT BARS	POUND
	LOCATION	
	5th Street Sta. 899+4Rt	517
	TOTAL	517
51000105	PIPE HANDRAIL	FOOT
	LOCATION	
	5th Street Sta. 899+4Rt	64
	TOTAL	64
55101200	STORM SEWER REMOVAL 24"	FOOT
	LOCATION	
	IL 78 Sta. 374+09.8Lt to 374+94.4Rt	40
	TOTAL	40
55101400	STORM SEWER REMOVAL 30"	FOOT
	LOCATION	
	IL 78 Sta. 374+94.4Rt to 376+09.5Rt	111
	TOTAL	111
56400510	FIRE HYDRANTS TO BE REMOVED AND REPLACED	EACH
	LOCATION	
	IL 81 Sta. 1348+28.7 Lt	1
	IL 81 Sta. 1356+00.9 Lt	1
	IL 78 Sta. 367+26.2 Rt	1
	IL 78 Sta. 373+03.1 Rt	1
	IL 78 Sta. 377+00.7 Rt	1
	6th Street Sta. 10+38.1 Rt	1
	6th Street Sta. 14+38.5 Rt	1
	Detour Route 5th Street Sta. 887+64 Lt	1
	TOTAL	8
60255500	MANHOLES TO BE ADJUSTED	EACH
	LOCATION	
	DETOUR ROUTE-STAGE 1A	
	IL 81 & LEXINGTON AVE. (SW QUAD) (State Cost)	2
	STAGE 3	
	IL 81 & LEXINGTON AVE. (SW QUAD)	2
	IL 81	
	Sta. 1350+01.3Rt	1
	Sta. 1351+24.6Rt	1
	Sta. 1354+38.7Rt	1
	Sta. 1354+60.9Rt	1
	Sta. 1354+66.8Lt	1
	Sta. 1355+05.9Rt	1
	IL 78	
	Sta. 365+08.5Rt	1
	Sta. 368+47.1Lt	1
	Sta. 370+34.7Rt	1
	7th Street	
	Sta. 20+29.1Rt	1
	Sta. 20+34.1Rt	1
	TOTAL	15
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH
	LOCATION	
	IL 81	
	Sta. 1353+00 Rt	1
	East 6th Street	
	Sta. 10+70Rt	1
	Sta. 12+036Rt	1
	Sta. 13+81.4Lt	1
	Sta. 13+83.1t	1
	TOTAL	5
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH
	LOCATION	
	IL 81 Sta. 1348+15Rt	1
	TOTAL	1
60260100	INLETS TO BE ADJUSTED	EACH
	LOCATION	
	IL 81 Sta. 1348+31Lt (Temporary after Stage 1)	1
	IL 81 Sta. 1348+28.9Rt (Temporary after Stage 2)	1
	TOTAL	2

PLOT DATE = Wed Nov 23 10:47:55 2005
 FILE NAME = c:\p\projects\64640\16082ev.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = bpkumar