

SUMMARY OF QUANTITIES

CONTRACT NO. 64B06

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
221	(198-1) M	ROCK ISLAND	29	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X080-2A 80% FED/ 20% STATE	SFTY - 3N 80% FED/ 20% STATE
20200100	EARTH EXCAVATION	CU YD	84	84	
20400800	FURNISHED EXCAVATION	CU YD	227	227	
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	63	63	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	158	158	
40600990	TEMPORARY RAMP	SQ YD	28	28	
44001205	BITUMINOUS CONCRETE SURFACE REMOVAL COMPLETE	SQ YD	215	215	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	197	197	
50102400	CONCRETE REMOVAL	CU YD	1.3	1.3	
50300225	CONCRETE STRUCTURES	CU YD	1.7	1.7	
50300260	BRIDGE DECK GROOVING	SQ YD	236	236	
50300300	PROTECTIVE COAT	SQ YD	258	258	
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	410	410	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3300	3300	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	137	137	
51500100	NAME PLATES	EACH	1	1	
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	287.5	287.5	
* 63000130	STEEL PLATE BEAM GUARDRAIL, TYPE A (SPECIAL)	FOOT	25	25	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	570	570	
63500105	DELINEATORS	EACH	4	4	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	4	4	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2892	2892	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	964	964	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	450	450	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	360	360	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2284	2284	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	

* SPECIALTY ITEMS

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X080-2A 80% FED/ 20% STATE	SFTY - 3N 80% FED/ 20% STATE
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	381	381	
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	410	410	
X0320887	POLYMER CONCRETE	CU FT	2.4	2.4	
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	33	33	
X0712400	TEMPORARY PAVEMENT	SQ YD	278	278	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	54	54	
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	251	251	
Z0002600	BAR SPLICERS	EACH	71	71	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	4		4
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2		2

* SPECIALTY ITEMS

PLOT DATE * Wed Oct 26 11:26:17 2005
 FILE NAME * c:\pwork\proj\64b06\64b06.dgn
 USER NAME * mgplj

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY

SUMMARY OF QUANTITIES