

SUMMARY OF QUANTITIES

URBAN
90% FED
10% STATE
SFTY-1D

CONTRACT NO. 64B71				
F.A. U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5773	112-YPM	ROCK ISLAND	7	2
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAY CODE	ITEM	UNIT	TOTAL QTY
X0325211	LED SIGNAL FACE RETROFIT, OPTICALLY PROGRAMMED, 1-FACE, 5-SECTION	EACH	2
67100100	MOBILIATION	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
78300100	PAVEMENT MARKING REMOVAL	SQ FT	9059
81012700	CONDUIT IN TRENCH, 2 1/2" DIA, PVC	FOOT	40
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	40
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL No 14 5C	FOOT	270
87502480	TRAFFIC SIGNAL POST GALVANIZED, 14 FT	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3
87900200	DRILL EXISTING HANDHOLE	EACH	1
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1 FACE, 3 SECTION, BRACKET MOUNTED	EACH	1
X7800500	POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS SPECIAL	SQ FT	928
X7800510	POLYUREA PAVEMENT MARKING SPECIAL - LINE 4"	FOOT	7273
X7800530	POLYUREA PAVEMENT MARKING SPECIAL - LINE 6"	FOOT	528
X7800540	POLYUREA PAVEMENT MARKING SPECIAL - LINE 8"	FOOT	6234
X7800550	POLYUREA PAVEMENT MARKING SPECIAL - LINE 12"	FOOT	1366
X7800580	POLYUREA PAVEMENT MARKING SPECIAL - LINE 24"	FOOT	790

PLOT DATE = Thu Oct 27 15:01:43 2005
FILE NAME = C:\prowork\view\050103\sum.dgn
PLOT SCALE = 28.0000 / IN.
USER NAME = h11k1

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT.	DRAWN BY	
DATE	CHECKED BY	