CONTRACT NO. 72449

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

• F.A.U. 7978 (OLD US 36), F.A.U. 7968 (CAMP BUTLER RD.)
•• 3R(BR, BR-1, BR-2), 19RS-8

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	••	SANGAMON	261	4

STA. TO STA.

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

LOCATION OF WORK				M 80% FEDERAL 20% STATE F.A.U. 7978 (OLD US 36)	M 80% FEDERAL 20% STATE F.A.U. 7968 (CAMP BUTLER RD.)	M 80% FEDERAL 20% STATE CAMP BUTLER BR. EX. S.N. 084-0086 PR. S.N. 084-0518	BHM 80% FEDERAL 20% STATE SANG RIVER BR. S.N. 084-0052	BHM 80% FEDERAL 20% STATE 7TH ST. BR. S.N. 084-0053					
			URBAN	CONSTRUCTION TYPE CODE									
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	1000-2A	X271-2A	X071-2A	X271-2A					
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.4	1.8	0.6								
25100105	MULCH, METHOD 1	ACRE	1.2	0.9	0.3								
25100630	EROSION CONTROL BLANKET	SQ YD	1,045		1,045								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	120	30	90								
28000300	TEMPORARY DITCH CHECKS	EACH	2		2								
28000400	PERIMETER EROSION BARRIER	FOOT	854		854								
28000500	INLET AND PIPE PROTECTION	EACH	5	3	2								
28100107	STONE RIPRAP, CLASS A4	SQ YD	518	342	43		133						
28200200	FILTER FABRIC	SQ YD	518	342	43		133						
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1,535		1,535								
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	990		990								
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	450		450								
35800100	PREPARATION OF BASE	SQ YD	6,597	4,630	1,967								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	41	36.3	4.7								
40600300	AGGREGATE (PRIME COAT)	TON	185	161.3	23.7								
40600895	CONSTRUCTING TEST STRIP	EACH	1	1									
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	270	218	52								
40600990	TEMPORARY RAMP	SQ YD	100	74	26								
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	782	701	81								
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	401			207		194					
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	232				232						
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	28,998	21,314	7,684								
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	55,936	53,438	2,498								
44000300	CURB REMOVAL	FOOT	746	519	227								
44000400	GUTTER REMOVAL	FOOT	4,638	2,523	2,115								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,143		1,143								
44002470	GUTTER INLET REMOVAL	EACH	1	1									
44002500	GUTTER OUTLET REMOVAL	EACH	3	2	1								
44200192	PAVEMENT PATCHING, TYPE II, 16 INCH	SQ YD	1,672	1,672									
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,788	1,694	94								

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.U. Route 7978 (OLD US 36)
F.A.U. Route 7968 (Camp Butler Rd.)
Section 3R(BR, BR-1, BR-2), 19RS-8
SANGAMON COUNTY

SCALE: VERT. HORIZ. | DRAWN BY: JWC
DATE: MAY 11, 2005 | CHECKED BY: RSC

•DGN-SPEC•
•DATE-TIME•
•REF01

D6 PROJECT: D652102 FILE: SHTSUMMARY.DGN