

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

F.A.U. 7978 (OLD US 36), F.A.U. 7968 (CAMP BUTLER RD.)	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
** 3R1BR, BR-1, BR-2, 19RS-8	*	**	SANGAMON	261	6
STA.		TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT			

LOCATION OF WORK			M 80% FEDERAL 20% STATE F.A.U. 7978 (OLD US 36)	M 80% FEDERAL 20% STATE F.A.U. 7968 (CAMP BUTLER RD.)	M 80% FEDERAL 20% STATE CAMP BUTLER BR. EX. S.N. 084-0086 PR. S.N. 084-0518	BHM 80% FEDERAL 20% STATE SANG RIVER BR. S.N. 084-0052	BHM 80% FEDERAL 20% STATE 7TH ST. BR. S.N. 084-0053					
			URBAN		CONSTRUCTION TYPE CODE							
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	1000-2A	X271-2A	X071-2A	X271-2A				
51203700	TEST PILE STEEL HP12X74	EACH	2			2						
51500100	NAME PLATES	EACH	3			1	1	1				
54002070	EXPANSION BOLTS 3/4 INCH X 15 INCH	EACH	8		8							
54003000	CONCRETE BOX CULVERTS	CU YD	10		10							
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	47	26	21							
54200649	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"	FOOT	100	100								
54215550	METAL END SECTIONS 15"	EACH	2	1	1							
54215559	METAL END SECTIONS 24"	EACH	2	2								
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	117	117								
58700200	BRIDGE SEAT SEALER	SQ FT	390.3			183.3	207					
59000100	EPOXY CRACK SEALING	FOOT	28					28				
60100945	PIPE DRAINS 12"	FOOT	128	128								
60224075	MANHOLES, TYPE A, 6' -DIAMETER	EACH	1	1								
60261200	INLETS TO BE ADJUSTED WITH NEW TYPE 10 FRAME & GRATE	EACH	1	1								
60404210	FRAMES AND GRATES, TYPE 2	EACH	3	2	1							
60405740	FRAMES AND GRATES TO BE REMOVED	EACH	1	1								
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	17	13	4							
60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	1,158	671	487							
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	264	264								
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	1	1								
60900515	CONCRETE THRUST BLOCKS	EACH	1	1								
*63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1,100	537.5	562.5							
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4								
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	12	8	4							
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	21	19	2							
63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	1,665	1,175	490							
67000400	ENGINEER'S OFFICE, TYPE A	CAL MO	16	3.2	3.2	3.2	3.2	3.2				
67100100	MOBILIZATION	L SUM	1	0.2	0.2	0.2	0.2	0.2				
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1								

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.U. Route 7978 (OLD US 36)
F.A.U. Route 7968 (Camp Butler Rd.)
Section 3R1BR, BR-1, BR-2, 19RS-8
SANGAMON COUNTY
SCALE: VERT. DRAWN BY: JWC
 HORIZ. CHECKED BY: RSC
DATE: MAY 11, 2005

•DGN-SPEC•
•DATE-TIME•
•REF01