

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

F.A.U. 7978 (OLD US 36),
F.A.U. 7968 (CAMP BUTLER RD.)
** 3R(BR, BR-1, BR-2), 19RS-8

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	261	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION OF WORK			M 80% FEDERAL 20% STATE F.A.U. 7978 (OLD US 36)	M 80% FEDERAL 20% STATE F.A.U. 7968 (CAMP BUTLER RD.)	M 80% FEDERAL 20% STATE CAMP BUTLER BR. EX. S.N. 084-0086 PR. S.N. 084-0518	BHM 80% FEDERAL 20% STATE SANG RIVER BR. S.N. 084-0052	BHM 80% FEDERAL 20% STATE 7TH ST. BR. S.N. 084-0053	CONSTRUCTION TYPE CODE				
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	1000-2A	1000-2A	X271-2A	X071-2A	X271-2A				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1								
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1								
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5							
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1			0.33	0.34	0.33				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	16	4	12							
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1								
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7,237	6,761	476							
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110		110							
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	91,376	78,705	12,671							
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,387	571	816							
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	177		177							
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24		24							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	804	751	53							
70400100	TEMPORARY CONCRETE BARRIER	FOOT	187.5	187.5								
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	187.5	187.5								
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	6,601		6,601							
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	148		148							
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	177		177							
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	84,364	78,294	6,070							
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	728	728								
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	24	24								
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	110		110							
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	411	411								
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	668		668							
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	24		24							
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	533	401	132							
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	42	38	4							
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	21	19	2							
78300100	PAVEMENT MARKING REMOVAL	SQ FT	48	48								
78300200	RAISED REFLECTIVE PAVEMENT MARKING REMOVAL	EACH	463	401	62							

* SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.U. Route 7978 (OLD US 36)
F.A.U. Route 7968 (Camp Butler Rd.)
Section 3R(BR, BR-1, BR-2), 19RS-8
SANGAMON COUNTY
SCALE: VERT. DRAWN BY: JWC
 HORIZ. CHECKED BY: RSC
DATE: MAY 11, 2005