

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	261	38
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 7978 (OLD US 36) & 7968 (CAMP BUTLER RD.)
 ** 3R(BR, BR-1, BR-2), 19RS-8

SCHEDULE OF QUANTITIES

CURB REMOVAL

LOCATION	QUANTITY (FOOT)
F.A.U. 7968 (Camp Butler Rd.)	
(S. Camp Butler Rd. Intersection)	
(Measured Using CADD)	
(SW Quadrant) (52)	105.73
(SE Quadrant) (53 to 54)	121.09
(7th St. Entrance Ramp)	
STA. 91+90.00 to STA. 93+50.00 LT (71)	160.00
STA. 92+50.00 to STA. 96+00.40 RT (70 to 72)	350.40
STA. 2+91.50 to STA. 3+00.00 RT (72)	8.50
STA E.O. #10-STA 96+00.44 (BK1)- STA. 2+91.50 (AH)	
PROJECT TOTAL	746

GUTTER INLET REMOVAL

LOCATION	QUANTITY (EACH)
(7th St. Entrance Ramp)	
STA. 91+92.30 LT (69)	1
PROJECT TOTAL	1

GUTTER OUTLET REMOVAL

LOCATION	QUANTITY (EACH)
F.A.U. 7978 (Old US 36)	
STA. 39+36.00 RT (16)	1
STA. 190+21.30 RT (42)	1
F.A.U. 7968 (E.B. Camp Butler Rd.)	
STA. 24+35.00 LT (61)	1
PROJECT TOTAL	3

COMBINATION CONCRETE CURB & GUTTER REMOVAL

LOCATION	QUANTITY (FOOT)
Camp Butler Rd. (Measured Using CADD)	
STA. 4+49.00 to STA. 5+64.00	236.20
STA. 5+94.00 to STA. 6+00.00	16.82
STA. 6+00.00 to STA. 7+06.00	214.87
STA. 7+37.00 to STA. 9+34.00	409.25
STA. 9+74.20 to STA. 11+09.10	264.98
PROJECT TOTAL	1,143

FRAME AND GRATES TO BE REMOVED

LOCATION	QUANTITY (EACH)
(7th St. Entrance Ramp)	
STA. 92+67.80 LT (71)	1
PROJECT TOTAL	1

TYPE B INLET BOX, STANDARD 609006

LOCATION	QUANTITY (EACH)
F.A.U. 7978 (Old US 36)	
STA. 191+45.87 RT (42)	1
PROJECT TOTAL	1

CONCRETE GUTTER, TYPE A (MODIFIED)

LOCATION	QUANTITY (FOOT)
F.A.U. 7978 (Old US 36)	
STA. 36+48.40 to STA. 39+03.00 (15 to 16)	254.60
F.A.U. 7968 (E.B. Camp Butler Rd.)	
STA. 15+01.00 to STA. 16+64.20 LT (58)	163.20
S.N.: 084-0086 STA. 16+58.26 to STA. 19+60.87	
STA. 20+74.50 to STA. 23+97.80 LT (59 to 61)	323.30
(7th St. Entrance Ramp)	
STA. 92+29.60 to STA. 93+38.00 LT (71)	108.40
STA. 92+88.60 to STA. 95+96.80 RT (71)	308.30
STA E.O. #10-STA 96+00.44 (BK1)- STA. 2+91.50 (AH)	
PROJECT TOTAL	1,158

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06

LOCATION	QUANTITY (FOOT)
F.A.U. 7968 (Camp Butler Rd.)	
(Measured Using CADD)	
Median Nose in Front of Cemetery Entr. (55)	41.93
F.A.U. 7968 (E.B. Camp Butler Rd.)	
STA. 9+88.30 to STA. 10+84.25 (55 to 56)	95.95
F.A.U. 7968 (W.B. Camp Butler Rd.)	
STA. 9+83.20 to STA. 11+09.10 (55 to 56)	125.90
PROJECT TOTAL	264

CLASS SI CONCRETE (OUTLET)

LOCATION	QUANTITY (CU YD)
F.A.U. 7978 (Old US 36)	
STA. 39+36.40 to STA. 36+48.40 RT (15 to 16)	0.92
STA. 39+03.00 to STA. 39+40.20 RT (16)	3.07
F.A.U. 7968 (E.B. Camp Butler Rd.)	
STA. 14+89.00 to STA. 15+01.00 LT (57 to 58)	0.92
S.N.: 084-0086 STA. 16+58.26 to STA. 19+60.87	
STA. 23+97.80 to STA. 24+35.00 LT (61)	3.07
(7th St. Entrance Ramp)	
STA. 91+93.60 to STA. 92+29.60 LT (71)	3.07
STA. 92+52.60 to STA. 92+88.60 RT (71)	3.53
STA. 93+38.00 to STA. 93+50.00 LT (71)	0.92
STA. 95+96.90 to STA. 96+00.40 RT (71)	
STA E.O. #10-STA 96+00.44 (BK1)- STA. 2+91.50 (AH)	
STA. 2+91.50 to STA. 3+00.00 (72)	0.92
PROJECT TOTAL	17

FRAMES AND GRATES TYPE 2

LOCATION	QUANTITY (EACH)
F.A.U. 7978 (Old US 36)	
STA. 39+36.00 RT (16)	1
F.A.U. 7968 (E.B. Camp Butler Rd.)	
STA. 24+35.00 LT (61)	1
(7th St. Entrance Ramp)	
STA. 91+92.30 LT (70)	1
PROJECT TOTAL	3

INLETS TO BE ADJUSTED WITH NEW TYPE 10 FRAME AND GRATE

LOCATION	QUANTITY (EACH)
(7th St. Entrance Ramp)	
STA. 92+67.80 LT (71)	1
PROJECT TOTAL	1

CONCRETE THRUST BLOCKS

LOCATION	QUANTITY (EACH)
(7th St. Entrance Ramp)	
STA. 91+72.35, 33.34' LT (70)	1
PROJECT TOTAL	1

MANHOLES, TYPE A, 6'-DIAMETER

LOCATION	QUANTITY (EACH)
(7th St. Entrance Ramp)	
STA. 91+92.30 LT (70)	1
PROJECT TOTAL	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.U. Route 7978 (OLD US 36) &
 F.A.U. Route 7968 (CAMP BUTLER RD.)
 Section 3R(BR, BR-1, BR-2), 19RS-8
 SANGAMON COUNTY

SCALE: VERT. DRAWN BY: JWC
 HORIZ. CHECKED BY: RSC
 DATE: