

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	••	SANGAMON	261	42
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- 7978 (OLD US 36) & 7968 (CAMP BUTLER RD.)
- 3R1BR, BR-1, BR-2, 19RS-8

PAINT PAVEMENT MARKING - LINE 6"

LOCATION	WHITE	
	SOLID (FOOT)	SKIP-DASH (FOOT)
F.A.U. 7978 (E.B. Old US 36) STA. 46+29.70 to STA 51+50.00 (18 to 19)		130.08
F.A.U. 7978 (W.B. Old US 36) STA. 46+80.00 to STA 51+00.00 (27 to 28)		105
(7th St. Entrance Ramp) STA. 77+00.00 to STA 81+50.00 (27 to 28)		112.50
(7th St. Exit Ramp) STA. 84+50.00 to STA 88+00.00 (27 to 28)		87.50
F.A.U. 7978 (Old US 36) STA. 187+75.00 to STA 189+32.80 (40) STA. 148+60.00 to STA 149+95.00 (49)	157.80 135	
PROJECT SUB-TOTAL	293	435
PROJECT TOTAL	728	

PAINT PAVEMENT MARKING - LINE 24"

LOCATION	WHITE SOLID (FOOT)
	F.A.U. 7978 (Old US 36) W. Approach
S.N.: 084-2017 STA. 80+63.13 to STA 79+76.87	
E. Approach	12
PROJECT TOTAL	24

THERMOPLASTIC PAVEMENT MARKING

LOCATION	5"			
	WHITE		6"	
	SOLID (FOOT)	DBL-SOLID (FOOT)	SOLID (FOOT)	YELLOW SOLID (FOOT)
F.A.U. 7968 (Camp Butler Rd.) STA. 175+44.33 to STA. 180+43.17 (52) STA. 175+54.33 to STA. 180+43.17 (52) STA. 175+54.33 to STA. 179+98.98 (52) STA. 179+98.98 to STA. 180+74.82 (52)	(Measured Using CADD) 1,975.36			96.36
STA EQ. #8-STA 180+74.82 (BK)- STA. 3+62.75 (AH)	889.30 75.84			
STA. 4+25.29 to STA. 9+13.00 (53 to 54) STA. 4+25.29 to STA. 9+13.00 (53 to 54) STA. 3+62.75 to STA. 4+97.01 (52 to 54) STA. 4+97.01 to STA. 10+00.00 (54 to 55)	(Measured Using CADD) 1,970.84			80.59
(S. Camp Butler Rd. Intersection) STA. 498+49.68 to STA. 499+45.60 (Measured Using CADD)		191.84		
(SW Quadrant) (SE Quadrant)	146.29 211.39			
(LT Turn Going West) (RT Turn Going East)			57.17 90.46	
PROJECT SUB-TOTAL	2,463.06	4,138.04	147.63	176.95
PROJECT TOTAL	6,601			

SCHEDULE OF QUANTITIES

SHORT - TERM PAVEMENT MARKING

LOCATION	QUANTITY (FOOT)
(After Milling) F.A.U. 7978 (Old US 36) STA. 86+80.00 to STA 75+55.27 (1 to 4)	102.25
STA EQ. #1-STA 79+55.27 (BK)- STA. 280+63.10 (AH)	
STA. 280+63.10 to STA. 217+86.34 (5 to 8)	570.61
STA EQ. #2-STA 217+86.34 (BK)- STA. 0+00.04 (AH)	
STA. 0+00.04 to STA. 28+32.50 (8 to 13)	257.50
F.A.U. 7978 (E.B. Old US 36) STA. 28+32.50 to STA. 56+42.40 (14 to 22)	255.45
F.A.U. 7978 (W.B. Old US 36) STA. 30+32.00 to STA. 58+70.30 (14, 23 to 30)	258.03
F.A.U. 7978 (Old US 36) STA. 58+70.30 to STA 62+06.10 (30 to 32)	30.53
STA EQ. #3-STA 62+06.10 (BK)- STA. 62+31.60 (AH)	
STA. 62+31.60 to STA. 66+55.00 (33)	38.49
STA EQ. #4-STA 66+55.00 (BK)- STA. 66+60.23 (AH)	
STA. 66+60.23 to STA. 67+56.56 (33)	8.76
S.N.: 084-0052 STA. 67+56.56 to STA 75+94.64	
STA. 75+94.64 to STA. 77+67.23 (34 to 35)	15.69
STA EQ. #5-STA 77+67.23 (BK)- STA. 77+62.00 (AH)	
STA. 77+62.00 to STA. 79+69.25 (35)	18.84
STA EQ. #6-STA 79+69.25 (BK)- STA. 179+65.25 (AH)	
STA. 179+65.25 to STA. 191+54.37 (35 to 42)	108.10
S.N.: 084-0053 STA. 191+54.37 to STA 193+45.27	
STA. 193+45.27 to STA. 203+06.52 (43 to 45)	87.39
STA EQ. #7-STA 203+06.52 (BK)- STA. 106+57.25 (AH)	
STA. 106+57.25 to STA. 153+36.00 (45 to 51)	425.34
F.A.U. 7968 (Camp Butler Rd.) STA. 175+44.53 to STA. 177+88.65 (52) STA. 177+88.65 to STA. 180+00.00 (52)	22.19 38.43
STA EQ. #8-STA 180+74.82 (BK)- STA. 3+62.75 (AH)	
STA. 4+25.00 to STA. 9+14.00 (52)	88.91
SUBTOTAL (MILLING) (1)	2,326.51

SHORT - TERM PAVEMENT MARKING (CONT')

LOCATION	QUANTITY (FOOT)
(S. Camp Butler Rd.) STA. 498+49.68 to STA. 499+50.00	9.12
(7th St. Exit Ramp) STA. 88+00.00 to STA. 99+55.40 (40)	14.13
(7th St.) STA. 5+32.00 to STA. 12+19.00 (79 to 81)	62.45
SUBTOTAL (MILLING) (2)	85.70
SUBTOTAL (MILLING) (1 & 2)	2,412.21
(After Leveling Binder) SUBTOTAL (LEVELING BINDER)	2,412.21
(After Surface Course) SUBTOTAL (SURFACE COURSE)	2,412.21
PROJECT TOTAL	7,237

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	QUANTITY (SQ FT)
(Removal of Short Term Pavement Marking) (After Surface Course)	804.06
PROJECT TOTAL	804

RAISED REFLECTIVE PAVEMENT MARKING REMOVAL

LOCATION	QUANTITY (EACH)
F.A.U. 7978 (Old US 36) (Beginning of Project to S.N. 084-2017) STA. 86+80.00 to STA 86+63.13 (Double)	14
(S.N. 084-2017 to Dixon Rd.) STA. 79+76.87 to STA 79+55.27	
STA EQ. #1-STA 79+55.27 (BK)- STA. 280+63.10 (AH)	
STA. 280+63.10 to STA 256+20.00	31
(Dixon Rd. to Maurice Werner Dr.) STA. 256+20.00 to STA 218+90.00	47
(Maurice Werner Dr. to Roselawn Rd.) STA. 218+90.00 to STA 217+86.34	
STA EQ. #2-STA 217+86.34 (BK)- STA. 0+00.04 (AH)	
STA. 0+00.04 to STA. 5+77.00	10
STA. 5+77.00 to STA. 23+40.00	21
(Double @ Painted & Concrete Median) STA. 23+40.00 to STA. 28+50.00	34
STA. 26+19.40 to STA. 28+32.50 (Rt. E.O.P.)	19
F.A.U. 7978 (E.B. Old US 36) STA. 28+32.50 to STA. 56+12.40	30
STA. 56+12.40 to STA. 58+44.40 (Rt. E.O.P.) (W.B. STA. 58+70.30 to STA. 61+00.00)	26
F.A.U. 7978 (W.B. Old US 36) STA. 28+50.00 to STA. 33+70.00 (Lt. E.O.P.) STA. 33+70.00 to STA. 46+29.70	21 13
(Double @ Painted Median) STA. 45+40.000 to STA. 46+20.00	13
STA. 46+29.70 to STA. 59+25.00	18
F.A.U. 7978 (Old US 36) STA. 61+00.00 to STA. 62+06.10	
STA EQ. #3-STA 62+06.10 (BK)- STA. 62+31.60 (AH)	
STA. 62+31.60 to STA. 66+55.00	
STA EQ. #4-STA 66+55.00 (BK)- STA. 66+60.23 (AH)	
STA. 66+60.23 to STA. 67+63.66	11
PROJECT SUB-TOTAL	308

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 F.A.U. Route 7978 (OLD US 36) &  
 F.A.U. Route 7968 (CAMP BUTLER RD.)  
 Section 3R1BR, BR-1, BR-2, 19RS-8  
 SANGAMON COUNTY

VERT. DATE:                      DRAWN BY: JWC  
 HORIZ.                      CHECKED BY: RSC

•DGN-SPEC•  
 •DATE-TIME•  
 •REF 01