

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION




ROLLED THREAD DOWEL BAR




BAR SPLICER ASSEMBLY ALTERNATIVES

** Heavy Hex Nuts conforming to ASTM A 563, Grade C. D or DH may be used.



INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt. "B" : Set bar splicer assembly by nailing to wood forms or cementing to steel forms. (E): Indicates epoxy coating.



SHEET NO. 30 TOTAL. FAU 7968 SANGAMON 200 33 SHEETS 261

Contract #72449 *SECTION 3R(BR, BR-1, BR-2)19RS-8

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.

Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length. All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars. Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars.

Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:

Minimum Capacity (Tension in kips) = $1.25 \times fy \times A_t$

Minimum *Pull-out Strength = $1.25 \times fs_{allow} \times A_f$

(Tension in kips)

Where fy = Yield strength of lapped reinforcement bars in ksi. fs_{allow}= Allowable tensile stress in lapped reinforcement bars in ksi (Service Load)

A_t = Tensile stress area of lapped reinforcement bars. * = 28 day concrete

Bar splicer assemblies shall be according to Section 508 of the Standard Specifications, except as noted. The furnishing and installation of bar splicer assemblies will be measured and paid for at the contract unit price each for "BAR SPLICERS."

> BAR SPLICER ASSEMBLY DETAILS F.A.U. ROUTE 7968 SECTION 3R(BR. BR-1, BR-2)19RS-8 SANGAMON COUNTY STATION 17+97.34 STRUCTURE NO. 084-0518

CHECKED BSD-1

DESIGNED

CHECKED

10-22-04

J. Mann

G. Ahanchi

JWM/GRA

DRAWN BECKY M. LEACH