

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	261	260
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* 7978 (OLD US 36) & 7968 (CAMP BUTLER RD) ** 3R1BR, BR-1, BR-2, 19RS-8				

INCIDENTAL BITUMINOUS CONCRETE SCHEDULE

DESCRIPTION	STATION	from E.O.P. (FOOT)	WIDTH (FOOT)	THICKNESS (INCH)	AGGR. ENTR.		BIT. ENTR.		SIDE RD.		TOTAL (TON)	Aggr. Shldr AREA (SQ FT)
					AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)		
					[F.A.U. 7978 (Old US 36)]	(cont.)						
LINCOLN ST. (LT)	148+00.00 LT	34	28	1.875					2,108.00	24.59	24.59	267.00
TR 420 (Overpass Rd.) (RT)	148+00.00 RT											
AGG PE (LT)	152+50.00 LT	7	24	3.5	217.00	4.73					4.73	99.00
SECTION ENDS	153+01.00											
LIMITS OF IMPROVEMENT	153+36.00											
Subtotal (pg 4) =					217.00	4.73	0.00	0.00	2,108.00	24.59	29.32	366.00
Total (Old US 36) =					13,463.75	363.43	20,146.25	235.04	6,743.00	78.67	677.14	11,725.50

DESCRIPTION	STATION	from E.O.P. (FOOT)	WIDTH (FOOT)	THICKNESS (INCH)	AGGR. ENTR.		BIT. ENTR.		SIDE RD.		TOTAL (TON)	Aggr. Shldr AREA (SQ FT)
					AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)		
					(Camp Butler Road)							
LIMITS OF IMPROVEMENT	175+44.53											
SECTION BEGINS	175+54.53											
AGG PE (w/ MBT) (LT)	177+64.00 LT	15	14	3.5	599.50	13.06					13.06	132.00
AGG PE (w/ MBI) (LT)	178+28.00 LT	15	16	3.5	629.50	13.71					13.71	135.00
C.L. of Roselawn Rd. (RT)	180+74.82	9	30	1.875					351.00	4.10	4.10	120.00
STA EQN #8	180+74.82 (BK) = 3+62.75 (AH)											
AGG PE (w/ MBT) (RT)	5+53.00 RT	15	13	3.5	584.50	12.73					12.73	130.50
PCC CE (LT)	5+75.00 LT											
AGG PE (RT)	7+19.00 RT	7	39	3.5	974.50	21.22					21.22	121.50
AGG PE (w/ MBT) (RT)	9+46.00 RT	15	24	3.5	749.50	16.32					16.32	147.00
Subtotal (Camp Butler Road)=					3,537.50	77.04	0.00	0.00	351.00	4.10	81.13	786.00

* QUANTITIES HAVE INCLUDED MAILBOX TURNOUTS WHICH SHALL BE BROUGHT UP TO GRADE USING INCIDENTAL BITUMINOUS SURFACING

DESCRIPTION	STATION	from E.O.P. (FOOT)	WIDTH (FOOT)	THICKNESS (INCH)	AGGR. ENTR.		BIT. ENTR.		SIDE RD.		TOTAL (TON)	Aggr. Shldr AREA (SQ FT)
					AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)		
					E.B. 7th St. Ent. Ramp							
STA EQN #9	84+76.41 (BK) = 84+78.60 (AH)											
STA EQN #10	96+00.40 (BK) = 2+91.50 (AH)											
BIT CE (RT)	3+62.00 RT	9	35	1.875			396.00	4.62			4.62	127.50
Nose of Median	5+32.00											
Subtotal (River ton Exit Ramp)=					0.00	0.00	396.00	4.62	0.00	0.00	4.62	127.50

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION DETAILS FOR RURAL ENTRANCE, MAILBOX TURNOUT & SIDE ROAD SHEET 6 OF 7 SCALE: VERT. HORIZ. DATE: MAY 21, 2004	DRAWN BY: CAD CHECKED BY: JCN
NAME	DATE		