

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	••	SANGAMON	261	261
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• 7978 (OLD US 36) & 7968 (CAMP BUTLER RD)				
•• 3R(BR, BR-1, BR-2), 19R5-8				

**INCIDENTAL BITUMINOUS CONCRETE SCHEDULE**

DESCRIPTION	STATION	from E.O.P. (FOOT)	WIDTH (FOOT)	THICKNESS (INCH)	AGGR. ENTR.		BIT. ENTR.		SIDE RD.		TOTAL (TON)	Aggr. Shldr AREA (SQ. FT)
					AREA	TOTAL	AREA	TOTAL	AREA	TOTAL		
					(SQ FT)	(TON)	(SQ FT)	(TON)	(SQ FT)	(TON)		
<i>7th Street</i>												
<i>STA EQN #11</i>	<i>92+07.67 (BK) = 0+41.08 (AH)</i>											
AGG PE (w/ MBT) (LT)	7+65.00 LT	15	13	3.5	584.50	12.73					12.73	130.50
AGG PE (RT)	9+24.00 RT	7	22	3.5	203.00	4.42					4.42	96.00
<b>SECTION ENDS</b>	11+84.00											
BIT PE (LT)	12+05.00 LT	7	12	1.875			133.00	1.55			1.55	81.00
<b>LIMITS OF IMPROVEMENT</b>	12+19.00											
<i>C.L. Lincoln Street</i>	12+97.00 Thru											
<i>Subtotal (7th Street) =</i>					787.50	17.15	133.00	1.55	0.00	0.00	18.70	307.50
<i>Subtotal (pg 4) =</i>					4,325.00	94.19	529.00	6.17	351.00	4.10	104.46	1,221.00
<i>Total (Entire Project) =</i>					17,788.75	457.62	20,675.25	241.21	7,094.00	82.76	781.59	12,946.50

\* QUANTITIES HAVE INCLUDED MAILBOX TURNOUTS WHICH SHALL BE BROUGHT UP TO GRADE USING INCIDENTAL BITUMINOUS SURFACING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**DETAILS FOR RURAL  
 ENTRANCE, MAILBOX TURNOUT  
 & SIDE ROAD**  
 SHEET 7 OF 7  
 SCALE: VERT. HORIZ.  
 DATE: MAY 21, 2004  
 DRAWN BY: CAD  
 CHECKED BY: JCN