

TEMPORARY RUMBLE STRIP		
LOCATION		EACH
Stage Const Box Culvert Sta 1158+80.50		
1138+37.00 RT		1
1143+37.00 RT		1
1148+37.00 RT		1
1169+29.00 LT		1
1174+29.00 LT		1
1179+29.00 LT		1
Stage Const Box Culvert Sta 1204+41		
1184+24.00 RT		1
1189+24.00 RT		1
1194+24.00 RT		1
1214+58.00 LT		1
1219+58.00 LT		1
1224+58.00 LT		1
Stage Const Box Culvert Sta 1221+20		
1200+74.00 RT		1
1205+74.00 RT		1
1210+74.00 RT		1
1231+65.00 LT		1
1236+65.00 LT		1
1241+65.00 LT		1
Stage Const Box Culvert Sta 1245+00		
1224+54.00 RT		1
1229+54.00 RT		1
1234+54.00 RT		1
1255+45.00 LT		1
1260+45.00 LT		1
1265+45.00 LT		1
Bridge over Little Wabash River		
1267+75.00 RT		1
1262+75.00 RT		1
1257+75.00 RT		1
1294+55.00 LT		1
1299+55.00 LT		1
1304+55.00 LT		1
TOTAL		30

SHORT-TERM PAVEMENT MARKING			
U.S. 45		NO. OF APPLICATIONS	FOOT
1143+00.00 to 1246+50.00		4	4140
1263+00.88 to 1276+97.11		4	558
1285+32.78 to 1311+00.00		4	1027
TOTAL			5725

TEMPORARY CONCRETE BARRIER (STATE OWNED)				
U.S. 45		Stage		Foot
1255+00.00 to 1259+00.00	12' LT	2-A		400
Stage Construction of Culverts				
1158+30.00 to 1158+80.00	LT	1-A		50
1157+60.00 to 1160+00.00	CL	1-A		240
1203+21.00 to 1205+61.00	CL	1-A		240
1220+70.00 to 1221+70.00	LT	1-A		100
1220+00.00 to 1222+40.00	CL	1-A		240
1244+50.00 to 1245+50.00	LT	1-A		100
1243+80.00 to 1246+20.00	CL	1-A		240
Bridge over Little Wabash River				
1276+75.00 to 1285+55.00	CL	1-D, 2-E		880
Detour 1				
1248+50.00 to 1250+00.00	LT	1-B		150
1249+00.00 to 1250+00.00	RT	1-B		100
1255+00.00 to 1261+00.00	RT	1-B		600
1260+00.00 to 1263+00.00	LT	1-B		300
TOTAL				3640

TEMPORARY PAVEMENT MARKING - LINE 4"			
LOCATION		TYPE	FOOT
Detour 1			
1100+00.00 to 1141+57		white solid yellow	4283 4283
Stage Const Box Culvert Sta 1158+80.50			
LT - Stage 1-A (Phase 1)			
1157+89.00 to 1159+76.00		solid yellow	187
1157+21.00 to 1160+41.00		white	320
RT - Stage 1-A (Phase 2)			
1158+01.00 to 1159+58.00		solid yellow	157
1157+21.00 to 1160+41.00		white	320
Stage Const Box Culvert Sta 1204+41			
LT - Stage 1-A (Phase 1)			
1203+88.00 to 1205+28.00		solid yellow	140
1202+14.00 to 1206+68.00		white	454
RT - Stage 1-A (Phase 2)			
1203+88.00 to 1205+28.00		solid yellow	140
1202+14.00 to 1206+68.00		white	454
Stage Const Box Culvert Sta 1221+20			
LT - Stage 1-A (Phase 1)			
1220+23.00 to 1222+18.00		solid yellow	195
1218+95.00 to 1223+45.00		white	450
RT - Stage 1-A (Phase 2)			
1220+71.00 to 1221+68.00		solid yellow	97
1218+95.00 to 1223+45.00		white	450
RT - Stage 1-A (Phase 4) Sta 1221+37			
1220+59.00 to 1221+82.00		solid yellow	123
1218+95.00 to 1223+45.00		white	450
Stage Const Box Culvert Sta 1245+00			
LT - Stage 1-A (Phase 1)			
1244+03.00 to 1245+98.00		solid yellow	195
1242+75.00 to 1247+25.00		white	450
RT - Stage 1-A (Phase 2)			
1244+51.00 to 1245+48.00		solid yellow	97
1242+75.00 to 1247+25.00		white	450
RT - Stage 1-A (Phase 4) Sta 1245+12.30			
1244+39.00 to 1245+62.00		solid yellow	123
1242+75.00 to 1247+25.00		white	450
Bridge over Little Wabash River			
1276+75.00 to 1287+55.00		solid yellow	1080
1276+75.00 to 1285+55.00		white	880
1274+75.00 to 1285+55.00		solid yellow	1080
1276+75.00 to 1285+55.00		white	880
TOTAL			18188

RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)			
U.S. 45			Foot
Stage 1-A (Phase 2) Sta 1158+80.50			
1157+60.00 to 1160+00.00	CL		240
Stage 1-A (Phase 2) Sta 1204+41			
1203+21.00 to 1205+61.00	CL		240
Stage 1-A (Phase 2) Sta 1221+20			
1220+30.00 to 1222+10.00	CL		180
1220+70.00 to 1221+70.00	RT		100
Stage 1-A (Phase 4) Sta 1221+37			
1220+30.00 to 1222+10.00	CL		180
1244+50.00 to 1245+50.00	RT		100
Stage 1-A (Phase 2) Sta 1245+00			
1244+10.00 to 1245+90.00	CL		180
1244+50.00 to 1245+50.00	RT		100
Stage 1-A (Phase 4) Sta 1245+12			
1244+00.00 to 1246+00.00	CL		200
Bridge over Little Wabash River			
1276+75.00 to 1285+55.00	CL		880
Detour 1			
1252+75.00 to 1254+45.00	RT		170
TOTAL			2470

WORK ZONE PAVEMENT MARKING REMOVAL			
LOCATION		WIDTH	SQ FT
Stage Const Box Culvert Sta 1158+80.5			
LT - Stage 1-A (Phase 1)			
1157+89.00 to 1159+76.00 CL		4	62
1157+21.00 to 1160+41.00 LT SIDE		4	107
RT - Stage 1-A (Phase 2)			
1158+01.00 to 1159+58.00 CL		4	52
1157+21.00 to 1160+41.00 RT SIDE		4	107
Stage Const Box Culvert Sta 1204+41			
LT - Stage 1-A (Phase 1)			
1203+88.00 to 1205+28.00 CL		4	47
1202+14.00 to 1206+68.00 LT SIDE		4	151
RT - Stage 1-A (Phase 2)			
1203+88.00 to 1205+28.00 CL		4	47
1202+14.00 to 1206+68.00 RT SIDE		4	151
Stage Const Box Culvert Sta 1221+20			
LT - Stage 1-A (Phase 1)			
1220+23.00 to 1222+18.00 CL		4	65
1218+95.00 to 1223+45.00 LT SIDE		4	150
RT - Stage 1-A (Phase 3) Sta 1221+37			
1220+71.00 to 1221+68.00 CL		4	32
1218+95.00 to 1223+45.00 RT SIDE		4	150
RT - Stage 1-A (Phase 4) Sta 1221+37			
1220+59.00 to 1221+82.00 CL		4	41
1218+95.00 to 1223+45.00 RT SIDE		4	150
Stage Const Box Culvert Sta 1245+00			
LT - Stage 1-A (Phase 1)			
1244+03.00 to 1245+98.00 CL		4	65
1242+75.00 to 1247+25.00 LT SIDE		4	150
RT - Stage 1-A (Phase 3) Sta 1245+12.30			
1244+51.00 to 1245+48.00 CL		4	32
1242+75.00 to 1247+25.00 RT SIDE		4	150
RT - Stage 1-A (Phase 4) Sta 1245+12.30			
1244+39.00 to 1245+62.00 CL		4	41
1242+75.00 to 1247+25.00 RT SIDE		4	150
Bridge over Little Wabash River			
1274+75.00 to 1277+35.00 CL		4	22
1284+95.00 to 1287+55.00 CL		4	22
1276+75.00 to 1285+55.00 RT SIDE		4	294
1276+75.00 to 1285+55.00 LT SIDE		4	294
TOTAL			2532

PAINT PAVEMENT MARKING - LINE 4"		
LOCATION	TYPE	FOOT
1143+00.00 to 1311+50.00	solid white	33700
	yellow 10' spaced @ 30'	4200
1200+00.00 to 1286+00.00	solid yellow	8600
TOTAL		46500

RAISED REFLECTIVE PAVEMENT MARKER		
U.S. 45		EACH
1143+00.00 to 1311+50.00		211
TOTAL		211

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE NARROW), TEST LEVEL 3		
LOCATION		EACH
US 45		
1255+00.00 Lt		1
1259+00.00 Lt		1
Stage Construction of Culverts		
1158+30.00 Lt		1
1158+80.00 Lt		1
1157+60.00 Cl		1
1160+00.00 Cl		1
1203+21.00 Cl		1
1205+61.00 Cl		1
1220+70.00 Lt		1
1221+71.00 Lt		1
1220+00.00 Cl		1
1222+40.00 Cl		1
1244+50.00 Lt		1
1245+50.00 Lt		1
1243+80.00 Cl		1
1246+20.00 Cl		1
Bridge over Little Wabash River		
1276+95.00 Cl		1
1285+35.00 Cl		1
Detour 1		
1248+50.00 Lt		1
1250+00.00 Lt		1
1249+00.00 Rt		1
1250+00.00 Rt		1
1255+00.00 Rt		1
1261+00.00 Rt		1
1260+00.00 Lt		1
1263+00.00 Lt		1
Total		26

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3		
LOCATION		EACH
Stage Construction of Culverts		
1157+34.00 Cl		1
1160+00.00 Cl		1
1203+21.00 Cl		1
1205+61.00 Cl		1
1220+30.00 Cl		1
1222+10.00 Cl		1
1220+70.00 Rt		1
1221+70.00 Rt		1
1220+30.00 Cl		1
1222+10.00 Cl		1
1244+10.00 Cl		1
1245+90.00 Cl		1
1244+50.00 Rt		1
1245+50.00 Rt		1
1244+10.00 Cl		1
1246+00.00 Cl		1
Bridge over Little Wabash River		
1276+95.00 Cl		1
1285+35.00 Cl		1
Detour Road		
1252+75.00 Rt		1
1254+45.00 Rt		1
Total		20

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE: 10-21-05 DRAWN BY: IJ CHECKED BY: MAR

Rev.