CONTRACT NO. 74142

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	97-3B-1-2	WHITE	15	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE SFTY-2A 50% STATE 50% INDIANA
	X0325212	DEBRIS REMOVAL (SPECIAL)	CAL DA	20	20
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	270	270
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	200	200
	28100809	STONE DUMPED RIPRAP, CLASS A5	TON	5050	5050
	28100811	STONE DUMPED RIPRAP, CLASS A6	TON	2400	2400
	50200300	COFFERDAM EXCAVATION	CU YD	360	360
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8
	67100100	MOBILIZATION	L SUM	1	1
*	A2002316	TREE, BETULA NIGRA (RIVER BIRCH), 2" CALIPER, BALLED AND BURLAPPED	EACH	14	14
*	A2005816	TREE, PLATANUS OCCIDENTALIS (SYCAMORE), 2" CALIPER, BALLED AND BURLAPPED	EACH	14	14
*	A2007616	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2" CALIPER, BALLED AND BURLAPPED	EACH	14	14
	X5121800	PERMANENT STEEL SHEET PILING	SQ FT	10430	10430
	Z0015500	DEBRIS REMOVAL	L SUM	1	1

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DRAWN BY

DATE

CHECKED BY

PLOT DATE = 12/2/2025
FILE NAME = o:\projects\74142\d81586pa.dgn
PLOT SCALE = 58.0000 ' / IN.
USER NAME = swarters