COUNTY HIGHWAY	FISCAL YEAR	TOTAL SHEETS	SHEET NO.
	2005	30	4
SEC 03-00001-06-BT			DUPAGE COUNTY

CONTRACT NO.: 83805

TREE REMOVAL

STATION	OFFSET	6 - 15 UNITS		STATION	OFFSET	6 - 15 UNITS
1+57	20' LT	8"		14+43	2' RT	6"
1+98	17' LT	8"		14+55	15' RT	7"
5+27	11' RT	7"		15+13	13' RT	6"
5+36	2' LT	11"		15+89	1' RT	6"
8+12	15' RT	11"		16+15	13' RT	8"
8+28	5' LT	7"		17+99	13' RT	11"
8+33	7' LT	9"		19+08	15' RT	8"
8+52	9' LT	9"		19+68	15' RT	8"
9+03	14' RT	12"		20+17	3' LT	6"
9+16	5' LT	6"		20+41	7' RT	8"
9+56	15' RT	9"		23+19	8' LT	6"
9+79	3' RT	9"		23+26	17' RT	9"
10+17	5' RT	13"		23+54	7' LT	9"
10+49	21' RT	13"		26+54	15' RT	6"
11+38	15' RT	8"		27+45	14' RT	8"
12+11	7' RT	7"		27+67	1' RT	11"
13+07	5' RT	6"		28+35	5' LT	11"
13+32	15' RT	13"		31+06	18' RT	9"
13+88	11' RT	6"		39+95	7' LT	15"
					TOTAL	330 UNITS

EROSION CONTROL

STATION	OFFSET	TEMPORARY DITCH CHECKS 28000300	INLET & PIPE PROTECTION 28000500	STATION	OFFSET	TEMPORARY DITCH CHECKS 28000300	INLET & PIPE PROTECTION 28000500
5+01	23' RT	1		35+99	29' RT	1	
5+77	21' RT	1		37+55	30' RT	1	
6+53	20' RT	1		39+00	30' RT	1	
7+23	23' RT	1		2+31	16' RT		1
7+99	25' RT	1		4+62	22' RT		1
8+77	27' RT	1		4+39	19' RT		1
9+55	29' RT	1		8+51	7' LT		1
10+24	32' RT	1		10+04	6' LT		1
13+00	28' RT	1		10+75	34' RT		1
14+59	27' RT	1		23+19	8' LT		1
16+77	26' RT	1		24+18	27' RT		1
26+99	27' RT	1		25+71	27' RT		1
28+38	18' RT	1		36+72	10' LT		1
29+99	21' RT	1		40+17	6' LT		1
31+56	27' RT	1		41+08	22' RT		1
33+00	27' RT	1		41+45	6' LT		1
34+54	28' RT	1					
					TOTALS	20	13

FENCE

STATION	OFFSET	CHAIN LINK FENCE, 6' 66400305	CHAIN LINK FENCE REMOVAL 66410300
14+25	11' LT	20'	40'
33+07	15' LT	20'	40'
	TOTALS	40'	80'

DRAINAGE

STATION	OFFSET	TRENCH BACKFILL 20800150	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12" 54213657	STORM SEWERS, CLASS A, TYPE 1 12" (FT) 550A0050	STORM SEWERS, CLASS A, TYPE 1 15" (FT) 550A0070	STORM SEWERS, CLASS A, TYPE 2 12" (FT) 550A0340	STORM SEWERS, CLASS A, TYPE 2 36" (FT) 550A0450	STORM SEWER REMOVAL 12" (FT) 55100500	STORM SEWER REMOVAL 15" (FT) 55100700	MANHOLES, TYPE A 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID 60221100	MANHOLES, TYPE A 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID 60223800	CATCH BASINS TO BE ADJUSTED 60250200	CATCH BASINS TO BE RECONSTRUCTED 60252800	CATCH BASINS TO BE CLEANED 60255410	PLUG EXISTING STORM SEWER Z0041700	REMOVE AND REINSTALL EXISTING PRECAST REINFORCED CONCRETE FLARED END SECTIONS XX003437
2+38	5' RT	18.20				25										
8+51	10' RT	5.04		26												
10+04	12.5' RT	5.63		29												
23+20	11' RT	10.91				32										
40+11	2' RT	10.92		15				15								
28+50	12' RT	2.14			7				6							
2+36	8.5' LT	15.08					10									
8+51	7' LT		1													
8+51	26' RT		1													
10+04	6' LT		1													
10+04	30.5' RT		1													
23+20	8' LT		1													
2+44	8' LT									1						
23+21	30.5' RT										1					
28+50	6' RT											1		1		
33+41	10' RT											1		1		
36+91	15' RT											1		1		
29+89	10' RT												1	1		
40+05	9' RT												1	1		
2+29	10' RT														2	
28+50	19' RT															1
	TOTALS	68	5	70	7	57	10	15	6	1	1	3	2	5	2	1

	REM & DISP OF UNSUITABLE MATERIAL (PGES) (CU YD)	REM & DISP OF UNSUITABLE MATERIAL (TOPSOIL) (CU YD)	EARTH EXCAVATION (CU YD)	STORM SEWER EXCAVATION (CU YD)	TOTAL SUITABLE EXCAVATION (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ FOR 15% SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE -) (CU YD)
1+00 TO 10+00	0	416	573	38	611	519	226	+293
10+00 TO 20+00	0	388	617	6	623	530	48	+482
20+00 TO 30+00	0	435	734	13	747	635	91	+544
30+00 TO 41+57.13	0	503	885	11	896	762	188	+574
TOTALS	0	1,742	2,809	68	2,877	2,445	553	+1,892

NO.	DATE	BY	REVISION	NO.	DATE	BY	REVISION

SCALE
DRAWN BY JMC DATE
CHECKED BY MRH DATE
APPROVED BY DWB DATE

RJN GROUP

RJN GROUP, INC.
CONSULTING ENGINEERS

PROJECT
Southern DuPage County Regional Trail
101st Street Connector – Waterfall Glen Spur

TITLE
SCHEDULES

DATE: JUNE 9, 2005
PROJECT No.: II-1900-01
SHEET:

11/17/2005 2:53:00 PM K:\II9000\cadd\Design\180L_schedule.dgn