

SUMMARY OF QUANTITIES		SAFETY CODE		2A	1E	1F
ITEM NO.	DESCRIPTION	CONSTRUCTION CODE		J000	Y030	Y031
		UNIT	TOTAL QUANTITY	ROADWAY 50% FEDERAL 25% CITY 25% COUNTY	ROADWAY LIGHTING 50% FEDERAL 25% CITY 25% COUNTY	TRAFFIC SIGNALS 50% FEDERAL 25% CITY 25% COUNTY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	380	380		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	480	480		
20200100	EARTH EXCAVATION	CU YD	44,790	44,790		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3,705	3,705		
20800250	TRENCH BACKFILL (SPECIAL)	CU YD	2,007	2,007		
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	5,430	5,430		
21301084	EXPLORATION TRENCH 84" DEPTH	FOOT	630	630		
25000200	SEEDING, CLASS 2	ACRE	3.7	3.7		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	981	981		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	981	981		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	981	981		
25000900	SEEDING, CLASS 1 (SPECIAL)	ACRE	7.2	7.2		
25100115	MULCH, METHOD 2	ACRE	3.7	3.7		
25200100	SODDING	SQ YD	1366	1366		
25200200	SUPPLEMENTAL WATERING	UNIT	866	866		
25301000	TREES TO BE TRANSPLANTED 2"	EACH	5	5		
25301400	TREES TO BE TRANSPLANTED 4-4 1/2"	EACH	11	11		
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	10.9	10.9		
28000300	TEMPORARY DITCH CHECKS	EACH	28	28		
28000400	PERIMETER EROSION BARRIER	FOOT	2,915	2,915		
28000500	INLET AND PIPE PROTECTION	EACH	21	21		
28000510	INLET FILTERS	EACH	86	86		
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	37,121	37,121		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2,683	2,683		
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	1,656	1,656		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	30	30		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,620	2,620		
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	90	90		
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	31,488	31,488		
42001300	PROTECTIVE COAT	SQ YD	34,686	34,686		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1,021	1,021		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	607	607		

\*SEE SPECIAL PROVISIONS  
 Δ SPECIALTY ITEMS

SUMMARY OF QUANTITIES		SAFETY CODE		2A	1E	1F
ITEM NO.	DESCRIPTION	CONSTRUCTION CODE		J000	Y030	Y031
		UNIT	TOTAL QUANTITY	ROADWAY 50% FEDERAL 25% CITY 25% COUNTY	ROADWAY LIGHTING 50% FEDERAL 25% CITY 25% COUNTY	TRAFFIC SIGNALS 50% FEDERAL 25% CITY 25% COUNTY
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	59,844	59,844		
44000100	PAVEMENT REMOVAL	SQ YD	18,509	18,509		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,404	1,404		
44000600	SIDEWALK REMOVAL	SQ FT	5,851	5,851		
44200101	PAVEMENT PATCHING, TYPE IV, 8 INCH	SQ YD	50	50		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	48	48		
48202300	BITUMINOUS SHOULDERS SUPERPAVE 5"	SQ YD	2,569	2,569		
50102600	CONCRETE REMOVAL	EACH	2	2		
50105210	REMOVE EXISTING CULVERTS	FOOT	1,386	1,386		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1		
54223249	PIPE CULVERTS, SALVAGED PIPE 24"	FOOT	97	97		
54247100	GRATING FOR CONCRETE FLARED END SECTION 15"	EACH	1	1		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	2,013	2,013		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	418	418		
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	218	218		
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	263	263		
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	324	324		
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	238	238		
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	240	240		
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	964	964		
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	8	8		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	181	181		
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	133	133		
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	631	631		
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	453	453		
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	48	48		
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	475	475		
550B0120	STORM SEWERS, CLASS B, TYPE 1 24"	FOOT	631	631		
60100915	PIPE DRAINS 6"	FOOT	275	275		
60107700	PIPE UNDERDRAINS 6"	FOOT	5,481	5,481		

\*SEE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES