

SCHEDULE OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
B07	00-00374-00-PV	CHAMPAIGN	149	9
STA.	TO STA.			
FED. ROAD DIST. NO. 7		ILLINOIS	F.A. PROJECT M-5181(38)	

CONTRACT NO. 91308

SUB-BASE GRANULAR MATERIAL, TYPE A 12" ITEM NO. 31100910

STATION	TO STATION	SQ YD
STAGE 1 - DUNCAN ROAD		
114+00.0 RT.	124+84.27 RT.	2,288.3
114+00.0 LT.	124+84.27 LT.	1,803.3
80+22.9 RT.	81+16.1 RT.	160.1
80+22.9 LT.	81+16.1 LT.	137.2
90+22.9 RT.	90+97.1 RT.	116.2
90+22.9 LT.	90+97.1 LT.	141.9
STAGE 1 SUBTOTAL		4,647.0
STAGE 2 - DUNCAN ROAD & CURTIS ROAD		
124+84.27 RT.	127+86.1 RT.	1,186.1
124+84.27 LT.	127+86.1 LT.	870.1
128+54.3 RT.	140+66.0 RT.	2,650.1
128+54.3 LT.	140+66.0 LT.	2,729.1
30+95.0 RT.	47+20.0 RT.	6,146.3
30+95.0 LT.	47+20.0 LT.	6,146.3
198+83.2 RT.	199+65.9 RT.	168.0
198+83.2 LT.	199+65.9 LT.	165.0
300+34.1 RT.	302+00.2 RT.	466.0
300+34.1 LT.	302+00.2 LT.	479.3
STAGE 2 SUBTOTAL		21,006.30
STAGE 3 - CURTIS ROAD		
47+20.0 RT.	61+00.0 RT.	5,226.6
47+20.0 LT.	61+00.0 LT.	5,224.6
61+00.0	61+00.0	75.7
398+83.8 LT.	399+65.9 LT.	164.9
398+83.8 RT.	399+65.9 RT.	163.3
500+34.1 LT.	501+38.8 LT.	306.8
500+34.1 RT.	501+38.8 RT.	306.0
STAGE 3 SUBTOTAL		11,467.3
TOTAL		37,121

SUB-BASE GRANULAR MATERIAL, TYPE B 4" ITEM NO. 31101200

STATION	TO STATION	SQ YD
STAGE 1 - DUNCAN ROAD		
114+00.0 LT.	124+84.27 LT.	742.6
(OMIT 119+83.1 P.E., 120+93.9 P.E., 124+14.8 C.E.)		
90+77.1 LT.	90+97.1 LT.	10.0
STAGE 1 SUBTOTAL		752.6
STAGE 2 - DUNCAN ROAD & CURTIS ROAD		
124+84.27 LT.	127+01.8 LT.	187.9
130+75.7 LT.	140+66.0 LT.	111.2
134+35.6 RT.	141+00.6 RT.	109.5
31+00.0 RT.	32+06.3 RT.	896.5
31+00.0 LT.	32+05.9 LT.	625.1
STAGE 2 SUBTOTAL		1,930.2
STAGE 3 - CURTIS ROAD		
STAGE 3 SUBTOTAL		0
TOTAL		2,683

AGGREGATE BASE COURSE, TYPE A 8" ITEM NO. 35100700

STATION	TO STATION	SQ YD
STAGE 1 - DUNCAN ROAD		
STAGE 1 SUBTOTAL		0
STAGE 2 - DUNCAN ROAD & CURTIS ROAD		
STAGE 2 SUBTOTAL		0
STAGE 3 - CURTIS ROAD		
61+00.0	66+00.0	1,656
STAGE 3 SUBTOTAL		1,656
TOTAL		1,656

AGGREGATE SURFACE COURSE, TYPE B ITEM NO. 40200800

LOCATION	SQ YD
STAGE 1 - DUNCAN ROAD	
STAGE 1 SUBTOTAL	0
STAGE 2 - DUNCAN ROAD & CURTIS ROAD	
35+21.8 RT. (P.E.)	9.3
STAGE 2 SUBTOTAL	9.3
STAGE 3 - CURTIS ROAD	
62+50.0 RT. (F.E.)	20.5
STAGE 3 SUBTOTAL	20.5
TOTAL	30

INCIDENTAL BITUMINOUS SURFACING (8" THICK) ITEM NO. 40800040

LOCATION	TON
STAGE 1 - DUNCAN ROAD	
STAGE 1 SUBTOTAL	0
STAGE 2 - DUNCAN ROAD & CURTIS ROAD (PARKING LOT)	
46+42.3 LT.	37
STAGE 2 SUBTOTAL	37
STAGE 3 - CURTIS ROAD (PARKING LOT)	
47+89.0 LT.	53
STAGE 3 SUBTOTAL	53
TOTAL	90

PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED) ITEM NO. 42000401

STATION	TO STATION	SQ YD
STAGE 1 - DUNCAN ROAD		
114+84.00 RT.	117+54.00 RT.	360.0
117+54.00 RT.	121+74.57 RT.	684.2
121+74.57 RT.	124+07.00 RT.	464.5
124+07.00 RT.	124+84.27 RT.	178.0
114+84.00 LT.	120+69.02 LT.	779.9
120+69.02 LT.	123+76.33 LT.	510.1
123+76.33 LT.	124+84.27 LT.	215.9
SOUTH ROLLING ACRES DRIVE RT.		90.8
SOUTH ROLLING ACRES DRIVE LT.		69.4
NORTH ROLLING ACRES DRIVE RT.		85.3
NORTH ROLLING ACRES DRIVE LT.		97.6
STAGE 1 SUBTOTAL		3,535.7
STAGE 2 - DUNCAN ROAD & CURTIS ROAD		
124+84.27 RT.	125+77.00 RT.	275.4
125+77.00 RT.	127+28.49 RT.	505.0
127+28.49 RT.	127+90.19 RT.	294.4
124+84.27 LT.	126+49.03 LT.	329.5
126+49.03 LT.	127+90.19 LT.	487.3
128+50.20 RT.	129+90.87 RT.	470.2
129+90.87 RT.	134+29.20 RT.	876.2
134+29.20 RT.	137+76.36 RT.	566.7
137+76.36 RT.	139+66.00 RT.	252.9
128+50.20 LT.	129+11.83 LT.	299.2
129+11.83 LT.	130+53.00 LT.	470.6
130+53.00 LT.	132+52.91 LT.	533.1
132+52.91 LT.	135+53.18 LT.	499.8
135+53.18 LT.	139+66.00 LT.	550.1
31+00.00 RT.	47+20.00 RT.	5,400.4
31+00.00 LT.	47+20.00 LT.	5,399.6
MARJORIE LANE LT.		77.6
MARJORIE LANE RT.		80.5
CHERRY HILLS DRIVE LT. (UNDIVIDED)		117.0
CHERRY HILLS DRIVE RT. (UNDIVIDED)		243.7
CHERRY HILLS DRIVE LT. (UNDIVIDED)		117.0
CHERRY HILLS DRIVE RT. (UNDIVIDED)		252.7
STAGE 2 SUBTOTAL		18,098.9
STAGE 3 - CURTIS ROAD		
47+20.00 RT.	61+00.00 RT.	4,600.8
47+20.00 LT.	61+00.00 LT.	4,599.2
MEADOW LANE LT.		79.0
MEADOW LANE RT.		77.1
WYNSTONE DRIVE LT. (UNDIVIDED)		119.2
WYNSTONE DRIVE RT. (UNDIVIDED)		129.8
WYNSTONE DRIVE LT. (UNDIVIDED)		118.5
WYNSTONE DRIVE RT. (UNDIVIDED)		129.2
STAGE 3 SUBTOTAL		9,852.8
TOTAL		31,488

BITUMINOUS SHOULDERS SUPERPAVE, 5" ITEM NO. 48202300

STATION	TO STATION	SQ YD
STAGE 1 - DUNCAN ROAD		
114+00.0 LT.	124+84.27 LT.	712.5
(OMIT 119+83.1 P.E., 120+93.9 P.E., 124+14.8 C.E.)		
90+77.1 LT.	90+97.1 LT.	9.1
STAGE 1 SUBTOTAL		721.6
STAGE 2 - DUNCAN ROAD & CURTIS ROAD		
124+84.27 RT	127+01.8 LT.	182.9
130+75.7 LT.	140+66.0 LT.	850.7
134+35.6 RT.	141+00.6 RT.	592.5
31+00.0 RT.	32+06.3 RT.	111.2
31+00.0 LT.	32+05.9 LT.	109.5
STAGE 2 SUBTOTAL		1846.8
STAGE 3 - CURTIS ROAD		
STAGE 3 SUBTOTAL		0
TOTAL		2,569

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH ITEM NO. 42300200

LOCATION	SQ YD
STAGE 1 - DUNCAN ROAD	
119+83.1 RT. - P.E.	185.2
120+93.9 LT. - P.E.	98.5
124+45.6 RT. - P.E.	18.8
124+45.6 RT. - P.E.	99.5
STAGE 1 SUBTOTAL	402.0
STAGE 2 - DUNCAN ROAD & CURTIS ROAD	
125+51.1 RT. - P.E.	19.8
125+51.1 RT. - P.E.	37.3
134+23.3 RT. - P.E.	19.3
34+23.3 RT. - P.E.	48.9
35+21.8 RT. - P.E.	18.7
35+21.8 RT. - P.E.	5.7
36+29.2 RT. - P.E.	14.3
36+29.2 RT. - P.E.	27.6
37+56.8 RT. - P.E.	14.4
37+56.8 RT. - P.E.	22.8
38+96.6 RT. - P.E.	14.3
38+96.6 RT. - P.E.	23.6
42+93.8 RT. - P.E.	14.4
42+93.8 RT. - P.E.	22.0
44+01.3 RT. - P.E.	15.9
44+01.3 RT. - P.E.	33.1
45+88.6 RT. - P.E.	14.3
45+88.6 RT. - P.E.	19.9
46+43.3 RT. - P.E.	17.6
46+43.3 RT. - P.E.	10.0
STAGE 2 SUBTOTAL	413.9
STAGE 3 - CURTIS ROAD	
47+84.2 RT. - P.E.	14.8
47+84.2 RT. - P.E.	16.0
51+87.1 RT. - P.E.	15.7
51+87.1 RT. - P.E.	30.0
53+52.1 RT. - P.E.	14.3
53+52.1 RT. - P.E.	28.9
54+83.9 RT. - P.E.	15.4
54+83.9 RT. - P.E.	30.8
57+13.2 RT. - P.E.	14.3
57+13.2 RT. - P.E.	24.5
STAGE 3 SUBTOTAL	204.7
TOTAL	1021

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH ITEM NO. 42300400

LOCATION	SQ YD
STAGE 1 - DUNCAN ROAD	
124+14.8 LT. - C.E.	446.8
STAGE 1 SUBTOTAL	446.8
STAGE 2 - DUNCAN ROAD & CURTIS ROAD	
36+67.3 LT. - C.E.	21.0
46+42.3 LT. - C.E.	13.9
46+42.3 LT. - C.E.	11.7
132+05.4 RT. - C.E.	86.1
STAGE 2 SUBTOTAL	132.7
STAGE 3 - CURTIS ROAD	
47+89.0 LT. - C.E.	14.6
47+89.0 LT. - C.E.	12.7
STAGE 3 SUBTOTAL	27.3
TOTAL	607

PORTLAND CEMENT CONCRETE SIDEWALK, 6" ITEM NO. 42400300

STATION	TO STATION	SQ FT
STAGE 1 - DUNCAN ROAD		
112+67.6 RT	114+84.0 RT	1,091.3
114+84.0 RT	121+95.8 RT	3,549.2
122+85.7 RT	124+84.27 RT	973.9
124+33.2 RT.		16.8
STAGE 1 SUBTOTAL		5,631.2
STAGE 2 - DUNCAN ROAD & CURTIS ROAD		
124+84.27 RT	127+50.7 RT	1,348.2
128+64.5 LT	130+93.1 LT	2,055.2
128+66.8 RT	134+50 RT	4,561.4
139+45.7 RT	139+84.8 RT	158.9
32+07.1 RT	32+35.1 RT	307.2
33+08.4 LT	41+51.24 LT	6,990.2
33+10.1 RT	40+40.3 RT	5,930.3
40+82.1 RT	47+20.0 RT	5,087.6
42+09.4 LT	47+20.0 LT	4,039.3
46+75.2 LT	46+79.3 LT	62.2
CHERRY HILLS DRIVE LT		758.8
CHERRY HILLS DRIVE RT		803.7
STAGE 2 SUBTOTAL		32,103.0
STAGE 3 - CURTIS ROAD		
47+20.0 LT	59+45.5 LT	9,781.9
47+20.0 RT	49+77.1 RT	2,042.8
50+18.9 RT	61+00.0 RT	8,617.9
60+04.3 LT	61+00.0 LT	734.8
WYNSTONE DRIVE LT		465.3
WYNSTONE DRIVE RT		466.9
STAGE 3 SUBTOTAL		22,109.6
TOTAL		59,844

PAVEMENT PATCHING, TYPE IV, 8" ITEM NO. 44200101

LOCATION	SQ YD
STAGE 1 - DUNCAN ROAD	
STAGE 1 SUBTOTAL	0
STAGE 2 - DUNCAN ROAD & CURTIS ROAD	
STAGE 2 SUBTOTAL	0
STAGE 3 - CURTIS ROAD	
72+23.9 LT.	49.1
STAGE 3 SUBTOTAL	49.1
TOTAL	50

AGGREGATE SHOULDERS, TYPE B (4" THICK) ITEM NO. 48101200

STATION	TO STATION	TON
STAGE 1 - DUNCAN ROAD		
STAGE 1 SUBTOTAL		0
STAGE 2 - DUNCAN ROAD & CURTIS ROAD		
STAGE 2 SUBTOTAL		0
STAGE 3 - CURTIS ROAD		
61+00.0 RT.	66+00.0 RT.	22.5
(OMIT 62+50, F.E.)		
61+00.0 LT.	66+00.0 LT.	25.4
STAGE 3 SUBTOTAL		47.9
TOTAL		48

FOR ADDITIONAL SCHEDULES OF QUANTITIES AND BILL OF MATERIALS SEE THE STAGE CONSTRUCTION AND MAINTENANCE OF TRAFFIC PLANS, REMOVALS/RELOCATIONS PLANS, PLAN AND PROFILE SHEETS, PAVEMENT MARKING PLANS, ROADWAY LIGHTING PLANS, TRAFFIC SIGNAL PLANS, AND TREE PLANTING PLANS.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DATE : 8-05
DRAWN BY : S.M.W.
CHECKED BY : R.L.H.