

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	16 A
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE		TRAFFIC SIGNS	HIGHWAY LIGHTING	IMPACT ATTENUATORS
				80% FEDERAL 10% STATE 10% LOCAL J000-2A		STA. 247+85.29 TO STA. 250+65.29				
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	2					2		
73700200	REMOVE CONCRETE FOUNDATION-GROUND MOUNT	EACH	2					2		
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14864		14,864					
△ 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	320		320					
△ 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	40709		40,709					
△ 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	1594		1,594					
△ 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	951		951					
△ 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	72		72					
△ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	123		123					
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	32		32					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	5		5					
78300400	THERMOPLASTIC PAVEMENT MARKING REMOVAL	SQ FT	1039		1,039					
△ 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1						1	
△ 81014600	CONDUIT TRENCHED 2" DIA. INTERMEDIATE METAL	FOOT	193						193	
△ 81014800	CONDUIT TRENCHED 3" DIA. INTERMEDIATE METAL	FOOT	80						80	
△ 81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	150						150	
△ 81500200	TRENCH AND BACKFILL FOR ELECTRIC WORK	FOOT	5600						5,600	
△ 81600315	UNIT DUCT, 2 *6 XLP, 1 *6 XLP GROUND 1" POLYETHYLENE	FOOT	5992						5,992	
△ 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	10						10	
△ 82500520	LIGHT CONTROLLER PEDESTAL MOUNT CB-RCS 60 AMP-480 VOLT	EACH	1						1	
△ * 83052600	LIGHT POLE, FIBERGLASS ANCHOR BASE, 45 FT. M.H., TENON MOUNT	EACH	6						6	
△ * 83052800	LIGHT POLE, FIBERGLASS ANCHOR BASE, 45 FT. M.H., TENON MOUNT, TWIN	EACH	2						2	
△ 83600355	LIGHT POLE FOUNDATION METAL, 15 BOLT CIRCLE, 8" X 6'	EACH	6						6	
△ 83600357	LIGHT POLE FOUNDATION METAL, 15 BOLT CIRCLE, 8" X 8'	EACH	2						2	
△ 83800650	BREAKAWAY DEVICE COUPLING, WITH STAINLESS STEEL SCREEN	EACH	32						32	
△ F30180Y2	SEEDLING - TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2 YEAR-OLD, BARE ROOT	UNIT	1.1		1.1					
△ G20050Y2	SEEDLING - CORNUS SERICEA (RED-OSIER DOGWOOD), 2 YEAR-OLD, BARE ROOT	UNIT	202		20.2					
* XZ193300	SURVEY MARKER, TYPE 1 (SPECIAL)	EACH	6		6					
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	194		194					

- SEE SPECIAL PROVISIONS
- QUANTITY PARTIALLY OR WHOLLY ASSUMED FOR ESTABLISHMENT OF UNIT PRICE

△ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAI-57, FAS 642
 SEC NO. 15-23K, 99-00124-02-PV
 COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE
 DATE 11/10/2005
 DRAWN BY KET
 CHECKED BY SKM



11/10/2005
 KET 05/24/05
 SKM 05/26/05
 SKM 05/27/05
 INST: J05557r a2028b0VW1S1wVc-606_02sum.dgn